

NOWPAP CEARAC

Northwest Pacific Action Plan
Special Monitoring and Coastal Environmental Assessment
Regional Activity Centre



5-5 Ushijimashin-machi, Toyama City, Toyama 930-0856, Japan
Tel: +81-76-445-1571, Fax: +81-76-445-1581
Email: webmaster@cearac.nowpap.org
Website: <http://cearac.nowpap.org/>

Integrated Report on Harmful Algal Blooms for the NOWPAP Region



CEARAC Report 2011



published in 2011

by the NOWPAP Special Monitoring and Coastal Environmental Assessment
Regional Activity Centre (NOWPAP CEARAC)

established at the Northwest Pacific Region Environmental Cooperation Center (NPEC)
5-5 Ushijimashin-machi, Toyama City, Toyama 930-0856, Japan

Tel: +81-76-445-1571, Fax: +81-76-445-1581

E-mail: webmaster@cearac.nowpap.org

Website: <http://cearac.nowpap.org/>

Copyright© NOWPAP CEARAC 2011

For bibliographical purposes, this document may be cited as:

NOWPAP CEARAC 2011

Integrated Report on Harmful Algal Blooms for the NOWPAP Region

ISBN 978-4-9902809-3-2

Preface

As part of the Regional Seas Programme of the United Nations Environment Programme (UNEP), the Northwest Pacific Action Plan (NOWPAP) was adopted in September 1994 by the People's Republic of China, Japan, the Republic of Korea and the Russian Federation. There are four Regional Activity Centres (RACs) responsible for carrying out individual NOWPAP activities and projects approved by the Intergovernmental Meeting.

In 1999, the Special Monitoring and Coastal Environmental Assessment Regional Activity Centre (CEARAC) was established as a RAC. It is hosted by the Northwest Pacific Region Environmental Cooperation Center (NPEC), which was established in 1998 in Toyama, Japan, under the auspices of the Ministry of Environment in Japan. CEARAC is responsible for coordinating the regional assessment of the marine, coastal and associated freshwater environments and for developing tools for environmental planning and management based on these assessments. CEARAC has two working groups. Working Group 3 (WG3) is responsible for the monitoring and assessment of harmful algal blooms (HABs), and Working Group 4 (WG4) is responsible for the development of new monitoring tools using remote sensing techniques. In recent years, WG3 and WG4 have worked on a joint assessment of the eutrophication status of the NOWPAP region.

The 'Integrated Report on Harmful Algal Blooms for the NOWPAP Region' was first published in 2005 to provide information on the status of HABs in the region and to address issues identified by WG3.

Based on the suggestions in the Integrated Report, CEARAC developed the '*Cochlodinium* Home Page' (<http://www.cearac-project.org/wg3/cochlo-entrance/>), the 'HAB Reference Database' (http://www.cearac-project.org/HAB_Integrated_Website/database/index.html) and published the Booklet of 'Countermeasures against Harmful Algal Blooms'. In order to share information not only among the NOWPAP member states, but with other international organizations, CEARAC developed the common sheet through the 'HAB Case Study'. This common sheet was implemented over 2008 to 2009, in order to establish an effective and efficient method of sharing information.

Over the past five years, the HAB situation in the NOWPAP region has changed. Up to 5 years ago, blooms of *C. polykrikoides* occurred frequently and were a major issue in the region, particularly as they caused significant damage to fisheries. In the last few years, however, the number of *C. Polykrikoides* bloom has decreased, and other species, such as *Chattonella antiqua*, have caused greater damage. Macroalgal blooms have also become an issue in recent years.

Sharing the latest information on HABs in the region is useful for preventing and mitigating HAB damage. As such, CEARAC has begun to summarize its findings and updated the 'Integrated Report on Harmful Algal Blooms for the NOWPAP Region' based on the approval at the 8th NOWPAP CEARAC Focal Points Meeting (Toyama, Japan, 13-15 September 2010).

CEARAC expects this latest report to assist environmental managers and decision-makers to understand the current status of HABs in the region.

The CEARAC Secretariat would like to thank all of the CEARAC Focal Points and HAB Case Study Experts for their great contributions to this publication.

NOWPAP CEARAC Focal Points

Ms. Guihua DONG

Senior Engineer, Ecological Environmental Monitoring Department, China National Environmental Monitoring Center (CNEMC), China

Mr. Junlong LI

Engineer, Marine Monitoring Department, China National Environmental Monitoring Center (CNEMC), China

Mr. Koichi MIYAMOTO

Deputy Director, Office of Marine Environment, Water Environment Division, Environmental Management Bureau, Ministry of the Environment Japan

Dr. Yasuwo FUKUYO

Professor, Director of Asian Natural Environmental Science Center, The University of Tokyo, Japan

Dr. Joji ISHIZAKA

Professor, Hydropheric Atmospheric Research Center, Nagoya University, Japan

Dr. Changkyu LEE

Senior Scientist, Southeast Sea Fisheries Research Institute, National Fisheries Research and Development Institute, Korea

Dr. Leonid MITNIK

Head of Department, Satellite Oceanography, V.I. Il'ichev Pacific Oceanological Institute, Far Eastern Branch of the Russian Academy of Sciences, Russia

Dr. Vladimir SHULKIN

Head of Laboratory, Laboratory of Geochemistry, Pacific Geographical Institute, Far Eastern Branch of the Russian Academy of Sciences, Russia

HAB Case Study Experts

Dr. Zhiming YU

Professor, Chinese Academy of Science, Institute of Oceanology, China

Dr. Yang Soon Kang

Research Scientist, Marine Ecology Research Division, National Fisheries Research and Development Institute, Korea

Dr. Tatiana ORLOVA

Senior Scientist, Institute of Marine Biology, Far East Branch of Russian Academy of Science, Russia

Secretariat

Special Monitoring & Coastal Environmental Assessment Regional Activity Centre (CEARAC)

5-5 Ushijimashin-machi, Toyama City, Toyama 930-0856, Japan
TEL: +81-76-445-1571
FAX: +81-76-445-1581
URL: <http://cearac.nowpap.org/>

Table of contents

Preface

Executive Summary

1	Introduction	6
1.1	Past CEARAC's activities on HABs	6
1.2	Definitions	8
1.3	Natural environment of the NOWPAP region	9
1.3.1	Sea areas	10
1.3.2	Rivers	10
1.3.3	Major oceanographic currents in the NOWPAP region	11
1.4	Impacts on the marine environment in the NOWPAP region	12
1.4.1	Population	12
1.4.2	Nutrients inputs from land	13
1.4.3	Aquaculture	14
2	Information on HAB monitoring	15
2.1	Monitoring framework in the NOWPAP region	15
2.1.1	Monitoring of HAB and monitoring parameters in the NOWPAP member states	16
2.1.2	Monitoring of shellfish toxin	19
2.2	Common issues with monitoring activities in the NOWPAP region	19
2.3	Monitoring framework in target sea areas of the HAB Case Study	23
3	HAB occurrence in the NOWPAP region	27
3.1	Red-tide occurrences in the NOWPAP region	27
3.1.1	Red tides in China	32
3.1.2	Red tides in Japan	36
3.1.3	Red tides in Korea	45
3.1.4	Red tides in Russia	48
3.2	Toxin-producing plankton and shipment stoppage in the target sea areas	51
3.3	Common issues on HABs in the NOWPAP region	54
3.3.1	Severe fishery damage caused by <i>Cochlodinium polykrikoides</i>	54
3.3.2	Fishery damage caused by <i>Chattonella antiqua</i> in Yatsushiro Sea	54
3.3.3	Threats from PSP and DSP	58
3.3.4	The new issue by massive blooms of green macroalgae <i>Ulva prolifera</i>	58
4	Challenges for studies to cope with HABs	59
4.1	Remote sensing techniques	59
4.2	Molecular genetic techniques	60
5	Conclusion	62
References		63
Annex I: Acronyms and abbreviations		66
Annex II: Red tide events, toxin events and water quality information in the target sea areas		68

Executive Summary

The NOWPAP region has faced serious problems due to the frequent occurrence of HABs. This is due to increased nutrient inputs from land associated with economic development, and an increase in agricultural production in surrounding countries. Even though the number of HABs has decreased in recent years, due to the establishment of sewage plants and appropriate treatment of discharged water, HABs occur every year in the region. HABs cause damage to aquaculture and fisheries that are highly active in the region and increasing in demand.

CEARAC conducted a case study in 2008 to collect information on monitoring structures and HAB occurrence in the NOWPAP member states. CEARAC also developed a common format for sharing information. The latest report shared amongst the NOWPAP member states was the ‘HAB Case Study Report’.

Marine environment in the NOWPAP region (Chapter 1)

The NOWPAP sea area is semi-enclosed and surrounded by China, Japan, Korea and Russia. The area covers 121-143°E longitude and 33-52°N latitude, a total area of about 1,700,000 km². Within this area there are four major ocean currents: the Tsushima Warm Current; the East Korean Warm Current; the Yellow Sea Warm Current; and the Liman Cold Current. The southern part of the region belongs to the subtropical zone, whereas the northern part is in the subarctic zone and freezes over winter.

In 2010, the total population of the coastal areas within the NOWPAP member states grew to 580 million, making it one of most highly-populated areas in the world. Such growth has resulted in an increased load of various land-based pollutants in the marine environment via large and small rivers, and caused environmental deterioration in various coastal areas. As certain types of aquaculture, such as commercial fisheries, shellfisheries and seaweed farming, operate in coastal areas, large amounts of such pollutants have resulted in eutrophication and environmental deterioration on the sea floor in some areas.

HAB monitoring in the NOWPAP member states (Chapter 2)

All of the NOWPAP member states have strengthened their systems of HAB surveillance, and all conduct regular red tide and shellfish toxin monitoring. The NOWPAP member states monitor red tides and toxin-producing plankton, as these species cause significant damage to fisheries. Each member state has introduced its own warning and action standards, requiring fisherman to be warned and to take certain action after the cell density of causative species reaches a specified level. These standards are based on empirical data, and aim to reduce the damage to fisheries and aquaculture.

The regular monitoring process involves the checking of certain marine environment indicators, such as the water temperature, salinity and nutrient concentrations. In addition to the regular monitoring process, post-red tide monitoring is conducted in China, Japan and Korea, with additional monitoring of *C. polykrikoides* in Korea. Local fishery agencies and other involved organizations are responsible for analysing and monitoring the data and identifying the relationship between red-tide occurrences and environmental conditions.

HAB Occurrences in the NOWPAP region (Chapter 3)

Between 2006 and 2008, there were 10 red-tide events in China, 208 in Japan, 21 in Korea and 31 in Russia. It is difficult to compare these figures, due to the size difference in target areas, and the monitoring frequency of each member state. Japan, however, had the largest number of red-tide events, which have caused increasing damage to fisheries in recent years.

In 2010, the loss to Japanese fisheries reached 5 billion Japanese Yen (about USD60 million) due to blooms of *Chattonella antiqua* in the Ariake Sea, the Omura Bay and the Yatsushiro Sea. On the other hand, the number of red tides in Korea has approximately halved since 2005, from an average to 5 occurrences per year. Since 2009, there have been no *Cochlodinium* bloom occurrences, and so it appears that HAB occurrences in Korea have declined in recent years.

There are 62 causative species recorded in the NOWPAP region. *Heterosigma akashiwo* has been reported in all member states, and while the characteristics of the species have not changed its distribution in the region has. In recent years, *C. polykrikoides* has moved northward in Japan and *Chaetoceros sp.* red tides have been reported in Russia.

All member states have reported causative species of shellfish toxins [6 paralytic shellfish poisonings (PSPs), 7 diarrhetic shellfish poisonings (DSPs) and 8 amnesic shellfish poisonings (ASPs)], but only PSPs and DSPs (PSPs in Japan and DSP in China) have been reported in the NOWPAP region.

Challenging studies to cope with HABs (Chapter 4)

There are direct and indirect measures taken to reduce HAB damage to fisheries. Direct measures include the use of physical, chemical and biological controls against causative species, while indirect methods include the control and improvement of water quality. In 2007, NOWPAP CEARAC published the 'Booklet of Countermeasures against Harmful Algal Blooms in the NOWPAP Region'. Various countermeasure methods have been implemented in the NOWPAP region and many are under research and/or development.

In addition to introducing countermeasures, forecasting and early detection are effective tools to help cope with HABs. In the NOWPAP region, remote sensing and molecular genetics techniques are being studied to improve forecasting and early detection. Monitoring the movement of high chlorophyll patches detected by remote sensing is useful in preventing fishery damage, by allowing fish cages to be moved in the aquaculture area. Techniques for detecting phytoplankton species using satellite images are now under development and are expected to reduce HAB damage. Early in situ detection of harmful species is important for preventing damage. Several new techniques using molecular biological approaches, such as Fluorescent In Situ Hybridization (FISH), real-time Polymerase Chain Reaction (PCR), and Loop-Mediated Isothermal Amplification (LAMP), are under development for targeting various HAB species. Damage to fisheries will be mitigated if harmful species can be easily detected and managed before proliferation.

1 Introduction

1.1 Past CEARAC's activities on HABs

To understand and assess the HAB situation in the NOWPAP region, experts from each member state prepared a National Report on HABs. CEARAC summarized the information from these reports and published the 'Integrated Report on Harmful Algal Blooms for the NOWPAP Region' in 2005. The integrated report summarized the HAB situation in the region, and suggested that CEARAC undertake the following activities:

- 1) To facilitate the study of *Cochlodinium*
- 2) To seek a collaborative approach for HAB monitoring
- 3) To establish a common understanding of HABs through the development of a database and information network
- 4) To help develop a policy on the control of land-based nutrient discharges
- 5) To cooperate with other international organizations involved in HAB study

Based on these suggestions, CEARAC has implemented a number of activities over the past few years.

Cochlodinium polykrikoides blooms have caused significant damage to fisheries and aquaculture in the NOWPAP region, and occur frequently in Japan and Korea. The biology of *C. polykrikoides* has been studied extensively by experts in Japan and Korea. To assist in sharing this information, CEARAC developed the '*Cochlodinium* Home Page' (<http://www.cearac-project.org/wg3/cochlo-entrance/index.htm>) in 2005 with the cooperation of experts in the NOWPAP member states. CEARAC further prepared a *Cochlodinium* pamphlet in five languages (English, Chinese, Japanese, Korean and Russian) to allow fishermen, young scientists and stakeholders to gain a quick understanding of the issues.

There are basically two approaches to preventing or minimizing red-tide damage. One is to arrest red-tide blooms before they cause significant damage. In 2007, CEARAC published the 'Booklet of Countermeasures against Harmful Algal Blooms (HABs) in the NOWPAP Region', which outlines effective countermeasures that have been implemented in member states. Further research and development into HAB countermeasures is currently being undertaken.

The second approach to minimizing HAB damage is to improve water quality. Eutrophication is common in the NOWPAP region and is a cause of red tides. CEARAC began working on marine eutrophication in 2009, which involved the development of procedures for assessing eutrophication status, including the evaluation of land-based sources of nutrients in the NOWPAP region. Each NOWPAP member state implemented an evaluation of eutrophication status using these procedures between 2010 and 2011. The assessment results on eutrophication status will be used to improve the marine environment and countermeasures against HABs.

CEARAC established the 'HAB Integrated Website' (http://www.cearac-project.org/HAB_Integrated_Website/) in 2009 to provide information on HABs to stakeholders and policy-makers. The website is available to both NOWPAP member states as well as other countries. On the website, past publications are downloadable, and various databases, such as reference papers and HAB occurrences, in the NOWPAP region are available.

To improve information sharing among NOWPAP member states, CEARAC implemented the 'HAB Case Study' in the 2008-2009 biennium in order to establish the most effective and labor-saving way to share information. Each member state selected target sea areas in which HABs occur frequently, and conducted regular monitoring (Table 1.1; Figure 1.1). Information on monitoring organization, monitoring parameters and HAB occurrences in these selected sea areas was collected and summarized in a national report. Based on this information, the common sheet for sharing information was developed. The latest information on the NOWPAP region is shared using the common sheet, which helps stakeholders gain an understanding of the HAB situation in

the region.

HABs are a common environmental issue not only in the NOWPAP region, but also in the north Pacific and southeastern Pacific. In these regions, there are other international organizations that are involved in HAB issues, such as the Intergovernmental Oceanographic Commission (IOC)/IOC Sub-Commission for the Western Pacific (WESTPAC) and the North Pacific Marine Science Organization (PICES). Cooperating with valuable information is important for the conservation of the marine environment in the Pacific region. CEARAC's Secretariat has participated in meetings with other international organizations and attended the PICES HAB Section as an ex-officio member. CEARAC has attempted to strengthen its cooperation with other international organizations.

CEARAC has subsequently implemented most of the suggestions made in the HAB Integrated Report (2005) from 2006. It is important to continue to regularly share the latest information on HABs throughout member states. Five years have passed since the publication of the HAB Integrated Report, and recent information on HAB occurrence has been collected through the HAB Case Study. As such, CEARAC plans to update the HAB Integrated Report by adding the latest information, data and techniques for preventing damage caused by HABs.

The aims of this Integrated Report are to share the current HAB problems in the NOWPAP Region not only among NOWPAP member states, but also among other countries and international organizations. This report was updated by adding information collected through HAB Case Studies in each member state from 2008 to 2010.

Table 1.1 Selected sea areas in each member state for the HAB Case Study

Selected Areas in the HAB Case Study	
China	Coastal area of Qingdao region and Dalian region
Japan	Northwest sea area of Kyushu region and Ariake Sea
Korea	South coast of Korea
Russia	Amurskii Bay, Vostok Bay and Aniva Bay

In Figure 1, the NOWPAP region is the area within the dashed lines, and the Case Study selected areas are shown in ovals. This integrated report shows the current HAB situation in the selected areas, which are significant areas of HABs for the NOWPAP member states.




Figure 1.1 Area of the NOWPAP region

The dashed line indicates the NOWPAP region, which covers approximately 121-143°E longitude and 33-52°N latitude without prejudice to the sovereignty of any state.
Ovals indicate the HAB Case Study Area of each member state.

1.2 Definitions

Since each NOWPAP member has their own definition of a HAB, specific definitions were agreed upon in the first WG3 Meeting in Busan, Korea, in October 2003. The group agreed to use the scientific names of phytoplankton (referred to as plankton after the definitions below) species as used in National Reports.

HAB: A proliferation of unicellular phytoplankton that can cause massive fish or shellfish kills, contaminate seafood with toxins and alter aquatic ecosystems in ways that humans perceive as being harmful. There are two phenomena, the so called Red Tide and Toxin-producing Plankton.

Red Tide: Water discoloration by vastly increased numbers of unicellular phytoplankton that induce deterioration of aquatic ecosystems and occasionally fishery damage.

Toxin-producing Plankton: Phytoplankton species that produce toxins intracellularly and contaminate fish and shellfish throughout the food chain.

Scientific name of phytoplankton: In this report, the scientific names of phytoplankton are based on the HAB Case Study Report of each member state. However, if the name is different among NOWPAP member states, the latest scientific name will be used in this report. In addition, the scientific names of the following species have been changed. Previous names are in parenthesis:

Karenia mikimotoi (*Gymnodinium mikimotoi*)

Akashiwo sanguinea (*Gymnodinium sanguineum*)

Mirionecta rubra (*Mesodinium rubrum*)

1.3 Natural environment of the NOWPAP region

This section provides a brief overview on the natural environment in the NOWPAP region, focusing on the three major sea areas, major rivers and ocean currents. Figure 1.2 shows the geographic characteristics of the NOWPAP region.




Figure 1.2 Geographic characteristics of the NOWPAP region

1.3.1 Sea areas

As shown in Figure 1.2, sea areas A, B and C constitute the major part of the NOWPAP region's sea area. Table 1.2 provides basic information on each sea area.

Table 1.2 Basic Information on the three sea areas in the NOWPAP region

	Sea Area A	Sea Area B	Sea Area C
Surface area (km^2)	1,300,000	400,000	7,284
Volume (km^3)	1,750,000	17,600	131
Average depth (m)	1,350	44	18
Maximum depth (m)	3,796	100	85

Source: EMECS (2003), Environmental Guidebook on the Enclosed Coastal Seas of the World.

Sea Area A is a semi-enclosed sea surrounded by Japan, the Korean Peninsula and Russia. It is connected to the open ocean through several straits. Sea Area A is the largest and deepest of the three sea areas.

Sea Area B is a semi-enclosed sea bounded by the Chinese mainland on the west, the Korean Peninsula on the east and the East China Sea on the south. The waters of Sea Area B are yellowish due to the large amount of yellow silt that discharges from the large Chinese rivers. The depth of Sea Area B is significantly shallower than that of Sea Area A, having an average depth of 44 m.

Sea Area C is the smallest and most enclosed. It is located to the northwest of Sea Area B, and these two sea areas are connected via a relatively wide strait. Sea Area C is shallower than Sea Area B, with an average depth of 18 m. Sea Area C functions as an offshore gateway to Beijing.

1.3.2 Rivers

Numerous large and small rivers flow into the three sea areas. Table 1.3 shows some of these major rivers.

Table 1.3 Major rivers that flow into the three sea areas

Sea Area	River	Country	Catchment area (km^2)	Flow rate (m^3/s)
A	Tumen	China, Russia	33,800	287
	Razdolnaya	Russia	16,800	78
	Nakdong	Korea	23,817	794
	Tumnin	Russia	22,400	252
	Ishikari	Japan	14,330	400
	Shinano	Japan	11,900	518
B	Yangtze	China	1,807,199	29,000
	Han	Korea	26,018	1,171
	Nakdong	Korea	23,817	365
	Kum	Korea	9,810	841
C	Yellow	China	752,443	1,820
	Haihe	China	264,617	717
	Liaohe	China	164,104	302

Sources: Northwest Pacific Region Environmental Cooperation Center: NPEC (2003), The State of the Environment of the Northwest Pacific Region.

River Bureau, Ministry of Land, Infrastructure and Transport (2002), River Discharges Year Book of Japan.

Ministry of Construction and Transportation (1998), Discharge Annual Report in Korea.

Pollution Monitoring Regional Activity Centre: POMRAC (2009), Regional Overview on River and Direct Inputs of Contaminants into the Marine and Coastal Environment in NOWPAP Region with Special Focus on the Land Based Sources of Pollution.

Some rivers reach enormous lengths and widths due mainly to their large catchment areas. These rivers have a significant influence on the NOWPAP region's sea areas. Despite their relatively small surface area, sea areas B and C receive large amounts of inflow from some of the largest rivers in China, such as the Yangtze and Yellow rivers. In comparison to the sea areas above, the rivers in Sea Area A are not as large as those of the other sea areas, due to their relatively small catchment areas.

1.3.3 Major oceanographic currents in the NOWPAP region

Two strong currents exist in Sea Area A, the Tsushima Warm Current and the Liman Cold Current. The Tsushima Warm Current, a branch of the Kuroshio Current, enters Sea Area A from the strait between Japan and Korea and flows northeastward. The Liman Cold Current runs along the Eurasian Continent from north to south.

The Tsushima Warm Current diverges into three smaller branches upon entering Sea Area A. The first branch runs along the coastline of the Japanese archipelago, and the second runs along the Korean Peninsula and then turns and meanders eastward. The third cuts across the center of Sea Area A. Eventually, the major bodies of these currents flow into the Pacific Ocean or the Sea of Okhotsk through the straits between Hokkaido and Honshu, and Hokkaido and Sakhalin respectively. According to past records, the Tsushima Warm Current enters Sea Area A and exits into the Pacific Ocean approximately 2 months later. Some of the remaining current continues to travel northward, slowly cooling during its travel. Due to the shallowness of the strait between the Sakhalin and Russian mainland, part of this current turns around and heads south along the Eurasian Continent, becoming the Liman Current.

The Kuroshio Current also diverges into sea areas B and C as the Yellow Sea Warm Current. Figure 1.3 is a schematic of the oceanographic currents in the NOWPAP region.




Figure 1.3 Major oceanographic currents in the NOWPAP region

Source: Based on Yoon J.H. (1997), Bull. Jpn. Soc. Fish. Oceanogr., 61 (3): 300–303.

1.4 Impacts on the marine environment in the NOWPAP region

1.4.1 Population

The total population in the NOWPAP region's catchment areas was approximately 580 million in 2010. This is an increase of 20 million since 2003. About 85% of the population is in the Chinese region, with approximately 33 and 50 million people inhabiting the Japanese and Korean regions, respectively. Only 3.8 million people inhabit the Russian catchment area. The population density is highest in Korea, followed by China and Japan. The population density in Russia is about one and a half to two orders of magnitude less than that of other NOWPAP member states. Figure 1.4 shows the population size and density in the NOWPAP region's catchment areas.




Figure 1.4 Population size and density in the NOWPAP region's catchment areas

Source: China Population and Housing Census (2010), 2010 Population Census of Japan, 2010 Population Census, Statistics Korea (2010), Russian Census (2010)

The population of China is the sum of those in Heilongjiang Province, Jilin Province, Liaoning Province, Hebei Province, Henan Province, Shandong Province, Shanxi Province, Jiangsu Province, Anhui Province, Beijing, Tianjin Province and Shanghai

The population of Japan is the sum of those in Hokkaido, Aomori Prefecture, Akita Prefecture, Yamagata Prefecture, Niigata Prefecture, Toyama Prefecture, Ishikawa Prefecture, Fukui Prefecture, Kyoto Prefecture, Hyogo Prefecture, Tottori Prefecture, Shimane Prefecture, Yamaguchi Prefecture, Fukuoka Prefecture and Saga Prefecture

The population of D.P.R. Korea and South Korea is the national population.

The population of Russia is the sum of those in Primorskiy Krai, Khabarovsk Krai and Sakhalin Oblast

1.4.2 Nutrients inputs from land

Eutrophication caused by excessive inputs of nitrogen and phosphorus is primarily related to red-tide occurrences. In the NOWPAP region, rapid economic growth caused a eutrophic trend in some areas. The NOWPAP Pollution Monitoring Regional Activity Centre (POMRAC) published the ‘Regional Overview on River and Direct Inputs of Contaminants into the Marine and Coastal Environment in NOWPAP Region with Special Focus on the Land Based Sources of Pollution’ in 2009. This report showed that huge amounts of nutrients flow into the NOWPAP region. In some countries, discharge control is well managed, reducing nutrient inputs into the ocean. However, annual inputs from some rivers have increased the eutrophication situation in the NOWPAP region, which has not yet been remedied. Table 1.4 and Figure 1.5 show the annual discharge of nutrients into the NOWPAP member states in 2005.

Table 1.4 Annual discharge of nutrients (tons/year) from major rivers in the NOWPAP member states in 2005

	NH ₄ -N	T-N	T-P	NH ₄	NO ₃	PO ₄
China	1,008,713	-	-	-	-	-
Japan	-	88,107	4,912	-	-	-
Korea	-	161,023	6,954	-	-	-
Russia	-	-	-	4,533	4,489	553

Source: POMRAC (2009), Regional Overview on River and Direct Inputs of Contaminants into the Marine and Coastal Environment in NOWPAP Region with Special Focus on the Land Based Sources of Pollution




Figure 1.5 The length of coastline normalized the river's total nitrogen input (t/year/km)

Source: POMRAC (2009), Regional Overview on River and Direct Inputs of Contaminants into the Marine and Coastal Environment in NOWPAP Region with Special Focus on the Land Based Sources of Pollution

1.4.3 Aquaculture

Various types of aquaculture operate in the NOWPAP region, including cultivating fish, shellfish and seaweeds. Figure 1.6 shows the major aquaculture operating areas in the region. Aquaculture operates widely along the coasts of China, Japan and Korea. In Russia, aquaculture is limited to certain areas, but is expanding. Table 1.5 shows the types of aquaculture conducted in the NOWPAP region.



Figure 1.6 Major aquaculture areas in the NOWPAP region

Sources: Yoon Y. H. (2001), Bull. Plankton Soc. Japan, 48 (2): 113–120.

Matsuoka K. (2004), Bull. Plankton Soc. Japan, 51 (1): 38–45.

Geological Institute, China Scientific Academy (1999); Chinese national atlas of natural resources.

Table 1.5 Types of aquaculture conducted in the NOWPAP Region

	Location	Type of aquaculture
China	Coast of Bohai Sea, Shandong Peninsula, Liaodong Peninsula	Tiger prawns, Scallop, Seaweeds, etc.
Japan	North coast of Kyushu	Amberjack, Red seabream, Yellowtail
	Wakasa Bay	Tiger puffer, Red seabream, Yellowtail,
	West coast of Hokkaido	Scallop
Korea	West and south coast	Bastard halibut, Amberjack, Rockfish
Russia	South coast of Sakhalin, Peter the Great Bay	Scallop, Seaweeds, Mussel, Cucumaria

2 Information on HAB monitoring

2.1 Monitoring framework in the NOWPAP region

HAB monitoring in the NOWPAP member states is primarily conducted by fisheries research organizations and environmental monitoring centers, but various national institutes also provide valuable information. Korea has a particularly well established cooperative structure between national institutes and local government, where local government focuses on monitoring inshore while national institutes monitor inshore and offshore areas.

Table 2.1 summarizes HAB monitoring organizations in each member state. The location of monitoring sites in the target sea areas of HAB Case Studies are shown in Figure 1.1.

Table 2.1 HAB monitoring organization in the NOWPAP member states

	Monitoring Organization	Monitored sea area
China	North China Sea Environmental Monitoring Centre	Qingdao coastal area
	National Marine Environmental Monitoring Centre	Zhangzi Island off Dalian
Japan	Yamaguchi Prefectural Fisheries Research Center	Coastal area of Yamaguchi Pref.
	Fukuoka Fisheries and Marine Technology Research Center	Northern Kyushu Fukuoka Bay, Karatsu Bay, Genkai Sea, Hibiki Sea, Ariake Sea
	Saga Prefectural Genkai Fisheries Promotion Center	Northern Kyushu Karatsu Bay, Nagoyaura, Kariya Bay, Imari Bay
	Saga Prefectural Ariake Fisheries Promotion Center	Ariake Sea
	Nagasaki Prefectural Institute of Fisheries	Northern Kyushu Imari Bay, Hirado Western Kyushu Ohmura Bay, Tachibana Bay, Coasts of Kitamatsu, Kujukushima, Coast of Seihei, Ariake Sea
	Shimane Prefectural Fisheries Technology Center	Coastal area of Shimane Pref.
	Tottori Prefectural Fisheries Experimental Station	Coastal area of Tottori Pref.
	Hyogo Fisheries Technology Institute	Coastal area of Hyogo Pref.
	Kyoto Prefectural Agriculture, Forestry and Fisheries Technology Center, Fisheries Technology Department	Coastal area of Kyoto Pref.
	Fukui Prefectural Fisheries Experimental Station	Coastal area of Fukui Pref.
	Ishikawa Prefecture Fisheries Research Center	Coastal area of Ishikawa Pref.
	Toyama Prefectural Fisheries Research Institute	Coastal area of Toyama Pref.
	Niigata Prefectural Fisheries and Marine Research Institute	Coastal area of Niigata Pref.

Table 2.1 Continued

Country	Monitoring organization	Monitored sea area
Korea	National Fisheries Research and Development Institute - Southeast Sea Fisheries Research Institute - Southwest Sea Fisheries Research Institute	South coast covering inshore and offshore Southeastern area Southwestern area
	Local government - Fisheries station under Gyeongnam province: Tonyeong (TFS), Sacheon (SFS), Goseong (GFS), Geoje (GEF), Namhae (NFS) - Fisheries station under Jeonam province: Wando (WFS), Yeosoo (YFS), Goheung (GFS), Jangheung (JFS), Kangjin (KFS)	South coast targeted on potential HAB areas in inshore Southeastern area Southwestern area
Russia	A.V. Zhirmunkii Institute of Marine Biology, FEB RAS (1991-2006)	Amurskii Bay and Vostok Bay
	Center of Monitoring of HABs & Biotoxins A.V. Zhimunskii Institute of Marine Biology, FEB RAS (2007-)	
	Sakhalin Research Institute of Fisheries & Oceanography	Aniva Bay

2.1.1 Monitoring of HAB and monitoring parameters in the NOWPAP member states

All NOWPAP members have a regular red tide and toxin-producing plankton monitoring program to check for the presence of HAB species. Member states target and strengthen the monitoring of red-tide species which cause major damage to fisheries (Table 2.2). Furthermore, each member state has set warning and action standards in order to prevent damage by various species (Table 2.3). This standard varies from country to country and from region to region. However, if the cell number of target species in situ is observed over the warning level, monitoring organizations alert fishermen. Moreover, if target species make a bloom over the action standard level, monitoring organizations encourage countermeasures, such as feed withdrawal and the movement of fish cages.

Japan and Russia target toxin-producing plankton species to prevent shellfish toxin and damage to human health. All NOWPAP member states set warning and action standards for cell density of toxin-producing plankton, *Alexandrium* spp., *Gymnodinium catenatum*, *Dinophysis* spp. and *Pseudo-nitzschia* spp.

Due to such monitoring, damage to human health by shellfish poisoning has not been reported in recent years.

In addition to the above mentioned monitoring, China, Japan and Korea conduct post red-tide monitoring, and Korea conducts additional monitoring focusing on *Cochlodinium polykrikoides* blooms.

Information on regular red-tide monitoring, post red-tide monitoring and the monitoring of shellfish toxin is summarized as Tables 2.4, 2.5 and 2.6 respectively.

Table 2.2 Target red-tide species and toxin-producing plankton species in monitoring programs

	Target red-tide species	Target toxin-producing plankton species
China	<i>Mirionecta rubra</i> <i>Noctiluca scintillans</i> <i>Skeletonema costatum</i> <i>Heterosigma akashiwo</i> <i>Eucampia zodianus</i> <i>Chaetoceros affinis</i> <i>Chattonella marina</i>	
Japan	<i>Karenia mikimotoi</i> <i>Cochlodinium polykrikoides</i> <i>Heterocapsa circularisquama</i> <i>Chattonella antiqua</i> <i>Chattonella marina</i> <i>H. akashiwo</i>	<i>Dinophysis fortii</i> <i>Dinophysis acuminata</i> <i>Dinophysis caudata</i> <i>Gymnodinium catenatum</i> <i>Alexandrium catenella</i> <i>Alexandrium tamarensense</i>
Korea	<i>Akashiwo sanguinea</i> <i>C. polykrikoides</i> <i>Prorocentrum dentatum</i> <i>Prorocentrum minimum</i> <i>Ceratium furca</i> <i>H. akashiwo</i> <i>Noctiluca scintillans</i>	
Russia	<i>Pseudo-nitzschia delicatissima</i> <i>Pseudo-nitzschia multiseries</i> <i>S. costatum</i> <i>K. mikimotoi</i> <i>N. scintillans</i> <i>Dynobryon balticum</i> <i>Chattonella sp.</i> <i>H. akashiwo</i>	<i>Pseudo-nitzschia delicatissima</i> <i>Pseudo-nitzschia fraudulenta</i> <i>Pseudo-nitzschia multistriata</i> <i>Pseudo-nitzschia multiseries</i> <i>Pseudo-nitzschia seriata/pungens</i> <i>A. tamarensense</i> <i>D. acuminata</i> <i>Dinophysis acuta</i> <i>D. fortii</i> <i>Dinophysis norvegica</i> <i>Dinophysis rotundata</i> <i>K. mikimotoi</i> <i>Protoceratium reticulatum</i>

Table 2.3 Warning and action standards for each causative species

Region	Species name	Warning/action standards (cell/ml)		Affected fish/shellfish
		Warning standard	Action standard	
China ¹	<i>M. rubra</i>	500		
	<i>N. scintillans</i>	50		
	<i>S. costatum</i>	5,000		
	<i>H. akashiwo</i>	50,000		
	<i>E. zodianus</i>	100		
	<i>C. marina</i>	100		
Japan	<i>A. tamarense</i>	1,000		
	<i>K. mikimotoi</i>	500	5,000	
	<i>H. akashiwo</i>	5,000	50,000	
	<i>H. akashiwo</i>	-	10,000	
	<i>C. antiqua</i>	1	10	Yellowtail, cockles etc.
	<i>C. marina</i>	1	10	Yellowtail etc.
Nagasaki Pref. ^{*4}	<i>K. mikimotoi</i>	100	500	Fish, Shellfish, crustaceans etc.
	<i>C. polykrikoides</i>	50	500	Yellowtail, rea seabream, pufferfish, striped jack etc.
	<i>H. akashiwo</i>	1,000	10,000	Yellowtail, grouper etc.
	<i>H. circularisquama</i>	10	50	Shellfish (bivalves)
	<i>Chattonella</i> spp.	2,500	5,000	
	<i>C. polykrikoides</i>	300	1,000	
Korea ⁵	<i>Gyrodinium</i> sp.	500	2,000	
	<i>K. mikimotoi</i>	1,000	3,000	
	Other dinoflagellates	30,000	50,000	
	Diatoms	50,000	100,000	
	Mixed blooms	40,000	80,000	
Russia ^{*6}	<i>Pseudo-nitzschia calliantha</i>	500		Shellfish
	<i>Pseudo-nitzschia delicatissima</i>	500		Shellfish
	<i>Pseudo-nitzschia fraudulenta</i>	500		Shellfish
	<i>Pseudo-nitzschia multistriata</i>	500		Shellfish
	<i>Pseudo-nitzschia multiseries</i>	500		Shellfish
	<i>Pseudo-nitzschia seriata/pungens</i>	500		Shellfish
	<i>A. tamarense</i>	0.5		Shellfish
	<i>D. acuminata</i>	0.5		Shellfish
	<i>D. acuta</i>	0.5		Shellfish
	<i>D. fortii</i>	0.5		Shellfish
	<i>D. norvegica</i>	0.5		Shellfish
	<i>D. rotundata</i>	0.5		Shellfish
	<i>P. reticulatum</i>	500		Shellfish

Sources:^{*1} Ocean and Fishery Administration of Shandong Province (2006), Annual Report of Marine Environment of Shandong Province

Ocean and Fishery Administration of Liaoning Province (2005-2009), Annual Report of Marine Environment of Liaoning Province

^{*2} Yamaguchi Prefecture (<http://www.pref.yamaguchi.lg.jp/cms/a16500/uminari-top.html>)

^{*3} Fukuoka Fisheries and Marine Technology Research Center (<http://www.sea-net.pref.fukuoka.jp/>)

^{*4} Nagasaki Prefectural Institute of Fisheries

(<http://www.marinelabo.nagasaki.jp/news/gyorendayori/H13/1307no75akasio-tyui.pdf>)

^{*5} National Fisheries Research and Development Institute (<http://portal.nfrdi.re.kr/redtide/index.jsp>)

^{*6} The Federal Legislative At SanPIN 2.3.2.2401-08

2.1.2 Monitoring of shellfish toxin

Monitoring of shellfish toxin is conducted in all of the NOWPAP member states in order to prevent the shipment and harvesting of contaminated shellfish by fishery research organizations.

All of the NOWPAP member states have quarantine limits for harvested shellfish. When the toxin level exceeds this limit, the shipping and harvesting of shellfish is stopped until the toxin level returns to an acceptable level. The standard value for preventing the shipment of shellfish is 80 µg (STX eq.)/100g of meat for PSP and 0.05 MU/g for DSP in China; 4 MU/g wet weight of meat for PSP and 0.05 MU/g wet weight of meat for DSP in Japan; 80 µg /100g of meat for PSP in Korea; 80 µg/100 g of saxitoxin (mollusks) for PSP and 0.16 mg/kg of okadaic acid (mollusks) for DSP and 20 mg/kg of domoic acid (mollusks) and 30 mg/kg of domoic acid (crab's internal) for ASP in Russia respectively. Some researchers have reported that 1 MU/g is equivalent to approximately 20 µg (STX eq.)/100g.

2.2 Common issues with monitoring activities in the NOWPAP region

Although HAB monitoring is conducted by all NOWPAP Members, there is some variation amongst members in monitoring methods and frequency. Such variation has resulted from differing HAB problems, and limited personnel, technology and finance in certain areas.

Local variations in monitoring schemes further confound HAB data comparisons within and between regions. This is particularly apparent in China and Japan. In Japan, for example, the method of HAB monitoring varies with each prefectoral fishery laboratory. This variation occurs because fishery laboratories conduct HAB monitoring in accordance with indigenous species and their monitoring budget. As a result, a consistent nationwide methodology for HAB monitoring has not been established. Furthermore, monitoring could be stopped if prefectoral fishery laboratories are unable to obtain finance for HAB monitoring.

Table 2.4 Parameters and frequency of regular red-tide monitoring in the NOWPAP member states

	China	Japan	Korea	Russia
Bloom and its causative organisms	- Name of red-tide species	- Name of red-tide species - Cell density - Water color	- Name of red-tide species - Cell density - Water color	- Name of red-tide species - Cell density - Water color
Monitoring parameters				
Water quality	- Transparency - Nutrients - Index on pH ^{*1} , DO ^{*2} , Nutrient quality ^{*3} , HAB risk ^{*4} , (in Dalian coastal area)	- Water temperature - Salinity - DO - pH - COD - Transparency - Nutrients - Chlorophyll a	- Water temperature - Salinity - DO - Transparency - Nutrients - Chlorophyll a	- Water temperature - Salinity - DO - Heavy metals
Meteorology	- Weather - Wind direction/speed	- Weather - Coverage by cloud - Wind direction/speed - Precipitation - Daylight time	No monitoring	- Weather - Ice cover
Others	No monitoring	Sediment quality	No monitoring	No monitoring
Monitoring frequency	No information	Fukuoka Pref.: 1/month Saga Pref.: (May-October) Nagasaki Pref.: (June-October)	1/month 9/year (March-November)	1991-1993 May-Dec (1-2/month) 1996-1998 Jan.-May (4/month) 1999-2000 May-Apr (2/month) 2004-2008 Oct-Dec (2/month)

*1: pH index (D_{pH}): the pH value is classified as one of indices, 1, 3 or 5, which refer to a pH range from 7.5 to more than 9.5. The higher the pH value, the higher the grade.

*2: DO index (D_{DO}): the DO value is classified as one of indices, 1, 3 or 5, which refer to a DO range from 105 % to more than 110%. The higher the DO saturation, the higher the grade.

*3: Nutrient quality index (D_u): D_u is determined by the dissolved inorganic nitrogen, dissolved inorganic phosphorus and COD concentrations. D_u is classified as one of three indices, 1, 3 and 5. The higher the D_u , the higher grade.

*4: HAB risk index (D_R): D_R is determined from the Chl-a concentration and biomass of the dominant species. Dominant species are classified into 5 types by length. D_R is classified into coincident grades as biomass. D_R is drawn by putting Chl-a and biomass of dominant species together and classified according to grades. D_R is classified into three grades initially, representing index value 1, 2-20 and 25, being low HAB risk, potential HAB risk and HAB occurrence respectively.

Table 2.5 Parameters and frequency of post-red tide monitoring in the NOWPAP member states

	China	Japan	Korea	Russia
Bloom and its causative species	- Name of red-tide species - Cell density - Bloom area size	- Name of red-tide species - Cell density - Bloom area size - Water color	- Name of red-tide species - Cell density - Bloom area size - Water color	No monitoring
Monitoring parameters	Water quality	- Water temperature - Salinity - DO	- Water temperature - Salinity - DO	- Water temperature - Salinity
Meteorology	No monitoring	No monitoring	Weather Coverage by cloud Wind direction/speed	No monitoring
Others	No monitoring	No monitoring	No monitoring	No monitoring
Monitoring frequency	Immediately after water discoloration	Immediately after water discoloration	Immediately after water discoloration	No monitoring

Table 2.6 Parameters and frequency of regular monitoring of shellfish toxin in the NOWPAP member states

	China	Japan	Korea	Russia
Bloom and its causative species	- Name toxin-producing plankton species	- Name of toxin-producing plankton species - Cell density - Water color	- Name of toxin-producing plankton species - Cell density - Water color	- Name of toxin-producing plankton species - Cell density
Monitoring parameters	Water quality	No monitoring	- Water temperature - Salinity - DO - pH - Transparency - Nutrients - Chlorophyll a	- Water temperature - Salinity - DO
Meteorology	No monitoring	No monitoring	No monitoring	No monitoring
Others	No monitoring	- Toxin levels in shellfish (MU/g)	- Toxin levels in shellfish	- Toxin levels in shellfish
Monitoring frequency	No information	Toxin-producing plankton monitoring: 12-16/year	1/month	Since 2008 3/year
		Toxin level monitoring: weekly during the period exceed standard. Otherwise, biweekly and/or less in non-blooming season	Every week, once toxin is detected (usually 30/year)	September

2.3 Monitoring framework in target sea areas of the HAB Case Study

In the ‘HAB Case Study’, each member state selected target sea areas where HABs frequently occur and where monitoring is regularly conducted. In these areas, organizations such as local fishery institutes conduct regular monitoring to better understand HAB occurrences, and to measure the situation of the marine environment.

The monitoring sites in the target sea areas of each member state are shown in Figures 2.1-2.5.




Figure 2.1 Location of monitoring sites in China

The target sea areas of China are the coastal areas of Qingdao and Dalian. The Qingdao coastal area faces the North Yellow Sea and includes Jiaozhou Bay. With an average water depth of 7 m and a maximum depth of 64 m, most parts of Jiaozhou Bay are less than 5 m deep. The major rivers which discharge directly into Qingdao area are the Haipo, Moshui, Licun and Dagu. Dalian coastal area is located on the opposite side of the Shandong Peninsula and faces the North Yellow Sea and Bohai Sea. The average depth in this area is 18 m. The Biliu, Fuzhou, Zhuanghae, Yingna, Dasha, Shizui, Liauancun and Dengsha rivers flow into this area. In the Qingdao coastal area, the North China Sea Environmental Monitoring Centre conducts HAB monitoring at 43 monitoring sites. In the Dalian coastal area, the National Marine Environmental Monitoring Centre has conducted HAB monitoring around Zhangzi Island since 2003.




Figure 2.2 Location of red-tide monitoring sites in Japan




Figure 2.3 Location of shellfish poisoning and toxin-producing plankton monitoring sites in Japan

The target sea areas of Japan are strongly influenced by the Tsushima Warm Current. The topography of the coastline is complex. In some areas, such as in the west Kyushu area, numerous small islands are scattered along the coast. There are also many remote islands, such as the Goto Islands, Tsushima and Iki. In this target sea area, four local fishery agencies conduct HAB monitoring. These are the Yamaguchi Prefectural Fisheries Research Center, the Fukuoka Fisheries and Marine Technology Research Center, the Saga Prefectural Genkai Fisheries Promotion Center and the Nagasaki Prefectural Institute of Fisheries. Fishery is a major industry in the coastal areas of this region, and many aquaculture farms operate along the calm inlets.




Figure 2.4 Location of monitoring sites in Korea

The target sea areas of Korea are located in the eastern part of the South Sea, which face the East China Sea. Its southern part, facing offshore, is directly affected by the Tsushima Warm Current, and has a long irregular coast line resulting in relatively low waves during typhoons. Fisheries, including fish farming, are therefore well developed in this area. The target sea area neighboring Goseong-jaran Bay and Jinju Bay is an important culture ground for finfish, cage culture and shellfish bottom culture.




Figure 2.5 Location of monitoring sites in Russia

The target sea areas in Russia cover the north part of Amurskii Bay, Vostok Bay and Aniva Bay. Amurskii Bay is the largest secondary bay within Peter the Great Bay in the northwestern part of the NOWPAP region. The Amurskii Bay is the most developed area in Primorskii Krai where the large cities of Vladivostok and Ussuriysk are located. Vostok Bay is a subarea of Peter the Great Bay. It has an increasing population and is one of the largest recreational zones in the Far East. Aniva Bay is one of the largest in Sakhalin Island, located in the south.

3 HAB occurrence in the NOWPAP region

The data on HAB occurrence in this report is based on the ‘HAB Case Study Report’ made by each member state from 2008 to 2010. The period of data shown in this report varies amongst member states, and is shown in Table 3.1. These differences are due to the year in which the reports on HAB occurrence in each member state were published.

Table 3.1 Periods of HAB occurrence in the NOWPAP member states used in this report

Period	
China	1990 – 2009
Japan	2006 – 2008 (Northwestern sea area of Kyushu region), 2008 (Ariake Sea)
Korea	2007 – 2009
Russia	1991 – 2010 (Amurskii Bay), 2001 – 2009 (Vostok Bay), 2001 – 2002 (Aniva Bay)

3.1 Red-tide occurrences in the NOWPAP region

Table 3.2 summaries recent red-tide occurrences in the NOWPAP region based on the ‘HAB Case Study Report’ of the NOWPAP member states. Red-tide events have been continuously recorded along the coastal areas with annual and spatial variations. Intensive fishery and aquaculture areas tend to have recorded numerous red-tide occurrences. To date, about 100 red-tide producing plankton species have been recorded in the NOWPAP Region (Table 3.3). In Table 3.3, red-tide plankton species observed in recent years are shown in parentheses.

Two flagellate species, *Heterosigma akashiwo* and *Noctiluca scintillans*, and the one diatom species, *Skeletonema costatum*, have been recorded in the coastal waters of all NOWPAP members states. Both of these flagellate species have caused extensive damage to local fisheries. Other common and damage-causing species include *Karenia mikimotoi*, *Akashiwo sanguinea* and *Prorocentrum micans*, all being flagellates. *Cochlodinium polykrikoides* is a species which has caused serious damage to fisheries in Japan and Korea.

The extent of red tides within the NOWPAP region is usually limited to less than 100 km² in the Japanese, Korean and Russian waters. Blooms in the Chinese waters however, often extend over 100 km² (Table 3.2). A possible reason for the difference in records between China and other NOWPAP members could be their different data sources. In China, bloom size was largely identified through aerial survey, whereas the other NOWPAP members collected data primarily from sea vessels.

Table 3.2 Summary of recent red-tide events in the NOWPAP region

	China (Qingdao coastal area and Dalian coastal area)	Japan (Northwestern sea area of Kyushu region and Ariake Sea)	Korea (South coast of Korea)	Russia (Amurskii Bay, Vostok Bay and Aniva Bay)
Total number of events	50 red-tide events from 1990–2009, of which 2 events led to fish-kills in the Dalian coastal area.	278 red-tide events occurred during 2005–2008. 1407 red-tide events recorded from 1979–2008, in which 122 events caused fishery damage.	194 red-tide events occurred during 1995–2009. 873 red-tide events recorded from 1995–2009, of which 209 events led to fish-kills over the whole Korean coast.	41 red-tide events recorded recorded. All events were harmless and caused no damage.
Causative species	See Table 3.3	See Table 3.3	See Table 3.3	See Table 3.3
Cell density	<i>Heterosigma akashiwo</i> recorded the highest density at 95,400 cells/ml.	The highest density is 173,000 cells/ml by multi-species red tide with <i>Heterocapsa rotundata</i> and <i>Amphidinium</i> sp.	In recent years, a low density of <i>Cochlodinium polykrikoides</i> bloom (below 5,600 cells/ml) was observed. <i>Scrippsiella trochoidea</i> recorded the highest density at 15,000 cells/ml.	<i>Skeletonema costatum</i> recorded the highest density at 12,700 cells/ml in the Amurskii Bay.
Size of bloom	In the Qingdao coastal area, <i>Mirionecta rubra</i> formed the largest red tide at 450 km ² . In Dalian, the largest red tide reached 827 km ² , however the causative species is unknown.	In the Ariake Sea, <i>Mirionecta rubra</i> formed the largest red tide at 171 km ² . The area of other red-tide events is less than 1 km ² .	Large blooms (ca. 40–60 km ²) were primarily by <i>C. polykrikoides</i> .	There is no information on size of bloom.
Duration	Most red tides lasted less than 1 week. However, <i>Rhizosolenia delicatula</i> bloom lasted for 20 days in 2004.	A multi-species red tide consisting of <i>Asterionella kariana</i> and <i>Skeletonema costatum</i> lasted for one month. Most red-tide events ended within one week.	The duration of a <i>C. polykrikoides</i> bloom was 22–50 days.	The duration of <i>Prorocentrum triestinum</i> bloom was 76 days in the Amurskii Bay, however the duration of most of blooms were less than 1 week in Vostok Bay and Aniva Bay.

Table 3.3 Red-tide species recorded in the NOWPAP region

Class	Genus and Species	China	Japan	Korea	Russia
Bacillariophyceae	<i>Asterionella</i> sp.	(✓)			
	<i>Asterionellopsis glacialis</i>				✓
	<i>Chaetoceros curisetum</i>		(✓)		
	<i>Chaetoceros socialis</i>	(✓) ✓			
	<i>Chaetoceros affinis</i>				✓
	<i>Chaetoceros contortus</i>				✓
	<i>Chaetoceros curisetus</i>				✓
	<i>Chaetoceros salsugineus</i>				✓
	<i>Chaetoceros</i> sp.	✓	(✓)	(✓)	
	<i>Coscinodiscus asteromphalus</i>	(✓) ✓			
	<i>Coscinodiscus gigas</i>		(✓)		
	<i>Coscinodiscus</i> sp.			(✓)	
	<i>Ditylum brightwellii</i>				(✓)
	<i>Dactyliosolen fragilissimus</i>				✓
	<i>Eucampia zodiacus</i>	(✓) ✓		(✓)	
	<i>Eucampia</i> sp.			(✓)	
	<i>Leptocylindrus danicus</i>	(✓)	(✓) ✓	(✓)	
	<i>Leptocylindrus minimus</i>				✓
	<i>Leptocylindrus</i> sp.			(✓)	
	<i>Navicula</i> sp.	(✓)		(✓)	
	<i>Neodelphineis pelagica</i>			(✓)	
	<i>Nitzschia hybrid f. hyaline</i>				✓
	<i>Nitzschia</i> sp.		(✓)		
	<i>Pseudo-nitzschia calliantha</i>				(✓) ✓
	<i>Pseudo-nitzschia multiseries</i>				(✓) ✓
	<i>Pseudo-nitzschia pseudodelicatissima</i>				(✓) ✓
	<i>Pseudo-nitzschia pungens</i> [†]			(✓) ✓	(✓) ✓
	<i>Pseudo-nitzschia delicatissima</i>				✓
	<i>Pseudo-nitzschia fraudulenta</i>				✓
	<i>Pseudo-nitzschia multistriata</i>				✓
	<i>Pseudo-nitzschia seriata</i>				✓
	<i>Pseudo-nitzschia</i> sp.			(✓)	
	<i>Rhizosolenia delicatula</i>	✓	(✓)		
	<i>Rhizosolenia fragilissima</i>				(✓)
	<i>Rhizosolenia setigera</i>				(✓)
	<i>Rhizosolenia</i> sp.	(✓)	(✓) ✓	(✓)	
	<i>Skeletonema costatum</i>	(✓) ✓	(✓) ✓	(✓) ✓	(✓) ✓
	<i>Skeletonema</i> sp.		✓	(✓)	
	<i>Thalassiosira decipiens</i>				(✓)
	<i>Thalassiosira rotula</i>				(✓)
	<i>Thalassiosira mala</i>				✓
	<i>Thalassiosira nordenskioeldii</i>				✓
	<i>Thalassiosira</i> sp.	✓	(✓) ✓	(✓)	
	<i>Thalassionema nitzschiooides</i>				✓
Cyanophyceae	<i>Microcystis viridis</i>			(✓)	

Table 3.3 Continued

Class	Genus and Species	China	Japan	Korea	Russia
Dinophyceae	<i>Akashiwo sanguinea</i>			✓	
	<i>Alexandrium catenella</i>	(✓) ✓	(✓)		
	<i>Alexandrium fraterculus</i>		(✓)	✓	
	<i>Alexandrium</i> sp.			(✓)	
	<i>Ceratium furca</i>	(✓)	(✓) ✓	✓	
	<i>Ceratium fusus</i>		(✓)	(✓) ✓	
	<i>Ceratium</i> sp.			(✓)	
	<i>Cochlodinium polykrikoides</i>	(✓) ✓	(✓) ✓		
	<i>Cochlodinium</i> sp.		(✓)		
	<i>Dinophysis ovata</i>	(✓)			
	<i>Exuviaella marina</i>	(✓)			
	<i>Gonyaulax spinifera</i>	(✓) ✓			
	<i>Gonyaulax polygramma</i>			✓	
	<i>Gymnodinium instriatum</i>		✓		
	<i>Gymnodinium</i> sp.			(✓)	
	<i>Gyrodinium</i> sp.	(✓)	(✓)		
	<i>Heterocapsa circularisquama</i>		(✓) ✓		
	<i>Heterocapsa</i> sp.	✓		(✓)	
	<i>Heterocapsa triquetra</i>			(✓) ✓	
	<i>Heterocapsa rotundata</i>				✓
	<i>Karenia mikimotoi</i>	(✓)	(✓) ✓	(✓)	
	<i>Noctiluca scintillans</i> ²	(✓) ✓	(✓) ✓	(✓) ✓	(✓) ✓
	<i>Noctiluca</i> sp.		✓		
	<i>Oxyrrhis marina</i>				(✓)
	<i>Prorocentrum balticum</i>		(✓)		
	<i>Prorocentrum dentatum</i>		(✓) ✓	(✓) ✓	
	<i>Prorocentrum micans</i>	(✓)	(✓)	(✓)	
	<i>Prorocentrum minimum</i>	(✓)	(✓) ✓	(✓) ✓	(✓) ✓
	<i>Prorocentrum sigmoides</i>		(✓) ✓		
	<i>Prorocentrum triestinum</i>		(✓) ✓	(✓) ✓	✓
	<i>Prorocentrum</i> sp.		✓	(✓) ✓	
	<i>Protoceratium reticulatum</i>				✓
	<i>Scrippsiella trochoidea</i>			(✓)	
	<i>Scrippsiella</i> sp.		✓		
Raphidophyceae	<i>Chattonella antiqua</i>	(✓) ✓	(✓) ✓		
	<i>Chattonella globosa</i>				(✓) ✓
	<i>Chattonella marina</i>	(✓) ✓	(✓)		
	<i>Chattonella</i> sp.				✓
	<i>Fibrocapsa japonica</i>		(✓)		
	<i>Heterosigma akashiwo</i> ³	(✓) ✓	(✓) ✓	(✓) ✓	(✓) ✓
Chrysophyceae	<i>Dictyocha fibula</i>		✓	(✓)	
	<i>Dinobryon balticum</i>				✓

Table 3.3 Continued

Class	Genus and species	China	Japan	Korea	Russia
Eugrenophyceae	<i>Eutreptia lanowii</i>				(✓)
	<i>Eutreptiella gymnastica</i>		(✓)	(✓)	(✓)
	<i>Eutreptiella</i> sp.			(✓)	
	<i>Euglena pascheri</i>				✓
Haptophyceae	<i>Phaeocystis</i> •] È		(✓)		
Cryptophyceae	<i>Chroomonas marina</i>			(✓)	
	<i>Chroomonas salina</i>			(✓)	
	<i>Cryptomonas acuta</i>			(✓)	
	<i>Cryptomonas</i> sp.			(✓)	
	<i>Plagioselmis</i> sp.				✓
Prasinophyceae	<i>Pyramimonas</i> sp.		(✓)		
Prumnesiophycidae	<i>Gephyrocapsa oceanica</i>			✓	
Ciliate	<i>Mirionecta rubra</i>	(✓) ✓	(✓) ✓	(✓) ✓	
	<i>Tontonia</i> sp.			(✓)	

The parentheses indicate the species reported in the last HAB Integrated Report.

*1: *Nitzschia pungens* is the synonym of *Pseudo-nitzschia pungens*. In this Report, *N. pungens* is referred to as *P. pungens*.

*2: *Noctiluca scintillans* is the sole species of the genus. Therefore, *Noctiluca* sp. is included in *N. scintillans*.

*3: Since 2000, the species considered to be part of *Gymnodinium* have been divided into several genera, based on the nature of the apical groove and biochemistry.

3.1.1 Red tides in China

In the North Yellow Sea, 50 red-tide events have been observed since 1990, with 42 of them in target sea areas. Fishery damage only resulted from two of these events.

Between 1990 and 2008, 29 red-tide events were recorded in the Qingdao coastal area (Table 3.4). The most frequently observed species were *Mirionecta rubra* and *Skeletonema costatum*.

In recent years, the area of red-tide occurrences has expanded. Jiaozhou Bay was a major area during the 1990's, while Fushan Bay has become a main area since the early 21st century. In the last 5-6 years, occurrences have spread from the western (Lingshan Bay) to the eastern (Shazikou Bay) parts of the Qingdao coastal area.

Table 3.4 Recent red-tide events in the Qingdao coastal area

Occurrence date	Occurrence location	Causative species	Occurrence area
26 Jun, 1990	Jiaozhou Bay	<i>M. rubra</i>	2 km ²
Apr, 1992	Jiaozhou Bay	-	-
12 May, 1992	East Qingdao area	-	-
Aug, 1992	Jiaozhou Bay	-	-
Aug, 1997	Center of Jiaozhou Bay	<i>S. costatum</i>	- (small)
3-8 Jul, 1998	Northeast part of Jiaozhou Bay	<i>S. costatum</i>	10 km ²
8-15 Jun, 1999	Northeast part of Jiaozhou Bay	<i>Eucampia zodiacucus</i>	- (small)
23-24 Jul, 1999	Jiaozhou Bay	<i>S. costatum</i>	26 km ²
26 Jul, 1999	Fushan Bay	<i>M. rubra</i>	60 km ²
20-23 Jul, 2000	Center of Jiaozhou Bay	<i>Noctiluca scintillans</i>	92 km ²
4 Apr, 2001	Fushan Bay	<i>N. scintillans</i>	- (small)
11-12 Jun, 2001	Jiaozhou Bay	<i>N. scintillans</i>	5 km ²
7-13 Jul, 2001	Mouth of Jiaozhou Bay	<i>M. rubra</i>	9.8 km ²
28 Jun-2 Jul, 2002	Fushan Bay	<i>M. rubra</i>	60 km ²
Jul, 2003	Jiaozhou Bay	<i>Coscinodiscus asteromphalus</i>	200 km ²
4-10 Jul, 2003	Tuandao Bay, Huiquan Bay	<i>M. rubra</i>	450 km ²
Feb, 2004	Northeast part of Jiaozhou Bay	<i>Guinaradia delicatula</i>	- (small)
9-28 Feb, 2004	East part of Jiaozhou Bay	<i>Rhizosolenia delicatula</i>	70 km ²
22-25 Mar, 2004	Northeast part of Jiaozhou Bay	<i>Thalassiosira nordenskioeldii</i>	70 km ²
Jul, 2004	North part of Jiaozhou Bay	<i>C. asteromphalus</i>	- (small)
10 Aug, 2004	Fushan Bay	<i>M. rubra</i>	50 km ²
12-17 Jun, 2005	Lingshan Bay	<i>Heterosigma akashiwo</i>	80 km ²
Aug, 2006	Fushan Bay	<i>M. rubra</i>	5 km ²
7- 10 Jun, 2007	Shazikou Bay	<i>H. akashiwo</i>	70 km ²
20-23 Aug, 2007	Eastern coastal area	<i>S. costatum</i>	15 km ²
25 -28 Sep, 2007	Shazikou Bay	<i>Gonyaulax spinifera</i>	8 km ²
28-29 Jun, 2008	Jiaozhou Bay	<i>Heterocapsa</i> sp.	5 km ²
7-8 Aug, 2008	Southern coastal area	<i>Chattonella antiqua</i>	86 km ²
26 Aug, 2008	Fushan Bay	<i>N. scintillans</i>	10 km ²

There have been 13 red-tide events in the Dalian coastal area since 1990 (Table 3.5). The dominant species in this area is *N. scintillans*. In Dalian, two bloom events were caused by toxin-producing plankton, *Exuviaella marina* and *Alexandrium catenella*.

Dalian Bay and surrounding areas was a main red tide affected area prior to 2000, and the

Zhuanghe area has become a heavily affected in recent years.

Table 3.5 Recent red-tide events in Dalian coastal area

Occurrence date	Occurrence location	Causative species	Occurrence area
1990	Changhai area	-	-
11 Aug, 1993	Dalian Bay	-	40 km ²
Jul, 1999	Dalian Bay	<i>E. marina</i>	
17-21 Jul, 1999	Dalian Bay	<i>N. scintillans</i>	100 km ²
2 Aug, 2000	Zhuanghe area	-	827 km ²
6 Sep, 2004	Jinshatan	<i>Chattonella marina</i>	-
25 Sep, 2004	Jinshatan	<i>A. catenella</i>	-
25 Jun, 2005	Caotun area	<i>N. scintillans</i>	-
26 Aug-3 Sep, 2005	Zhuanghe area	<i>Chaetoceros affinis</i>	16 km ²
29 Aug-2 Sep, 2005	Zhuanghe area	<i>C. affinis</i>	16 km ²
8 May, 2006	Zhuanghe area	<i>N. scintillans</i>	20 km ²
27 Feb, 2008	Dalian Bay	<i>T. nordenskioeldii</i> , <i>S. costatum</i>	108 km ²
Aug, 2008	Xianghai Bay	<i>C. marina</i>	5 km ²

The number of red-tide events has increased significantly in target sea areas over recent years. Figure 3.1 shows the yearly trend in red-tide events in these areas from 1990 to 2008. Since 1999, the number of red-tide events has increased dramatically. Eighty percent of red-tide events occurred between June and August in the Qingdao region and 75% occurred between July and September in Dalian. The locations of red-tide events in recent years are shown in Figures 3.2a and b.




Figure 3.1 Number of red-tide events in target sea areas in China




Figure 3.2a Locations of red-tide events in the Qingdao coastal area




Figure 3.2b Locations of red-tide events in the Dalian coastal area

3.1.2 Red tides in Japan

There have been 1,407 red-tide events observed in the northwestern sea area of the Kyushu region since 1979. Of these events, 122 caused fishery damage. Figure 3.3 shows the number of red-tide events by year. The annual number of red-tide events has fluctuated between 29 and 92, and highest in 1980. From 2005 to 2008, 278 red-tide events occurred in Japanese target areas (Table 3.6), with 45% of these occurring in the Ariake Sea. Figure 3.4 shows the location of red-tide events in the northwestern sea area of Kyushu and in the Ariake Sea from 2006 to 2008, and Figures 3.5a-c show the location of red-tide events by month in 2006, 2007 and 2008, respectively.

In regards to species that are known to cause fishery damage, *Cochlodinium polykrikoides* was recorded 42 times, its frequency increasing over recent years. *Karenia mikimotoi* was recorded 157 times and has been recorded continuously from 1979 to 2008. *Heterocapsa circularisquama* was recorded 17 times, all after 1996. *Chattonella antiqua* was recorded 12 times, all after 1990. In 2008, fishery damage was small and economic loss was less than one million Japanese yen. In 2006 and 2007 however, fishery damage totaled over 15 million Japanese yen. In recent years, *K. mikimotoi* is a red-tide species that has caused extensive fishery damage.




Figure 3.3 Number of red-tide events in target sea areas in Japan

Table 3.6 Recent red-tide events in the target sea area in Japan

Occurrence date	Occurrence location	Causative species	Occurrence area
20-27 Feb, 2006	Coastal area of Yamaguchi	<i>Noctiluca scintillans</i>	
24 Feb-15 Mar, 2006	West Kyushu	<i>Cryptophyceae</i>	
25-28 Feb, 2006	Coastal area of Yamaguchi	<i>N. scintillans</i>	
1-2 May, 2006	West Kyushu	<i>Strombidium</i> sp.	0.00005 km ²
27-29 Mar, 2006	Coastal area of Yamaguchi	<i>N. scintillans</i>	0.3 km ²
15-26 May, 2006	Goto Islands	<i>Heterosigma akashiwo</i>	0.005 km ²
16 May-29 Jun, 2006	West Kyushu	<i>H. akashiwo</i>	
1-3 Jun, 2006	West Kyushu	<i>Prorocentrum</i> sp.	0.0001 km ²
5-12 Jun, 2006	North Kyushu	<i>N. scintillans</i>	
21-27 Jun, 2006	North Kyushu	<i>Prorocentrum triestinum</i>	
29 Jun, 2006	North Kyushu	<i>Skeletonema</i> sp., <i>Leptocylindrus</i> sp., <i>Chaetoceros</i> sp., <i>P. triestinum</i>	
3-14 Jul, 2006	West Kyushu	<i>K. mikimotoi</i>	
4-12 Jul, 2006	West Kyushu	<i>Ceratium furca</i>	0.44 km ²
8-31 Jul, 2006	West Kyushu	<i>K. mikimotoi</i>	
9-11 Jul, 2006	West Kyushu	<i>Mirionecta rubra</i>	
11-31 Jul, 2006	North Kyushu	<i>Skeletonema</i> sp., <i>Chaetoceros</i> sp.	
13 Jul-4 Aug, 2006	Coastal area of Yamaguchi	<i>K. mikimotoi</i>	50 km ²
14-18 Jul, 2006	West Kyushu	<i>Prorocentrum</i> spp.	0.5 km ²
18-26 Jul, 2006	North Kyushu	<i>K. mikimotoi</i>	
20-22 Jul, 2006	North Kyushu	<i>C. furca</i>	
20-23 Jul, 2006	North Kyushu	<i>M. rubra</i>	
20-25 Jul, 2006	West Kyushu	<i>K. mikimotoi</i>	
20-25 Jul, 2006	Tsushima Island	<i>C. polykrikoides</i>	
21-23 Jul, 2006	North Kyushu	<i>C. furca</i>	
25 Jul-11 Aug, 2006	North Kyushu	<i>K. mikimotoi</i>	
26-30 Jul, 2006	North Kyushu	<i>Nizchia</i> sp. <i>Thalassiosira</i> sp.	
27-30 Jul, 2006	North Kyushu	<i>Skeletonema costatum</i>	
2-11 Aug, 2006	Coastal area of Yamaguchi	<i>K. mikimotoi</i>	
21-25 Aug, 2006	North Kyushu	<i>Thalassiosira</i> sp. <i>S. costatum</i>	
21-25 Aug, 2006	West Kyushu	<i>Prorocentrum minimum</i>	
22-23 Aug, 2006	North Kyushu	<i>Thalassiosira</i> sp.	
6-21 Sep, 2006	West Kyushu	<i>H. akashiwo</i>	
22-26 Sep, 2006	North Kyushu	Diatoms	
11-13 Oct, 2006	North Kyushu	<i>C. polykrikoides</i>	0.25 km ²
16-19 Oct, 2006	Coastal area of Yamaguchi	<i>M. rubra</i>	0.0001 km ²
26 Oct-6 Nov, 2006	West Kyushu	<i>Prorocentrum sigmoides</i>	5.3 km ²
30 Oct-7 Dec, 2006	North Kyushu	<i>P. sigmoides</i>	2.1 km ²
1-3 Nov, 2006	Tsushima Island	<i>M. rubra</i>	

Table 3.6 Continued

Occurrence date	Occurrence location	Causative species	Occurrence area
20-22 Nov, 2006	North Kyushu	<i>P. triestinum</i>	
27-28 Nov, 2006	North Kyushu	<i>P. triestinum</i>	
16-18 Jan, 2007	Tsushima Island	<i>Scrippsiella</i> sp.	
6-9 Feb, 2007	Coastal area of Yamaguchi	<i>N. scintillans</i>	
9-19 Feb, 2007	Coastal area of Yamaguchi	<i>N. scintillans</i>	
8 Mar-9 May, 2007	North Kyushu	<i>Gephyrocapsa oceanic</i>	
23-30 Mar, 2007	Coastal area of Yamaguchi	<i>Noctiluca</i> sp.	
23 Mar-2 Apr, 2007	Goto Islands	<i>N. scintillans</i>	0.0005 km ²
26-30 Mar, 2007	Coastal area of Yamaguchi	<i>Noctiluca</i> sp.	
9-12 Apr, 2007	Coastal area of Yamaguchi	<i>Noctiluca</i> sp.	
19-24 Apr, 2007	Coastal area of Yamaguchi	<i>Noctiluca</i> sp.	
23-30 May, 2007	Coastal area of Yamaguchi	<i>Noctiluca</i> sp.	
25-29 May, 2007	Tsushima Island	<i>H. akashiwo</i>	
5-6 Jun, 2007	Tsushima Island	<i>N. scintillans</i>	
7-12 Jun, 2007	North Kyushu	<i>H. akashiwo</i>	
14-16 Jun, 2007	Tsushima Island	<i>C. furca</i>	
14 Jun-5 Jul, 2007	West Kyushu	<i>K. mikimotoi</i>	
19 Jun-9 Jul, 2007	West Kyushu	<i>K. mikimotoi</i>	
22-27 Jun, 2007	North Kyushu	<i>S. costatum</i>	
24-29 Jun, 2007	Goto Islands	<i>C. furca</i>	0.005 km ²
24 Jun-7 Jul, 2007	Goto Islands	<i>C. furca</i>	0.02 km ²
25-27 Jun, 2007	Goto Islands	<i>C. furca</i>	0.01 km ²
27-29 Jun, 2007	Goto Islands	<i>P. triestinum</i>	0.25 km ²
2-5 Jul, 2007	West Kyushu	<i>K. mikimotoi</i>	
6-9 Jul, 2007	North Kyushu	<i>H. akashiwo</i>	
7-9 Jul, 2007	Tsushima Island	<i>C. furca</i>	
9-16 Jul, 2007	North Kyushu	<i>S. costatum</i> <i>P. triestinum</i> <i>H. akashiwo</i>	
11-23 Jul, 2007	North Kyushu	<i>K. mikimotoi</i> <i>C. polykrikoides</i>	
27-29 Jul, 2007	North Kyushu	<i>N. scintillans</i>	
1-2 Aug, 2007	North Kyushu	<i>N. scintillans</i>	
6-16 Aug, 2007	North Kyushu	<i>Chaetoceros</i> sp. <i>P. triestinum</i>	
22-27 Aug, 2007	West Kyushu	<i>Skeletonema</i> sp.	
23-24 Aug, 2007	North Kyushu	<i>M. rubra</i>	
23-28 Aug, 2007	North Kyushu	<i>Chaetoceros</i> sp. <i>K. mikimotoi</i>	
24-25 Aug, 2007	West Kyushu	<i>P. triestinum</i>	
28 Aug-3 Sep, 2007	West Kyushu	<i>K. mikimotoi</i>	
6-12 Sep, 2007	West Kyushu	<i>K. mikimotoi</i>	
6-11 Sep, 2007	Tsushima Island	<i>Dictyocha fibula</i>	
11-13 Sep, 2007	West Kyushu	<i>Gyrodinium</i> <i>instriatum</i>	

Table 3.6 Continued

Occurrence date	Occurrence location	Causative species	Occurrence area
12-18 Sep, 2007	North Kyushu	<i>Leptocyindrus</i> sp. <i>Chaetoceros</i> sp. <i>Skeletonema</i> sp.	
16-28 Sep, 2007	West Kyushu	<i>P. sigmoides</i>	
20-25 Sep, 2007	North Kyushu	<i>Skeletonema</i> sp. <i>Thalassiosira</i> sp. <i>Chaetoceros</i> sp.	
3-5 Oct, 2007	West Kyushu	<i>P. sigmoides</i>	
15-16 Nov, 2007	North Kyushu	<i>C. polykrikoides</i>	
19-29 Nov, 2007	Goto Islands	<i>M. rubra</i>	
21 Nov, 2007	Tsushima Island	<i>M. rubra</i>	
26-27 Nov, 2007	Goto Islands	<i>M. rubra</i>	
29-30 Nov, 2007	Goto Islands	<i>M. rubra</i>	
29 Nov-6 Dec, 2007	Coastal area of Yamaguchi	<i>M. rubra</i>	0.0001 km ²
1-5 Dec, 2007	Goto Islands	<i>M. rubra</i>	
5-23 Dec, 2007	North Kyushu	<i>M. rubra</i>	
7-19 Dec, 2007	Coastal area of Yamaguchi	<i>M. rubra</i>	0.04 km ²
10-11 Dec, 2007	Goto Islands	<i>M. rubra</i>	
11-12 Dec, 2007	West Kyushu	<i>M. rubra</i>	
12-13 Dec, 2007	West Kyushu	<i>M. rubra</i>	
12-14 Dec, 2007	Coastal area of Yamaguchi	<i>M. rubra</i>	0.02 km ²
12-19 Dec, 2007	Goto Islands	<i>M. rubra</i>	
21-24 Dec, 2007	North Kyushu	<i>Akashiwo sanguinea</i>	
29 Feb, 2008	Coastal area of Yamaguchi	<i>Noctiluca</i> sp.	
6 Mar, 2008	Coastal area of Yamaguchi	<i>Noctiluca</i> sp.	
11 Mar, 2008	Coastal area of Yamaguchi	<i>Noctiluca</i> sp.	
12-17 Mar, 2008	North Kyushu	<i>N. scintillans</i>	
17-18 Mar, 2008	North Kyushu	<i>N. scintillans</i>	
21-22 Mar, 2008	West Kyushu	<i>N. scintillans</i>	
14-30 Apr, 2008	North Kyushu	<i>Gephyrocapsa oceanica</i>	
15 Apr, 2008	Coastal area of Yamaguchi	<i>Noctiluca</i> sp.	
30 Apr-2 May, 2008	North Kyushu	<i>N. scintillans</i>	
8-12 May, 2008	West Kyushu	<i>H. akashiwo</i>	
8-14 May, 2008	North Kyushu	<i>N. scintillans</i>	
15-29 May, 2008	North Kyushu	<i>P. minimum</i> <i>P. dentatum</i>	
15-20 May, 2008	North Kyushu	<i>Leptocylindrus danicus</i>	
28-30 May, 2008	North Kyushu	<i>H. akashiwo</i>	
30-31 May, 2008	West Kyushu	<i>H. akashiwo</i>	
4-13 Jun, 2008	North Kyushu	<i>H. akashiwo</i>	
13-14 Jun, 2008	West Kyushu	<i>Skeletonema</i> sp.	
20-23 Jun, 2008	West Kyushu	<i>M. rubra</i>	
23-30 Jun, 2008	North Kyushu	<i>S. costatum</i>	
23 Jun-2 Jul, 2008	North Kyushu	<i>C. antiqua</i>	

Table 3.6 Continued

Occurrence date	Occurrence location	Causative species	Occurrence area
24-28 Jun, 2008	West Kyushu	<i>Ceratium fusus</i>	
24 Jun-1 Jul, 2008	West Kyushu	<i>H. akashiwo</i>	
24-25 Jun, 2008	North Kyushu	<i>Chaetoceros</i>	
25-27 Jun, 2008	Iki Island	<i>H. akashiwo</i>	0.1 km ²
25 Jun-1 Jul, 2008	North Kyushu	<i>Prorocentrum triestinum</i>	
1-2 Jul, 2008	West Kyushu	<i>Prorocentrum</i> sp.	
2-24 Jul, 2008	West Kyushu	<i>K. mikimotoi</i>	
3-4 Jul, 2008	North Kyushu	<i>P. dentatum</i>	
17-18 Jul, 2008	West Kyushu	<i>H. akashiwo</i>	
23 Jul, 2008	Coastal area of Yamaguchi	<i>K. mikimotoi</i>	
25-26 Jul, 2008	West Kyushu	<i>Rhizosolenia</i> sp.	
26 Jul-21 Aug, 2008	West Kyushu	<i>Chattonella antiqua</i> <i>Chattonella marina</i> <i>C. fusus</i>	
30 Jul, 2008	Coastal area of Yamaguchi	<i>K. mikimotoi</i>	
1-7 Sep, 2008	West Kyushu	<i>M. rubra</i>	171 km ²
4-5 Sep, 2008	Goto Islands	<i>M. rubra</i>	0.03 km ²
10-21 Sep, 2008	West Kyushu	<i>Akashio sanguinea</i> <i>C. fusus</i>	
22-30 Sep, 2008	North Kyushu	<i>C. polykrikoides</i>	
24-28 Sep, 2008	West Kyushu	<i>M. rubra</i>	
30 Sep-1 Oct, 2008	West Kyushu	<i>Heterocapsa circularisquama</i>	
3-15 Oct, 2008	North Kyushu	<i>Skeletonema</i>	
3-9 Oct, 2008	North Kyushu	<i>C. antiqua</i>	
9-10 Oct, 2008	West Kyushu	<i>Skeletonema</i>	
7-27 Nov, 2008	North Kyushu	<i>M. rubra</i> <i>C. polykrikoides</i> <i>A. catenella</i> <i>G. catenatum</i>	
25-26 Nov, 2008	Goto Islands	<i>M. rubra</i>	
26-27 Nov, 2008	Tsushima Island	<i>M. rubra</i>	
3-22 Dec, 2008	Goto Islands	<i>M. rubra</i>	




Figure 3.4 Location of red tides from 2006 to 2008 in target sea areas




Figure 3.5a Location of red-tide events by months in 2006




Figure 3.5b Location of red-tide events by months in 2007




Figure 3.5c Location of red-tide events by months in 2008

3.1.3 Red tides in Korea

Throughout the entire Korean coast, 873 red-tide events have been observed since 1995. Of these, 179 were in Korea's target sea areas. The number of red-tide events has sharply decreased since 2005 however, with less than six events a year (Figure 3.6). After 2005, *C. polykrikoides* blooms have clearly decreased and there have not been any fish killed in the Korean target sea areas since 2008.




Figure 3.6 Annual trend of red-tide events in target sea areas

From 2007 to 2009, 16 red-tide events were recorded on the south coast of Korea (Table 3.7). The most frequently observed species was *C. polykrikoides*, which caused 9 events.

Table 3.7 Recent red-tide occurrence in south coast of Korea

Occurrence date	Occurrence location	Causative species	Occurrence area
24-30 Jul, 2007	Tongyeong Dosan	<i>Akashiwo sanguinea</i>	-
6 Aug-15 Sep, 2007	Namhae Mizo	<i>C. polykrikoides</i>	50 km ²
9 Aug-12 Sep, 2007	Tongyeong Sarang Suyou-do	<i>C. polykrikoides</i>	70 km ²
11 Aug-1 Sep, 2007	Goseong Bay	<i>C. polykrikoides</i>	3 km ²
3-9 Sep, 2007	Jinju Bay	<i>C. polykrikoides</i>	2 km ²
19-29 Oct, 2007	Upper Sarang-do	<i>C. polykrikoides</i>	2 km ²
4 Aug-23 Sep, 2008	Tongyeong Dosan	<i>C. polykrikoides</i>	40 km ²
8 Aug-22 Sep, 2008	Namhae Mizo	<i>C. polykrikoides</i>	60 km ²
16-25 Sep, 2008	Tongyeong Sarang Suyou-do	<i>C. polykrikoides</i>	60 km ²
29 Aug-5 Sep, 2008	Goseong Bay	<i>C. polykrikoides</i>	3 km ²
11-20 Sep, 2008	Jinju Bay	<i>C. polykrikoides</i>	2 km ²
Aug, 2009	Donghae-myeon	<i>C. furca</i>	0.8 km ²
11-19 Aug, 2009	Nam-myeon	<i>A. fraterculus</i>	2 km ²
11-13 Aug, 2009	Tae-do	<i>G. polygramma</i>	3 km ²
24-26 Aug, 2009	Chilcheon-do	<i>S. trochoidea</i>	2 km ²
1-9 Nov, 2009	Sandong eunjeom	<i>Gymnodinium. sp.</i>	0.5 km ²

In Korean target sea areas, more than 60% of red-tide events occurred between July and August, with *C. polykrikoides* being the major causative species. Another fish killing species, *Chattonella* spp., also occurred between July and August along west coast. The duration of red-tide events was between 5 and 50 days, and varied significantly depending on the causative species. *C. polykrikoides* lasted between 22 and 50 days, while other dinoflagellates lasted between 5 and 11 days. The longer duration of *C. polykrikoides* events than other dinoflagellates, is thought to be related to the greater availability of nutrients offshore, which are supplied by currents. *C. polykrikoides* also spread to neighboring areas by wind or currents where nutrients were abundant.

Figure 3.7a-d shows the spatial distribution of red-tide affected areas from 2007 to 2009.




Figure 3.7a Spatial distribution of HABs in 2007
(red areas indicate HAB-affected dimensions).




Figure 3.7b Cumulative spatial distribution of HABs in 2008
(red areas indicate HAB-affected dimensions).




Figure 3.7c Changes in HAB affected areas every half a month
(red areas indicate HAB-affected dimensions).




Figure 3.7d Spatial distribution of HABs in 2009
(red areas indicate HAB-affected dimensions)

3.1.4 Red tides in Russia

In Russian target sea areas, 53 red-tide events and a total of 20 red-tide species have been observed since 1991. No cases of fishery damage have been recorded. Most red-tide events occurred in Amurskii Bay and Vostok Bay. In Aniva Bay, one *Heterosigma akashiwo* red-tide event was recorded. Figure 3.8 shows the annual trend of red-tide events in target sea areas. In recent years, red-tide events have occurred consistently in the area.

Table 3.8 and Figures 3.9 a-c indicate the location and causative species of red-tide events in target sea areas.




Figure 3.8 Annual trend of red-tide events in target sea areas

Table 3.8 Recent red-tide occurrences in Amurskii Bay, Vostok Bay and Aniva Bay

Occurrence date	Occurrence location	Causative species	Occurrence area
8 Jul-12 Aug, 1991	Amurskii Bay	<i>Prorocentrum minimum</i>	
19 Nov, 1993	Amurskii Bay	<i>Chattonella</i> sp.	
28 Feb, 1996	Amurskii Bay	<i>Heterosigma akashiwo</i>	
2-16 Jul, 1996	Amurskii Bay	<i>Noctiluca scintillans</i>	
8 Jul-30 Aug, 1996	Amurskii Bay	<i>Chaetoceros affinis</i>	
5-12 Aug, 1996	Amurskii Bay	<i>Chaetoceros curvisetus</i>	
4 Nov-16 Dec, 1996	Amurskii Bay	<i>Leptocylindrus minimus</i>	
22 Jul-30 Aug, 1996	Amurskii Bay	<i>Skeletonema costatum</i>	
4 May-4 Jun, 1997	Amurskii Bay	<i>Chaetoceros contortus</i>	
29 Jul, 1997	Amurskii Bay	<i>Thalassiosira mala</i>	
19-28 Aug, 1997	Amurskii Bay	<i>Protoceratium reticulatum</i>	
5-12 Mar, 1998	Amurskii Bay	<i>Plagioselmis</i> sp.	
26 Jan-17 Feb, 1998	Amurskii Bay	<i>Thalassiosira nordenskioeldii</i>	
13 Aug, 2001	Aniva Bay	<i>H. akashiwo</i>	
16 Aug, 2001	Vostok Bay	<i>S. costatum</i>	
30 Sep, 2001	Vostok Bay	<i>Asterionellopsis glacialis</i>	
14 Jul, 2002	Vostok Bay	<i>Chatonella globosa</i>	

Table 3.8 Continued

Occurrence date	Occurrence location	Causative species	Occurrence area
23 Apr, 2003	Vostok Bay	<i>Heterocapsa rotundata</i>	
17 Nov, 2004	Amurskii Bay	<i>Chaetoceros salsugineus</i>	
12 Jul, 2005	Amurskii Bay	<i>Euglena pascheri</i>	
1 Sep, 2005	Vostok Bay	<i>H. akashiwo</i>	
5 Jun-3 Jul, 2006	Amurskii Bay	<i>Thalassionema nitzschiooides</i>	
4 Aug, 2006	Vostok Bay	<i>H. akashiwo</i>	
20 Aug, 2006	Vostok Bay	<i>S. costatum</i>	
6-20 Aug, 2007	Amurskii Bay	<i>S. costatum</i>	
8 Aug, 2007	Vostok Bay	<i>H. akashiwo</i>	
20 Aug, 2007	Amurskii Bay	<i>H. akashiwo</i>	
30 Oct, 2007	Amurskii Bay	<i>H. akashiwo</i>	
7 Jun, 2008	Amurskii Bay	<i>H. akashiwo</i>	
29 Aug, 2008	Amurskii Bay	<i>P. minimum</i>	
15 Sep, 2008	Amurskii Bay	<i>P. reticulatum</i>	
11 Jan, 2009	Amurskii Bay	<i>P. reticulatum</i>	
8 Jun, 2009	Amurskii Bay	<i>P. reticulatum</i>	
4 Jul, 2009	Vostok Bay	<i>Nitzschia hybrid f. hyalina</i>	
2 Aug, 2009	Amurskii Bay	<i>P. triestinum</i>	
9 Sep, 2009	Amurskii Bay	<i>P. minimum</i>	
30 Mar, 2010	Amurskii Bay	<i>H. akashiwo</i>	
30 Jul, 2010	Amurskii Bay	<i>Dactyliosolen fragilissimus</i>	



Figure 3.9a Location of red-tide events in Amurskii Bay




Figure 3.9b Location of red-tide events in Vostok Bay



Figure 3.9c Location of red-tide events in Aniva Bay

3.2 Toxin-producing plankton and shipment stoppage in the target sea areas

Table 3.9 shows the status of toxin-producing plankton and damage caused to fisheries and human health in the target sea areas of each member state. In this report, toxin-producing species are separated into paralytic shellfish poisoning (PSP), diarrhetic shellfish poisoning (DSP) and amnesic shellfish poisoning (ASP) inducing species, rather than their taxonomic classification. All of the NOWPAP member states regularly monitor the status of shellfish toxin, and toxin producing plankton species of PSP, DSP and/or ASP events.

A total of 20 toxin-producing plankton species were recorded in the last ‘HAB Integrated Report’. In the ‘HAB Case Study Reports’, the number of toxin-producing plankton species decreased to a total of 18 species including, 4 new *Pseudo-nitzschia* species (Table 3.10).

Six species were PSP-inducing species, including *Alexandrium* spp. and *Gymnodinium catenatum*. The most commonly recorded PSP species in the NOWPAP Region was *A. tamarens*e, but in recent years *G. catenatum* has induced more PSP contamination in Japan.

The PSP species, *A. tamarens*e, *A. catenella* and *G. catenatum* were reported in the ‘HAB Case Study Report’ of all NOWPAP member states. In China, Korea and Russia, poisoning is not recorded. However, in Japan PSP was detected 13 times from 2006 to 2008. In four of these cases, shipment stoppage was imposed as the toxin level exceeded the safety limit.

Nine of the ten DSP species recorded in the NOWPAP Region belong to the genus *Dinophysis*. The other was *Exuviaella marina*, which was recorded only in China. Among the *Dinophysis* species, *D. fortii* and *D. acuminata* were recorded in all of the NOWPAP member seas. In the ‘HAB Case Study Report’, *Dinophysis* species were reported in Japan and Russia.

DSP species have been recorded in China, Japan and Russia.

In the Dalian Bay in China, an *E. marina* bloom occurred and DSP was detected. However, no damage to fisheries or human health by this poisoning was reported.

Damage from DSP was not recorded in Japan during 2006-2008 and Russia has not been affected by DSP as of yet.

ASP-inducing *Pseudo-nitzschia* species were mainly recorded in Russia. In Korea, only *Pseudo-nitzschia pungens* were observed. ASP-inducing species probably also exist in China and Japan, but they are not targeted in regular monitoring. In the NOWPAP region, the damage caused by ASP has not been reported to date, but this should be investigated in the future.

Table 3.9 Status of toxin-producing plankton and damage to fisheries and human health in the target sea areas of the NOWPAP member state

	China	Japan	Korea	Russia
Targeted toxin-producing species in regular monitoring	<i>Alexandrium tamarense</i>	<i>A. tamarense</i> , <i>A. catenella</i> , <i>Gymnodinium catenatum</i> , <i>Dinophysis fortii</i> , <i>D. acuminata</i> , <i>D. caudata</i>	No targeted species	<i>A. tamarense</i> , <i>Dinophysis fortii</i> , <i>D. acuminata</i> , <i>D. acuta</i> , <i>D. norvegica</i> , <i>D. rotundata</i> , <i>Protoceratium reticulatum</i> <i>Pseudo-nitzschia calliantha</i> , <i>P. delicatissima</i> , <i>P. fraudulenta</i> , <i>P. multistriata</i> , <i>P. multiseries</i> , <i>P. seriata/pungens</i> ,
Observed toxin-producing species in recent years	<i>A. catenella</i> <i>Exuviaella marina</i>	<i>A. catenella</i> <i>G. catenatum</i> <i>D. fortii</i> <i>D. acuminata</i> <i>D. caudata</i>	<i>G. catenatum</i> <i>Pseudo-nitzschia pungens</i>	<i>A. tamarense</i> <i>D. fortii</i> <i>D. acuminata</i> , <i>D. acuta</i> <i>D. norvegica</i> , <i>D. rotundata</i> <i>Pseudo-nitzschia calliantha</i> <i>P. multiseries</i> , <i>P. pseudodelicatissima</i> <i>P. pungens</i> , <i>P. delicatissima</i> <i>P. fraudulenta</i> , <i>P. multistriata</i> <i>P. seriata</i>
Affected species	No information	PSP: <i>Mytilus galloprovincialis</i> , <i>Crassostrea gigas</i> , <i>Chlamys senatoria nobilis</i> DSP: <i>Mytilus galloprovincialis</i> , <i>Mizuhopecten yessoensis</i>	No information	PSP: <i>Mizuhopecten yessoensis</i> DSP: <i>Crenomytilus grayanus</i> , <i>Mytilus trossulus</i> ASP: <i>Crenomytilus grayanus</i> , <i>Mytilus trossulus</i> , <i>Mizuhopecten yessoensis</i>
Damage	In 1999, damage to human health by DSP occurred.	DSP exceeded safety limit caused by <i>G. catenatum</i> in the Sensaki Bay in 2006, 2007 and 2008, in the Yuya Bay in 2007 and in the Tamanoura Bay in 2007.	No shellfish poisoning was reported	No damage to fisheries or human health was reported, however, toxin levels higher than the standard were observed in each area.
Mitigation measures	Regular monitoring to check abundance of toxin producing species and toxin content in shellfish meat. PSP toxin safety limit is 80 µg(saxitoxin)/100 g meat.	Regular monitoring to check abundance of toxin producing species and toxin content in the shellfish meat. PSP toxin safety limit is 4 MU/g wet weight of meat. DSP toxin safety limit is 0.05 MU/g wet weight of meat. In principal, shipment of shellfish will be stopped until the toxin levels return to acceptable levels for three consecutive inspections.	Regular monitoring to check abundance of toxin producing species and toxin content in the shellfish meat at over 100 stations around shellfish aquaculture farms. PSP toxin safety limit is 80 µg/100 g meat.	Regular monitoring to check abundance of toxin producing species and toxin content in the shellfish meat. PSP toxin safety limit is 0.8 mg(saxitoxin)/kg meat. DSP toxin safety limit is 0.16 mg(okadaic acid)/kg meat. ASP toxin safety limit is 20 mg(domestic acid)/kg meat for mollusks and 30 mg(domestic acid)/kg meat for crab's internal.

Table 3.10 Toxin-producing plankton species recorded in the NOWPAP region

	Species name	China	Japan	Korea	Russia
PSP	<i>Alexandrium acatenella</i>				(✓)
	<i>Alexandrium tamarensense</i>		(✓)	(✓)	(✓) ✓
	<i>Alexandrium catenella</i>	(✓) ✓	(✓) ✓		
	<i>Alexandrium pseudogonyaulax</i>				(✓)
	<i>Alexandrium tamiyavanichii</i>		(✓)		
	<i>Gymnodinium catenatum</i>	(✓) ✓		✓	
DSP	<i>Dinophysis fortii</i>	(✓)	(✓) ✓	(✓)	(✓) ✓
	<i>Dinophysis acuminata</i>	(✓)	(✓) ✓	(✓)	(✓) ✓
	<i>Dinophysis acuta</i>			(✓) ✓	
	<i>Dinophysis caudata</i>	(✓) ✓			
	<i>Dinophysis infundibulus</i>		(✓)		
	<i>Dinophysis mitra</i>		(✓)		
	<i>Dinophysis norvegica</i>			(✓) ✓	
	<i>Dinophysis ovata</i>	(✓)			
	<i>Dinophysis rotundata</i>		(✓)	(✓)	(✓) ✓
	<i>Exuviaella marina</i>	(✓) ✓			
ASP	<i>Pseudo-nitzschia calliantha</i>			(✓) ✓	
	<i>Pseudo-nitzschia multiseries</i>			(✓) ✓	
	<i>Pseudo-nitzschia pseudodelicatissima</i>			(✓) ✓	
	<i>Pseudo-nitzschia pungens</i>		(✓) ✓	(✓) ✓	
	<i>Pseudo-nitzschia delicatissima</i>				✓
	<i>Pseudo-nitzschia fraudulenta</i>				✓
	<i>Pseudo-nitzschia multistriata</i>				✓
	<i>Pseudo-nitzschia seriata</i>				✓

Parentheses indicate that the species was reported in the last HAB Integrated Report.

3.3 Common issues on HABs in the NOWPAP region

3.3.1 Severe fishery damage caused by *Cochlodinium polykrikoides*

Red tides have frequently resulted in large mortality rates in fishery resources and huge economic loss to fisheries in the NOWPAP Region. For example, in 1999 approximately USD7 million of fishery damage was recorded in Imari Bay, Kyushu, Japan. Even greater economic losses were recorded in Korea in 1995 and 2003, worth approximately USD95 million and USD19 million, respectively. Red tides often occur in semi-enclosed areas, such as inlets and embayments, where aquaculture often operates. Although various species are known to cause red tides, *C. polykrikoides* has caused the most damage to fisheries in Japan and Korea in recent years. In Korea, *C. polykrikoides* is the causative species of all HAB events in the last 15 years.

Since 2005, *C. polykrikoides* blooms have occurred frequently in Japan and Korea, but the number of occurrences and damage to fisheries has decreased in the past years. The locations of *C. polykrikoides* blooms in the Japanese and Korean regions are plotted in Figure 3.10, the data of which are derived from national reports, recent research papers and the ‘HAB Case Study Reports’.

To prevent or reduce future damage from *C. polykrikoides*, various studies have been conducted to understand the ecology of the species. Several studies have focused on the transportation mechanisms of *C. polykrikoides*. Miyahara et al. (2005) traced the movement of *C. polykrikoides* blooms along the Sea Area A coast in the Chugoku region in 2003, by referring to satellite images showing chlorophyll-a concentration (field measurements verified that the high chlorophyll-a concentration in the satellite images was predominantly due to *C. polykrikoides*). Figure 3.11 shows how the *C. polykrikoides* blooms moved along the coast of the Chugoku region. Miyahara et al. concluded that this particular bloom was most likely transported to the coast of the Chugoku region through the Tsushima Warm Current.

Kim et al. (2004) studied the impact of water temperature, salinity and irradiance on the growth rate of *C. polykrikoides*. The highest growth rate was recorded when the water temperature was 25 °C, salinity was 34 ppt and irradiance was >90 µmol/m²/s. Such physical parameters might explain the *C. polykrikoides* blooms in the Japanese (Kyushu) and Korean regions, all of which occurred between August and October when the water temperature was close to 25 °C. However, optimum growth conditions for *C. polykrikoides* require further investigation through the collection of field data.

To predict and provide warning of *C. polykrikoides* blooms based on the scientific data, Korea conducts specific *C. polykrikoides* monitoring. This monitoring is conducted before, during and after *C. polykrikoides* blooms, usually from June to October. For detection of the spatial distribution of *C. polykrikoides* blooms, satellite images of SST and Chlorophyll-a are applied. *C. polykrikoides* blooms in Korea occur over huge scales in offshore areas. The information on SST and Chlorophyll-a are helpful parameters for the prediction of *C. polykrikoides* blooms. In 2008, *C. polykrikoides* blooms tens of kilometers long were detected using satellite images (Table 3.11).

3.3.2 Fishery damage caused by *Chattonella antiqua* in Yatsushiro Sea

Since 2008, Fishery damage caused by *C. antiqua* has been quite serious in the Yatsushiro Sea. The Yatsushiro Sea, outside of the NOWPAP region, is adjacent to the Ariake Sea and contains many aquaculture farms. In 2008, the amount of fishery damage was 184 million Japanese yen (about 2 million USD). The damage increased to 2.9 billion Japanese yen in 2009 and 5.3 billion in 2010. The damage caused by *C. antiqua* expanded throughout the Ariake Sea and Omura Bay. *C. antiqua*

is the species of greatest concern in the Kyushu region.




Figure 3.10 Locations of *C. polykrikoides* blooms in Japan and Korea

Blue circles indicate locations of *C. polykrikoides* blooms before 2005. Red circles indicate blooms after 2005.

Sources: NOWPAP CEARAC (2005); Integrated Report on HABs for the NOWPAP Region
Yoon Y. H. (2001); A summary on the red-tide mechanisms of the harmful dinoflagellate, *Cochlodinium polykrikoides* in Korean coastal waters, Bull. Plankton Soc. Japan, 48 (2): 113–120.

Matsuoka K. (2004); Present status in study on a harmful unarmored dinoflagellate *Cochlodinium polykrikoides* Margalef., Bull. Plankton Soc. Japan, 51 (1): 38–45.







Figure 3.11 Movement of *C. polykrikoides* blooms along the coast of the Chugoku Region in Sea Area A

Note: The movement of *C. polykrikoides* blooms along the coast of the Chugoku region from September 4 to 7 is clearly seen in green. The spread of primary production on September 16 and 18 is thought to be caused by the typhoon on September 12.

Source: Miyahara et al. (2005): A harmful bloom of *Cochlodinium polykrikoides* Margalef (Dinophyceae) in the coastal area of San-in, western part of the Japan Sea, in September 2003, Bull. Plankton Soc. Japan, 52(1), 11–18.

Table 3.11 Satellite images during HAB events in the South Sea of Korea

Year	Event No.	Duration	Area	SST, nLw 551, Chl-a
2008	SE-2008-1	2 Aug, 2008	South Sea of Korea	 <p>Daily composite Image of SST NOAA Satellite, 2008.08.02.NFRDI, KOREA.</p> <p>0 10 20 30 40 °C</p>
2008	SE-2008-1	2 Aug, 2008	South Sea of Korea	 <p>AQUA-1 MODIS nLw-551 2008.08.02.NFRDI, KOREA</p> <p>mW/cm² /μm/sr</p> <p>0.3 0.6 0.9 1.2 1.5 1.8 2.1 2.4 2.7</p>
2008	SE-2008-1	2 Aug, 2008	South Sea of Korea	 <p>AQUA-1 MODIS Chlorophyll 2008.08.02.NFRDI, KOREA</p> <p>mg/m³</p> <p>0 0.5 1 1.5 2 2.5</p>

3.3.3 Threats from PSP and DSP

Shellfish poisoning is a common threat in the NOWPAP Region. In China, more than 600 people have suffered shellfish poisoning since 1967, of which 30 cases were fatal. The majority of these fatalities were from PSP. In Japan, approximately 900 people have suffered from DSP and PSP poisoning since monitoring began. In Korea, shipping of shellfish was temporarily suspended in 2002 and 2003 due to PSP. Although there have been no reports of shellfish poisoning in Russia, the presence of various toxin-producing species has been recorded in Russian waters. Shellfish poisoning in Russia could become a major threat in the future, particularly due to the expansion of their aquaculture industry.

3.3.4 The new issue by massive blooms of green macroalgae *Ulva prolifera*

Green tides, which are caused by huge volumes of green macroalgae, have been reported in many parts of the world. Such green macroalgae blooms are not directly harmful to fisheries or human health, but macroalgae often grow rapidly and huge volumes become stranded on the coast. In such cases, stakeholders have to remove them in order to keep the coast clean and safe. In recent years, such macroalgae blooms have become an issue of concern throughout the world.

In 2008, massive green macroalgae (*Ulva prolifera*) blooms occurred in the Yellow Sea and the East China Sea and became stranded in the coastal area of Qingdao. This bloom covered an area of about 2,400 km² and the total volume removed reached 1 million tons (Hu and He 2008). A similar massive bloom (1,600 km²) occurred in 2009 (Hu et al. 2010). In 2008, the removal and treatment of such a large volume of *U. prolifera* cost more than USD100 million. Some scientists hypothesize that the cause of *U. prolifera* is the aquaculture of seaweed in the coastal waters of Jiangsu Province (Hu 2009; Liu et al. 2009). The study of the source of *U. prolifera* is implemented using satellite images and numerical simulation.

It is also thought that macroalgae blooms are related to eutrophication. In the NOWPAP region, eutrophication is a serious environmental issue. It is expected that improving the marine environment in this region will prevent green-tide damage.

4 Challenges for studies to cope with HABs

To prevent damage by HABs, appropriate countermeasures should be conducted. The first step, and maybe the last step, is to create a marine environment where HABs cannot occur. The ideal environment is the one where appropriate nutrients levels are maintained and a natural material cycle occurs. However, in determining whether the environment is appropriate, it is necessary to monitor not only the water quality, but also condition of material cycle in environment. Even if the appropriate environment is created, HABs may occur. Therefore, it is important to reduce the risks as much as possible. As of now, the reduction of nutrient loads from the land has been a primary focus, but it is desirable to develop and improve measures which take into consideration an area's ecosystems.

The second step is to detect HABs in their early stage, and to conduct countermeasures before they grow. If early detection is possible, early announcement and/or warnings can be made, giving fishermen sufficient time to implement countermeasures. Some methods for detecting HABs in their early stage, using molecular genetic techniques and remote sensing techniques, are studied increasingly using *in situ* application. Molecular genetic techniques and remote sensing techniques are introduced in sections 4.1 and 4.2.

The final step is to develop and apply countermeasures to prevent damage when red tides occur. The NOWPAP region has experienced serious fishery damage in the past, and through them, various countermeasures have been developed. Countermeasures against red tides can be classified broadly as either direct or indirect measures. Direct measures are implemented directly against red-tide causative species. These countermeasures eliminate HABs through physical, chemical or biological control. Indirect measures, on the other hand, include methods such as moving fish cages from red-tide areas. There are currently no countermeasures available to prevent the poisoning of fish or shellfish by toxin-producing plankton. Instead, countermeasures focus on preventing the poisoning of consumers by, for example, regular safety inspections and shipping restrictions. Information on countermeasures in the NOWPAP region is summarized in the 'Booklet of Countermeasures against Harmful Algal Blooms in the NOWPAP Region' (http://www.cearac-project.org/wg3/publications/HAB_Booklet.pdf).

Removing causative species from water is another countermeasure option. In Korea, countermeasures to remove causative species using a centrifugal separation system have been applied. New ballast water treatment technologies are also useful for reducing the damage of HABs.

4.1 Remote sensing techniques

Satellites are useful tools for red-tide monitoring and offer the ability to obtain information from wider areas. Although there are some challenges, such as the difference in size between the actual red tide and the resolution of the satellite image and interference from clouds, satellites are utilized to monitor red tides in the NOWPAP region (Tang et al. 2003; Ishizaka et al. 2006; Ahn et al. 2006). In Korea, satellites are one of the most effective tools for monitoring *Cochlodinium*.

In addition to being used to identify the distribution of different Chlorophyll-*a* concentrations on the seas surface and estimating areas of red-tide occurrences, satellite images have been recently used as a tool for determining red tides by different wavelength ranges (He et al. 2008; Takahashi et al. 2009).

As high resolution images such as ALOS become available, it is expected that red-tide monitoring with satellite images will increase globally. Satellites can increasingly be used for species identifying, which was previously difficult to do. Global Ecology and Oceanography of Harmful Algal Blooms (GEOHAB) established a new Working Group to increase research in this area.

Satellite images are used not only for monitoring but also for forecasting the movement of red tides

and thereby reducing red-tide damage. When a red tide occurs close to marine culture areas, it may drift on ocean currents and damage these areas. The course of the red tide's movement can be forecast by the flow field and distribution of a red tide using satellite images. Appropriate countermeasures, such as moving preserves and feed withdrawal, can then be taken. These approaches are currently being tested and, when established, recommendations aimed at damage prevention will be provided.

In addition, more studies on understanding red tides by combining in situ monitoring with remote sensing monitoring and numerical simulation have been promoted (Onitsuka et al. 2010). In the NOWPAP region, there have been incidents of red-tide damage to areas remote from the area where the red tides first occur. For example, when *Cochlodinium* red tide occurred along the Korean coastal waters and was transferred by the current to the coastal area of Japan, the Sanin region was damaged by the red tide. Such trans-boundary transfer of red tide can be forecast using satellite images and numerical simulation. The application of these techniques can lead to the minimization of damage. It is therefore expected that there will be an advancement in these technologies.

4.2 Molecular genetic techniques

Most important in preventing red-tide damage is the early identification of the causative species and its cell density, as well as taking appropriate countermeasures. The shorter the time it takes to identify the species on site and calculate the cell density, the less damage HABs will cause to the sea area. However, not all the people conducting HAB monitoring are familiar with species identification. In situ prompt identification and measurement of cell numbers requires a high level of expertise. It is therefore necessary to develop an easy and fast way of species identification and cell density measurement which any person can apply.

At present, a molecular biological approach using a unique DNA marker of each species is applied. Fluorescent In Situ Hybridization (FISH) method, real-time Polymerase Chain Reaction (PCR) and Loop-Mediated Isothermal Amplification (LAMP) methods are based on this approach. The FISH method detects the presence or absence of target plankton in the sea by designing complementary probes in DNA markers on species-specific rRNA which are marked with fluorescent pigment. The degree of fluorescence allows the approximate cell number to be estimated (Hosoi-Tanabe and Sako 2006; Takao et al. 2007; Nishitani et al. 2007). Another common method is real-time PCR (Kamikawa et al. 2005, 2006; Kai et al. 2006; Kamikawa et al. 2007). Different from the FISH method, the real-time PCR method identifies species by primers with a peculiar DNA marker. Real-time PCR is also used for identifying cysts, so it is appropriate for species developing cysts and for identifying the presence of cysts in sediment.

The LAMP method is the most simple. It can amplify target gene sequences at a given temperature (around 65 °C) without special reagent or tools. As the efficiency of amplification is good, it is possible to identify species at a low cost.

These methods set probes and primers for each plankton. There are probes developed for many species. These methods can be applied to detect the presence of specific plankton species which are difficult to identify by their shape. People without species identification knowledge can undertake these tests. They are therefore commonly used throughout the world.

Until recently, Mouse Assay and High Speed Liquid Chromatography have been popular methods for detecting shellfish poisoning. However, the recently developed Enzyme Linked Immunosorbent Assay (ELISA) method, which uses biological techniques, has become quicker and easier (Kawatsu et al. 2002). This method is to set the detective quantification of an antigen by checking the enzyme reaction. Using this method, OA, DTX1, 2 and 3 can be detected quickly and accurately.

Various studies have been conducted on the HAB causative species in the NOWPAP region. These include the identification of populations distributed in each sea area at gene level, understanding how they transfer to other sea areas, the expansion of their distribution and associated mechanisms

(Hosoi-Tanabe et al. 2006; Kim and Kim 2007; Kim et al. 2008; Iwataki et al. 2008; Mikulaki et al. 2008; Nagai et al. 2009). A new method focusing on microsatellites, molecular markers with advanced polymorphism, is under development in order to understand the status of transfer by genetic variation in one species (Nagai et al. 2006A, B).

All of the above mentioned methods are useful for quick identification of red tide and shellfish poisoning causative species. Allowing a person without any profound knowledge to identify causative species can lead to quick responses to red-tide occurrences and can reduce damage. Simple low cost methods need to be developed.

5 Conclusion

Considering that all of the NOWPAP member states have conducted regular red tide and toxin-producing plankton monitoring, CEARAC has constructed a system to monitor HABs and regularly share information on HAB events in the region. Through sharing information and knowledge on HABs, it is expected that each member state will enhance its measures against HABs.

Although the number of HAB events in the NOWPAP region has decreased compared with decades ago, HABs still cause significant damage to fisheries. There is also the new issue of Macroalgal blooms in the region. To prevent HAB damage, it is necessary to understand the status and mechanism of these events, and to address them using existing and new technologies and methods (see countermeasures introduced in Chapter 4). Some technologies are still being developed, and their establishment will contribute to a reduction in HAB damage in the region.

The problem with these countermeasures is that they are only a response to events that have occurred. Thus, it is also necessary to create an environment where red tides are unlikely to occur. Rapid economic development in the surrounding countries, the concentration of populations along the coastal areas and the increase in agricultural production cause eutrophication, a major problem in the region, and a cause of red tides. In order to prevent red tides, it is therefore necessary to reduce the amount of eutrophication in the NOWPAP region, and to remediate the environment in the area to its natural nutrient levels and natural material circulation.

Taking the present status and goals into consideration, CEARAC developed the common procedure for evaluating the status of eutrophication in the NOWPAP region, and implemented assessments in the target sea areas of each NOWPAP member state. Assessment indicators include direct factors, such as nutrient enrichment (e.g. nutrient concentration in the sea area), nutrient input from land, the number of red-tide occurrences and chlorophyll-a concentration. This assessment method recommends analysis of both the current status and trends. Through these activities, the status of eutrophication in the NOWPAP region will improve in near future.

Through these assessments, each member state understands their individual challenges, and countermeasures will be tailored to improve the status of eutrophication and to reduce red-tide occurrences in the region.

Problems of eutrophication however, cannot be solved by mere reduction of nutrient loads. In Japan, for example, despite the reduction of land-based nutrient loads, the number of red-tide occurrences has not significantly decreased. This may be because current marine ecosystem conditions are not the same as they used to be. Another reason may be the deteriorated process of material circulation in the marine environment caused by human activities.

In order to solve HAB problems and to develop and apply effective countermeasures in the NOWPAP region, it is necessary to improve the status of eutrophication and to improve knowledge on the status of ecosystems including HAB causative species.

In recent years, environmental issues such as the treatment of ballast water and marine biodiversity have received more global attention. There are many busy ports in the NOWPAP region, and many ships are crossing the seas. Shipping density has steadily increased since the early 1990's due to increasing intra-regional trade. For this reason, the region is threatened with invasive species including new HAB causative species. Such non-indigenous species could lead to ecological disorder and increased HAB damage. Therefore, it will be desirable to take action against such environmental issues.

References

- Ahn, Y-H., P. Shanmugam, J-H Ryu and J-C Jeong (2006): Satellite detection of harmful algal bloom occurrences in Korean water. *Harmful Algae*, 5, 213-231.
- EMECS (2003): Environmental Guidebook on the Enclosed Water Bodies of the World,
- Hosoi-Tanabe, S., I. Otake and Y. Sako (2006): Phylogenetic analysis of noxious red tide flagellates *Chattonella antiqua*, *C. marina*, *C. ovata* and *C verruculosa* (Raphidophyceae) based on the rRNA gene family, *Fisheries Sci.*, 72, 1200-1208
- Hosoi-Tanabe, S. and Sako Y. (2006): Development and application of fluorescence in situ hybridization (FISH) method for simple and rapid identification of the toxic dinoflagellates *Alexandrium tamarense* and *Alexandrium catenella* in cultured and natural seawater. *Fish. Sci.*, 72, 77-82
- Hu C. (2009): A novel ocean color index to detect floating algae in the global oceans. *Remote Sens. Environ.*, 113, 2118-2129
- Hu C. and M-X. He (2008): Origin and offshore extent of floating algae in Olympic sailing area. *Eos Trans. AGU*, 89, 302-303
- Hu C., D. Li, C. Chen, J. Ge, F. E. Muller-Karger, J. Liu, F. Yu and M-X. He (2010): On the recurrent *Ulva prolifera* blooms in the Yellow Sea and East China Sea. *J. Geophys. Res.*, 115, C05017
- Ishizaka J., Y. Kitaura, Y. Touke, H. Sasaki, A. Tanaka, H. Murakami, T. Suzuki, K. Matsuoka and H. Nakata (2006): Satellite Detection of Red Tide in Ariake Sound, 1998-2001. *J. Ocean.*, 62, 37-45
- Iwataki, M., H. Kawami, K. Mizushima, C. M. Mikulski, G. J. Doucette, J. R. Relox, A. Anton, Y. Fukuyo and K. Matsuoka (2008): Phylogenetic relationships in the harmful dinoflagellate *Cochlodinium polykrikoides* (Gymnodiniales, Dinophyceae) inferred from LSU rDNA sequences. *Harmful Algae*, 7, 271-277
- Kai, A., Y. K. Cheung, P. K. K. Yeung and J. T. Y. Wong (2006): Development of single-cell PCR methods for the Raphidophyceae. *Harmful Algae*, 5, 649-657
- Kawatsu K., Y. Hamano, A. Sugiyama, K. Hashizume and T. Noguchi (2002): Development and application of an enzyme immunoassay based on a monoclonal antibody against gonyautoxin components of paralytic shellfish poisoning toxins., *J. Food Protection*, 65, 1304-1308
- Kamikawa R., S. Hosoi-Tanabe, S. Nagai, S. Itakura and Y. Sako (2005): Development of a quantification assay for the cysts of the toxic dinoflagellate *Alexandrium tamarense* using real-time polymerase chain reaction. *Fish. Sci.*, 71, 987-991
- Kamikawa R., J. Asai, T. Miyahara, K. Murata, K. Oyama, S. Yoshimatsu, T. Yoshida and Y. Sako (2006): Application of a real-time PCR assay to comprehensive method for monitoring harmful algae. *Microbes Environ.*, 21, 163-173
- Kamikawa, R., S. Nagai, S. Hosoi-Tanabe, S. Itakura, M. Yamaguchi, Y. Uchida, T. Baba and Y. Sako (2007): Application of real-time PCR assay for detection and quantification of *Alexandrium*

- tamarens* and *Alexandrium catenella* cysts from marine sediments. Harmful Algae, 6, 413-420
- Kim, K. Y. and Kim, C. H. (2007): Phylogenetic relationships among diverse Dinoflagellate species occurring in coastal waters off Korean inferred from large subunit ribosomal DNA sequence data. Algae, 22, 57-67
 - Kim, K. Y., M. Iwataki and C. H. Kim (2008): Research Note: Molecular phylogenetic affiliations of *Dissodinium pseudolunula*, *Pheophykklos hartmannii*, *Polykrikos* cf. *schwartzii* and *Polykrikos kofoidii* to *Gymnodinium sensu stricto* species (Dinophyceae). Phycological Res., 56, 89-92
 - Liu D., J. K. Keesing, Q. Xing and P. Shi (2009): World's largest macroalgal bloom caused by expansion of seaweed aquaculture in China. Mar. Sci. Bulletin, 58, 888-895
 - Matsuoka K. (2004): Present status in study on a harmful unarmored dinoflagellate *Cochlodinium polykrikoides* Margalef. Bull. Plankton Soc. Japan, 51, 38-45
 - Mikulski, C. M., Y. T. Park, K. L. Jones, C. K. Lee, W. A. Lim, Y. Lee, C. A. Scholin and G. J. Doucette (2008): Development and field application of rRNA-targeted probes for the detection of *Cochlodinium polykrikoides* Margalef in Korean coastal waters using whole cell and sandwich hybridization formats. Harmful algae, 7, 347-359
 - Ming-Xia He, Y. Wang, L. Hu, Q. Yang, S. He, C. Hu and R. Doerffer (2008): Detection of Red Tides Using MERIS 681 nm and 709 nm Bands in the East China Sea: A Case Study. Proc. Dragon 1 Programme Final Results 2004-2007.
 - Ministry of Construction and Transportation (1998), Discharge Annual Report in Korea.
 - Miyahara K., R. Uji, H. Yamada, Y. Matsui, T. Nishikawa and G. Onitsuka (2005): A harmful bloom of *Cochlodinium polykrikoides* Margalef (Dinophyceae) in the coastal area of San-in, western part of the Japan Sea, in September 2003. Bull. Plankton Soc. Japan, 52, 11-18
 - Nagai S., S. Yamaguchi, C. Lian, Y. Matsuyama and S. Itakura (2006): Development of microsatellite makers in the noxious red tide-causing algae *Heterosigma akashiwo* (Raphidophyceae). Molecular Ecology Notes, 6, 477-479
 - Nagai S., M. Sekino, Y. Matsuyama and S. Itakura (2006): Development of microsatellite makers in the toxic dinoflagellate *Alexandrium catenella* (Dinophyceae). Molecular Ecology Notes, 6, 120-122
 - Nagai S., G. Nishitani, S. Sakamoto, T. Sugaya, C. K. Lee, C. H. Kim, S. Itakura and M. Yamaguchi (2009): Genetic structuring and transfer of marine dinoflagellate *Cochlodinium polykrikoides* in Japanese and Korean coastal waters revealed by microsatellite. Molecular Ecology, 18, 2337-2352
 - Nishitani G., S. Nagai, E. Masseret, C. Lian, S. Yamaguchi, N. Yasuda, S. Itakura, D. Grzebyk, P. Berrebi and M. Sekino (2007): Development of compound microsatellite makers in the toxic dinoflagellate *Alexandrium catenella* (Dinophyceae). Plankton & Benthos Res., 2, 128-133
 - NOWPAP CEARAC (2005): Integrated Report in Harmful Algal Blooms (HABs) for the NOWPAP Region
 - NPEC (2003): The State of the Environment of the Northwest Pacific Region.
 - Onitsuka G., K. Miyahara, N. Hirose, S. Watanabe, H. Semura, R. Hori, T. Nishikawa, K. Miyaji and M. Yamaguchi (2010): Large-scale transportation of *Cochlodinium polykrikoides* blooms by the

Tsushima Warm Current in the southwest Sea of Japan. Harmful Algae, 9, 390-397

- POMRAC (2009), Regional Overview on River and Direct Inputs of Contaminants into the Marine and Coastal Environment in NOWPAP Region with Special Focus on the Land Based Sources of Pollution.
- River Bureau, Ministry of Land, Infrastructure and Transport (2002), River Discharges Year Book of Japan.
- Sasaki H., A. Tanaka, M. Iwataki, Y. Touke, E. Siswanto, C. K. Tan and J. Ishizaka (2008): Optical properties of the red tide in Isahaya Bay, southwestern Japan: Influence of chlorophyll a concentration. J. Oceanogr., 64, 511-523.
- Takahashi W., H. Kawamura, T. Omura and K. Furuya (2009): Detecting Red Tides in the Eastern Seto Inland Sea with Satellite Ocean Color Imagery. J. Ocean., 65, 647-656
- Takao, Y., Y. Tomaru, K. Nagasaki, Y. Sasakura, R. Yokoyama and D. Honda (2007): Fluorescence in situ hybridization using 18s eRNA-targeted probe for specific detection of thraustochytrids (Labyrinthulomycetes). Plankton & Benthos Res., 2, 91-97
- Tang D., D. R. Kester, I. Ni, Y. Qi and H. Kawamura (2003): In situ and satellite observation of a harmful algal bloom and water condition at the Pearl River estuary in the last autumn 1998. Harmful Algae, 2, 89-99
- Yoon Y. H. (2005): A summary on the red-tide mechanisms of the harmful dinoflagellate, *Cochlodinium polykrikoides* in Korean coastal waters. Bull. Plankton Soc. Japan, 48, 113-120

Annex I: Acronyms and abbreviations

ALOS: Advanced Land Observing Satellite
ASP: Amnesic Shellfish Poisoning
CEARAC: Special Monitoring & Coastal Environment Assessment Regional Activity Centre
COD: Chemical Oxygen Demand
DNA: Deoxyribonucleic Acid
DO: Dissolved Oxygen
DSP: Diarrhetic Shellfish Poisoning
DTX: Dinophysistoxin
ECD: Electrolytic Clay Dispenser
EKWC: East Korean Warm Current
ELISA: Enzyme-Linked Immunosorbent Assay
EMECS: International Center for the Environmental Management of Enclosed Coastal
FISH: Fluorescent In Situ Hybridization
FPM: Focal Points Meeting
HAB: Harmful Algal Bloom
HPLC: High Performance Liquid Phase Separations
IMB FEB RAS: The Institute of Marine Biology Far Eastern Branch Russian Academy of Sciences
IOC: Intergovernmental Oceanographic Commission
LAMP: Loop-Mediated Isothermal Amplification
LCC: Liman Cold Current
LC-MS: Liquid Chromatography Mass Spectrometry
MU: Mouse Unit
NFRDI: National Fisheries Research and Development Institute
NOWPAP: Northwest Pacific Action Plan
NPEC: Northwest Pacific Region Environmental Cooperation Center
OA: Okadaic Acid
PCR: Polymerase Chain Reaction
PICES: North Pacific Marine Science Organization
POMRAC: Pollution Monitoring Regional Activity Centre
PSP: Paralytic Shellfish Poisoning
RAC: Regional Activity Centre
SEPA: State Environmental Protection Administration
SOA: State Oceanic Administration
SST: Sea Surface Temperature
STX: Saxitoxin
TTR: Training Through Research
TWC: Tushima Warm Current
UNEP: United Nations Environment Programme

WESTPAC: IOC Sub-Commission for the Western Pacific

WG3: Working Group 3

WG4: Working Group 4

YWC: Yellow Sea Warm Current

Annex II: Red tide events, toxin events and water quality information in the target sea areas

Annex II-1 Red tide events in the NOWPAP region

Country	Organization	Event No.	Duration (Start)				Duration (End)				Locatio of occurrence			Causative species ^(*)	Maximum density (cells/ml)	Fish/Shellfish species	Quantity	Economic loss (Chinese Yuan)	Shellfish poisoning	Environmental parameters ^{(*)2}	Size of bloom (km ²)		
			Pref	Year	No.	Month	day	Year	Month	day	Sub-area	Spot	Qingdao	Jiaozhou Bay	Mesodinium rubrum	-	-	-	DO (mg/L)				
China	North China Sea Environmental Monitoring Centre	QD 1990 1	QD	1990	6	26	-	-	-	-	Dalian	Changhai country	-	-	-	-	-	-	-	-	-	2	
		DL 1990 2	DL	-	-	-	-	-	-	-	Qingdao	Jiaozhou Bay	-	-	-	-	-	-	-	-	-	-	
		QD 1992 1	QD	1992	5	12	-	-	-	-	Qingdao	East Qingdao	-	-	-	-	-	-	-	-	-	-	
		QD 1992 3	QD	-	8	-	-	-	-	-	Qingdao	Jiaozhou Bay	-	-	-	-	-	-	-	-	-	-	
		DL 1993 1	DL	1993	8	11	-	-	-	-	Dalian	Dalian Bay	-	-	-	-	-	-	-	-	-	40	
		QD 1997 1	QD	1997	8	-	-	-	-	-	Qingdao	Jiaozhou Bay	-	-	-	-	-	-	-	-	-	-	
		QD 1998 1	QD	1998	7	3	1998	7	8	6	Qingdao	Jiaozhou Bay	Skeletonema costatum	-	-	-	-	-	-	-	-	-	10
		QD 1	QD	1	6	8	1999	6	15	8	Qingdao	Jiaozhou Bay	Eucampia zoilacus	4,500	-	-	-	-	-	-	-	-	-
		QD 2	QD	2	7	23	1999	7	24	2	Qingdao	Jiaozhou Bay	Skeletonema costatum	-	-	-	-	-	-	-	-	-	26
		QD 3	QD	3	7	26	-	-	-	-	Qingdao	Fushan Bay	Eucampia zoilacus	-	-	-	-	-	-	-	-	-	60
China	SD 6	SD 6	SD	7	17	1999	7	21	5	Dalian	Dalian Bay	Mesodinium rubrum	-	-	-	-	-	-	-	-	-	100	
	SD 7	SD 7	SD	8	6	-	-	-	-	Shandong	Penglai	Nocillula scintillans	-	-	-	-	-	-	-	-	-	680	
	LN 1	LN 1	LN	8	2	-	-	-	-	Dalian	Zhuanghe	Nocillula scintillans	-	-	-	-	-	-	-	-	-	160	
	QD 2	QD 2	QD	7	20	2000	7	23	4	Qingdao	Jiaozhou Bay	Nocillula scintillans	-	-	-	-	-	-	-	-	-	827	
	QD 1	QD 1	QD	4	4	-	-	-	-	Liaoning	Fushan Bay	Nocillula scintillans	-	-	-	-	-	-	-	-	-	92	
	LN 2	LN 2	LN	5	24	-	-	-	-	Dandong	Dandong	Nocillula scintillans	-	-	-	-	-	-	-	-	-	-	
	QD 3	QD 3	QD	6	11	2001	6	12	2	Qingdao	Jiaozhou Bay	Nocillula scintillans	-	-	-	-	-	-	-	-	-	5	
	QD 4	QD 4	QD	7	7	2001	7	13	7	Qingdao	Jiaozhou Bay	Mesodinium rubrum	-	-	-	-	-	-	-	-	-	9.8	
	QD 5	QD 5	QD	6	20	-	-	-	-	Coast of Jiangsu	Coast of Jiangsu	Skeletonema costatum	-	-	-	-	-	-	-	-	-	1000	
	NY 6	NY 6	NY	8	24	2001	9	14	22	North Yellow Sea	Yalujiang Estuary	Eucampia zoilacus	-	-	-	-	-	-	-	-	-	110	
China	QD 2002 1	QD 2002 1	QD	6	28	2002	7	2	5	Qingdao	Fushan Bay	Mesodinium rubrum	-	-	-	-	-	-	-	-	-	60	
	LN 1	LN 1	LN	6	-	-	-	-	-	Liaoning	Dandong	Coscinodiscus asteromphalus	-	-	-	-	-	-	-	-	-	30	
	QD 2003 2	QD 2003 2	QD	7	-	-	-	-	-	Qingdao	Jiaozhou Bay	Mesodinium rubrum	-	-	-	-	-	-	-	-	-	200	
	QD 3	QD 3	QD	7	4	2003	7	10	7	Qingdao	East Qingdao	Gymnodinium deliciula	-	-	-	-	-	-	-	-	-	450	
	QD 1	QD 1	QD	2	-	-	-	-	-	Qingdao	Jiaozhou Bay	Rhizosolenia delicatula	-	-	-	-	-	-	-	-	-	70	
	QD 2	QD 2	QD	2	9	2004	2	28	20	Qingdao	Jiaozhou Bay	Thalassiosira nordenskioeldii	-	-	-	-	-	-	-	-	-	70	
	QD 3	QD 3	QD	3	22	2004	3	25	4	Qingdao	Jiaozhou Bay	Coscinodiscus asteromphalus	-	-	-	-	-	-	-	-	-	70	
	QD 4	QD 4	QD	7	-	-	-	-	-	Qingdao	Jiaozhou Bay	Mesodinium rubrum	-	-	-	-	-	-	-	-	-	50	
	QD 5	QD 5	QD	8	10	-	-	-	-	Qingdao	Fushan Bay	Chattonella antiqua	-	-	-	-	-	-	-	-	-	50	
	DL 6	DL 6	DL	9	6	-	-	-	-	Dalian	Jinshan	Lingnan Bay	Heterosigma akashiwo	95,400	-	-	-	-	-	-	-	-	80
China	QD 2005 1	QD 2005 1	QD	6	12	2005	6	17	6	Qingdao	Shazikou Bay	Heterosigma akashiwo	53,100	-	-	-	-	-	-	-	-	-	70
	QD 2007 2	QD 2007 2	QD	8	20	2007	8	23	4	Qingdao	East Qingdao	Skeletonema costatum	11,100	-	-	-	-	-	-	-	-	-	15
	QD 3	QD 3	QD	9	25	2007	9	28	4	Qingdao	Shazikou Bay	Gonyaulax spinifera	-	-	-	-	-	-	-	-	-	8	
	QD 1	QD 1	QD	6	28	2008	6	29	2	Qingdao	Jiaozhou Bay	Heirocassis sp.	3,280	-	-	-	-	-	-	-	-	-	-
	QD 2	QD 2	QD	8	7	2008	8	8	2	Qingdao	South Qingdao	Chattonella antiqua	520	-	-	-	-	-	-	-	-	-	86

¹ Scientific name is based on the Integrated Report on Harmful Algal Blooms (HABs) for the NOWPAP Region (NOWPAP CEARAC 2005).

² In case of China, the range of environmental parameters means the value which observed in some monitoring points during HAB event.

³ In case of Korea, the range of environmental parameters means the value which observed in some monitoring points.

⁴ In case of Russia, the range of environmental parameters means the value which observed during HAB event.

Annex II-1 Red tide events in the NOWPAP region (Continued)

County	Organization	Event No.	Duration(Start)			Duration(End)			Locatio of occurrence			Causative species(*1)	Maximum density (cells·ind./mL)	Fishery damage			Environmental parameters			
			Pref. Cod	Year	No.	Month	day	Year	Month	day	Sub-area			Quantity	Economic loss (1,000 Japanese Yen)	Temp. (°C)	Salinity	DO (mg/L)	Size of bloom (km ²)	
Yamaguchi Prefectural Fisheries Research Center	YM	1	2006	2	20	2006	2	27	8	Coastal area	Between Aburaya Bay and coastline of Woshiba	<i>Nocillula scintillans</i>	2,150	-	-	10.0	-	-		
	YM	2	2006	2	25	2006	2	28	4	Coastal area	Coastline of Nagato City (Sensaki Bay, Fukagawa Bay)	<i>Nocillula scintillans</i>	-	-	-	-	-	-	-	
	YM	3	2006	3	27	2006	3	29	3	Coastal area	Coastline of Nagato City (Sensaki Bay)	<i>Nocillula scintillans</i>	-	-	-	-	-	-	0.3	
	YM	4	2006	7	13	2006	8	4	23	Coastal area	Coastline of Shimonoseki City	<i>Karenia mikimotoi</i>	57,500	Amberjack, etc.	370 ind.	1,800	-	25.4	-	-
	YM	5	2006	8	2	2006	8	11	10	Coastal area	Between Hagi City and Abu Town	<i>Karenia mikimotoi</i>	4,900	Kingfish	60 ind.	120	-	28.2	-	-
	YM	6	2006	10	16	2006	10	19	4	Coastal area	Niwase fishing port	<i>Mesodinium rubrum</i>	68	-	-	-	-	-	0.0001	
Fukuoka Fisheries and Marine Technology Research Center	FO	1	2006	6	5	2006	6	12	8	North Kyushu	West region of Chikuzen Sea	<i>Nocillula scintillans</i>	200	-	-	-	-	-	-	
	FO	2	2006	6	21	2006	6	27	7	North Kyushu	Fukuoka Bay	<i>Procentrum tintinninum</i>	10,060	-	-	-	-	-	-	
Saga Prefectural Genkai Fisheries Promotion Center	SA	1	2006	7	20	2006	7	22	3	North Kyushu	Fukuoka Bay	<i>Skeletonema sp.</i>	28,240	-	-	-	-	-	-	
	SA	2	2006	7	20	2006	7	23	4	North Kyushu	Fukuoka Bay	<i>Lepidocyathus sp.</i>	11,800	-	-	-	-	-	-	
	SA	3	2006	7	26	2006	7	30	5	North Kyushu	Fukuoka Bay	<i>Chaetoceros sp.</i>	1,710	-	-	-	-	-	-	
	SA	4	2006	7	27	2006	7	30	4	North Kyushu	Fukuoka Bay	<i>Procentrum tintinninum</i>	14,980	-	-	-	-	-	-	
	SA	5	2006	7	18	2006	7	26	9	North Kyushu	Kamon Strait	<i>Skeletonema sp.</i>	47,110	-	-	-	-	-	-	
	SA	6	2006	8	21	2006	8	26	5	North Kyushu	Imari Bay	<i>Other Diatom</i>	2,020	-	-	-	-	-	-	
Japan	SA	7	2006	11	20	2006	11	22	3	North Kyushu	Imari Bay	<i>Other Diatom</i>	1,740	Damaged (The details were not known)	1,200	-	-	-	-	-
	SA	8	2006	11	27	2006	11	28	2	North Kyushu	Imari Bay	<i>Ceratium furca</i>	340	-	-	-	-	-	-	
	SA	9	2006	1	24	2006	3	15	20	West Kyushu	Imari Bay	<i>Mesodinium rubrum</i>	1,180	-	-	-	-	-	-	
	SA	10	2006	5	1	2006	5	26	5	North Kyushu	Imari Bay	<i>Nitzschia sp.</i>	13,300	-	-	-	-	-	-	
	SA	11	2006	6	16	2006	6	29	45	West Kyushu	Imari Bay	<i>Thalassiosira sp.</i>	5,940	-	-	-	-	-	-	
	SA	12	2006	7	1	2006	7	18	5	West Kyushu	Imari Bay	<i>Skeletonema costatum</i>	11,140	-	-	-	-	-	-	
Nagasaki Prefectural Institute of Fisheries	NS	1	2006	8	21	2006	8	23	2	North Kyushu	Imari Bay	<i>Thalassiosira sp.</i>	2,520	-	-	-	-	-	-	
	NS	2	2006	8	22	2006	8	23	2	North Kyushu	Imari Bay	<i>Ceratium furca</i>	2,022	-	-	-	-	-	-	
	NS	3	2006	9	6	2006	9	11	22	3	North Kyushu	Imari Bay	<i>Procentrum tintinninum</i>	7,240	-	-	-	-	-	-
	NS	4	2006	9	11	2006	9	11	28	2	North Kyushu	Imari Bay	<i>Procentrum tintinninum</i>	2,940	-	-	-	-	-	-
	NS	5	2006	9	12	2006	9	15	20	West Kyushu	Imari Bay	<i>Cryptophyceae</i>	148,000	-	-	-	-	-	-	
	NS	6	2006	9	13	2006	9	15	2	West Kyushu	Imari Bay	<i>Strombodium sp.</i>	55	-	-	-	-	-	-	
Nagasaki Prefectural Institute of Fisheries	NS	7	2006	9	14	2006	9	17	14	West Kyushu	Imari Bay	<i>Heterosigma akashiwo</i>	11,800	-	-	-	-	-	-	
	NS	8	2006	9	15	2006	9	17	14	West Kyushu	Imari Bay	<i>Procentrum tintinninum</i>	225,000	-	-	-	-	-	-	
	NS	9	2006	9	16	2006	9	18	3	West Kyushu	Imari Bay	<i>Procentrum tintinninum</i>	3,400	-	-	-	-	-	-	
	NS	10	2006	9	17	2006	9	18	5	West Kyushu	Imari Bay	<i>Karenia mikimotoi</i>	15,800	-	-	-	-	-	-	
	NS	11	2006	9	18	2006	9	21	3	West Kyushu	Imari Bay	<i>Ceratium furca</i>	6,950	-	-	-	-	-	-	
	NS	12	2006	9	19	2006	9	21	16	West Kyushu	Imari Bay	<i>Mesodinium rubrum</i>	13,570	-	-	-	-	-	-	
Nagasaki Prefectural Institute of Fisheries	NS	13	2006	9	20	2006	9	22	6	West Kyushu	Imari Bay	<i>Procentrum tintinninum</i>	92,200	-	-	-	-	-	-	
	NS	14	2006	9	21	2006	9	25	6	West Kyushu	Imari Bay	<i>Heterosigma akashiwo</i>	225,000	-	-	-	-	-	-	
	NS	15	2006	9	22	2006	9	26	5	West Kyushu	Imari Bay	<i>Procentrum tintinninum</i>	3,400	-	-	-	-	-	-	
	NS	16	2006	9	23	2006	9	27	3	West Kyushu	Imari Bay	<i>Pufferfish</i>	1,000 ind.	-	-	-	-	-	-	
	NS	17	2006	9	24	2006	9	28	18	West Kyushu	Imari Bay	<i>Red seabream</i>	70 ind.	-	-	-	-	-	-	
	NS	18	2006	9	25	2006	9	29	19	West Kyushu	Imari Bay	<i>Cochlodinium polykrikoides</i>	135	-	-	-	-	-	-	
Nagasaki Prefectural Institute of Fisheries	NS	19	2006	9	26	2006	9	30	20	West Kyushu	Imari Bay	<i>Ceratium furca</i>	667	-	-	-	-	-	-	
	NS	20	2006	9	27	2006	9	31	24	West Kyushu	Imari Bay	<i>Karenia mikimotoi</i>	16,000	Pufferfish	10,350	-	-	-	-	
	NS	21	2006	9	28	2006	9	31	25	West Kyushu	Imari Bay	<i>Procentrum minimum</i>	12,800	-	-	-	-	-	-	
	NS	22	2006	10	11	2006	10	10	13	West Kyushu	Imari Bay	<i>Heterosigma akashiwo</i>	11,300	-	-	-	-	-	-	
	NS	23	2006	10	12	2006	10	11	6	West Kyushu	Imari Bay	<i>Cochlodinium polykrikoides</i>	646	-	-	-	-	-	-	
	NS	24	2006	10	13	2006	10	12	7	West Kyushu	Imari Bay	<i>Procentrum sigmoides</i>	160	-	-	-	-	-	-	
Nagasaki Prefectural Institute of Fisheries	NS	25	2006	11	1	2006	11	11	3	West Kyushu	Imari Bay	<i>Procentrum sigmoides</i>	14,380	-	-	-	-	-	-	
	NS	26	2006	11	1	2006	11	11	3	West Kyushu	Imari Bay	<i>Mesodinium rubrum</i>	490	-	-	-	-	-	-	

*1 Scientific name is based on the Integrated Report on Harmful Algal Blooms (HABs) for the NOWPAP Region (NOWPAP CEARAC 2005).

*2 In case of China, the range of environmental parameters means the value which observed at some monitoring points during HAB event.

*3 In case of Korea, the range of environmental parameters means the value which observed in some monitoring points.

*4 In case of Russia, the range of environmental parameters means the value which observed during HAB event.

Annex II-1 Red tide events in the NOWPAP region (Continued)

Country	Organization	Event No.	Duration(Start)				Duration(End)				Locatio of occurrence			Causative species(*1)	Maximum density (cells/lnd. mL)	Fishery damage			Environmental parameter				
			Pref	Year	No.	Month	day	Year	Month	day	Sub-area	Spot				Quantity	Economic los (1,000 Japanese Yen)	Temp. (°C)	Salinity				
			Code	e														DO (mg/L)	Size of bloom (km ²)				
Yamaguchi Prefectural Fisheries Research Center	YM	1	2007	2	6	2007	2	9	4	Coastal area of Yamaguchi	Coastline of Shimonesaki City/Between Toyoura town and Yoshimi	<i>Nocilicella scintillans</i>	-	-	-	-	-	-	-	0.8			
	YM	2	2007	2	9	2007	2	19	11	Coastal area of Yamaguchi	Sensaki Bay	<i>Nocilicella scintillans</i>	2,110	-	-	-	-	-	-	-			
	YM	3	2007	3	23	2007	3	30	8	Coastal area of Yamaguchi	Coastline of Shimonesaki City/Between Toyooka town and Sentocho	<i>Nocilicella sp.</i>	2,990	-	-	-	-	-	-	-			
	YM	4	2007	3	26	2007	3	30	5	Coastal area of Yamaguchi	Between Aburaya Bay and Sensaki Bay	<i>Nocilicella sp.</i>	-	-	-	-	-	-	-	-			
	YM	5	2007	4	9	2007	4	12	4	Coastal area of Yamaguchi	Coastline of Hagi City/Between Otsushi and Yudamai of Toyoura town	<i>Nocilicella sp.</i>	-	-	-	-	-	-	-	-			
	YM	6	2007	4	19	2007	4	24	6	Coastal area of Yamaguchi	Coastline of Hagi City/Between Ominato and Koshidatama	<i>Nocilicella sp.</i>	-	-	-	-	-	-	-	-			
	YM	7	2007	5	23	2007	5	30	8	Coastal area of Yamaguchi	Coastline of Hagi City (Sannomagasaki)	<i>Nocilicella sp.</i>	-	-	-	-	-	-	-	-			
	YM	8	2007	11	29	2007	12	6	8	Coastal area of Yamaguchi	Shimonesaki fishing port	<i>Mesodinium rubrum</i>	19	-	-	-	-	-	-	-	0.0001		
	YM	9	2007	12	7	2007	12	19	13	Coastal area of Yamaguchi	Ohura fishing port of Nagato City	<i>Mesodinium rubrum</i>	4,280	-	-	-	-	-	-	-	0.04		
	YM	10	2007	12	12	2007	12	14	3	Coastal area of Yamaguchi	Coastline of Hagi City (Susa Town)	<i>Mesodinium rubrum</i>	170	-	-	-	-	-	-	-	0.02		
Fukuoka Fisheries and Marine Technology Research Center	FO	1	2007	3	8	2007	5	9	63	North Kyushu	Fukioka Bay	<i>Gephyrocapsa oceanica</i>	-	Damaged	(The details were not known.)	-	-	-	-	-			
	FO	2	2007	6	7	2007	6	12	6	North Kyushu	Fukioka Bay	<i>Heirosoma akashiwo</i>	-	-	-	-	-	-	-	-			
	FO	3	2007	6	22	2007	6	27	6	North Kyushu	Fukioka Bay	<i>Skeletocystis acutivalvata</i>	-	-	-	-	-	-	-	-			
	FO	4	2007	7	6	2007	7	9	4	North Kyushu	Fukioka Bay	<i>Heirosoma akashiwo</i>	-	-	-	-	-	-	-	-			
	FO	5	2007	7	9	2007	7	16	8	North Kyushu	Fukioka Bay	<i>Skeletocystis acutivalvata</i>	-	-	-	-	-	-	-	-			
	FO	6	2007	8	6	2007	8	16	11	North Kyushu	Fukioka Bay	<i>Procentrum fuscum</i>	-	-	-	-	-	-	-	-			
	FO	7	2007	8	23	2007	8	28	6	North Kyushu	Fukioka Bay	<i>Chaetoceros sp.</i>	-	-	-	-	-	-	-	-			
	FO	8	2007	9	12	2007	9	18	7	North Kyushu	Fukioka Bay	<i>Lepicyathus sp.</i>	-	-	-	-	-	-	-	-			
	FO	9	2007	9	20	2007	9	25	6	North Kyushu	Fukioka Bay	<i>Skeletocystis acutivalvata</i>	-	-	-	-	-	-	-	-			
	SA	10	2007	9	1	2007	9	2	2	North Kyushu	Hedo Point	<i>Thalassiosira SD</i>	-	-	-	-	-	-	-	-			
Saga Prefectural Genkai Fisheries Promotion Center	SA	19	2007	12	21	2007	12	24	4	North Kyushu	Karatsu Bay	<i>Karenia mikimotoi</i>	3,900	-	-	-	-	-	-	-	15.0	34.1	7.4
	NS	1	2007	1	16	2007	1	18	3	Remote Is.	Tsushima	<i>Karenia mikimotoi</i>	90	-	-	-	-	-	-	-	14.6	-	6.4
	NS	2	2007	3	23	2007	4	2	11	Remote Is.	Tsushima	<i>Spirtoisella SD</i>	5,360	-	-	-	-	-	-	-	16.7	35.8	7.7
	NS	4	2007	5	25	2007	5	29	5	Remote Is.	Tsushima	<i>Heirosoma akashiwo</i>	350	-	-	-	-	-	-	-	19.7	33.5	5.6
	NS	5	2007	6	5	2007	6	6	2	West Kyushu	Kujukushima	<i>Nocilicella scintillans</i>	1,350	-	-	-	-	-	-	-	21.9	33.5	5.0
	NS	6	2007	6	14	2007	7	5	22	West Kyushu	Kujukushima	<i>Karenia mikimotoi</i>	1,880	-	-	-	-	-	-	-	24.9	33.6	11.6
	NS	7	2007	6	14	2007	6	16	3	Remote Is.	Tsushima	<i>Ceratium furca</i>	16,500 (yellow tail)	-	-	-	-	-	-	-	24.9	33.6	11.6
	NS	8	2007	6	19	2007	7	9	21	West Kyushu	Kujukushima	<i>Karenia mikimotoi</i>	97,000 (yellow tail)	-	-	-	-	-	-	-	24.9	33.6	11.6
	NS	9	2007	6	24	2007	6	27	14	Remote Is.	Goto	<i>Ceratium furca</i>	730	-	-	-	-	-	-	-	24.9	31.5	7.6
	NS	10	2007	6	25	2007	6	27	3	Remote Is.	Goto	<i>Ceratium furca</i>	88	-	-	-	-	-	-	-	22.4	34.1	7.2
Japan	NS	12	2007	6	27	2007	6	29	3	Remote Is.	Tsushima	<i>Procentrum trevisanum</i>	2,232,000	-	-	-	-	-	-	-	22.3	33.4	7.5
	NS	13	2007	7	2	2007	7	5	4	West Kyushu	Kujukushima	<i>Ceratium furca</i>	5,100	-	-	-	-	-	-	-	25.2	-	0.25
	NS	14	2007	7	7	2007	7	9	3	Remote Is.	Tsushima	<i>Ceratium furca</i>	27	-	-	-	-	-	-	-	-	-	-
	NS	15	2007	7	11	2007	7	23	13	North Kyushu	Hirado	<i>Cochlidinium polykrikoides</i>	8650 (yellow tail)	-	-	-	-	-	-	-	30.1	-	-
	NS	17	2007	7	22	2007	7	29	3	North Kyushu	Hirado/Tsurinari Bay	<i>Nocilicella scintillans</i>	2,445	-	-	-	-	-	-	-	-	-	-
	NS	20	2007	8	22	2007	8	27	6	West Kyushu	Omura Bay	<i>Stichococcus sp.</i>	4,750	-	-	-	-	-	-	-	-	29.2	-
	NS	21	2007	8	23	2007	8	24	2	West Kyushu	Imari Bay	<i>Mesodinium rubrum</i>	1,250	-	-	-	-	-	-	-	-	-	0.045
	NS	22	2007	8	24	2007	8	25	2	West Kyushu	Crustine of Shiri	<i>Procentrum trevisanum</i>	1,500	-	-	-	-	-	-	-	-	-	0.025
	NS	23	2007	8	28	2007	9	3	7	West Kyushu	Omura Bay	<i>Karenia mikimotoi</i>	5,800	-	-	-	-	-	-	-	-	-	-
	NS	24	2007	9	6	2007	9	12	7	West Kyushu	Omura Bay	<i>Dichodicha fibula</i>	15,700 (yellow tail)	-	-	-	-	-	-	-	-	11.5	-
Nagasaki Prefectural Institute of Fisheries	NS	25	2007	9	6	2007	9	11	6	Remote Is.	Tsushima	<i>Gyrodinium istriatum</i>	46	-	-	-	-	-	-	-	25.6	24.3	4.9
	NS	27	2007	9	11	2007	9	13	3	West Kyushu	Tachibana Bay	<i>Procentrum sinuosides</i>	541	-	-	-	-	-	-	-	27.3	33.2	101%
	NS	28	2007	9	16	2007	9	28	13	West Kyushu	Omura Bay	<i>Procentrum sinuosides</i>	4,040	-	-	-	-	-	-	-	30.0	32.7	129%
	NS	29	2007	10	3	2007	10	5	3	Remote Is.	Harada	<i>Cochlodinium polykrikoides</i>	2,500	-	-	-	-	-	-	-	29.2	-	-
	NS	30	2007	11	15	2007	11	16	2	North Kyushu	(Usuka)Flute Bay	<i>Mesodinium rubrum</i>	176	-	-	-	-	-	-	-	-	-	0.005
	NS	31	2007	11	19	2007	11	29	11	Remote Is.	Tsushima	<i>Mesodinium rubrum</i>	157	-	-	-	-	-	-	-	-	-	0.005
	NS	32	2007	11	21	2007	11	21	1	Remote Is.	Goto	<i>Mesodinium rubrum</i>	1,488	-	-	-	-	-	-	-	-	-	0.004
	NS	33	2007	11	26	2007	11	27	2	Remote Is.	Goto	<i>Gyrodinium istriatum</i>	4,110	-	-	-	-	-	-	-	20.1	34.4	-
	NS	34	2007	11	29	2007	11	30	5	Remote Is.	Goto	<i>Mesodinium rubrum</i>	810	-	-	-	-	-	-	-	-	-	0.045
	NS	35	2007	12	1	2007	12	5	5	Remote Is.	Hirodo	<i>Mesodinium rubrum</i>	3,640	-	-	-	-	-	-	-	-	-	0.025
Prefectural Institute of Fisheries	NS	36	2007	12	6	2007	12	23	19	North Kyushu	(Usuka)Flute Bay	<i>Mesodinium rubrum</i>	1,220	-	-	-	-	-	-	-	16.7	33.2	7.8
	NS	37	2007	12	10	2007	12	11	2	Remote Is.	Kujukushima	<i>Mesodinium rubrum</i>	1,152	-	-	-	-	-	-	-	-	-	-
	NS	38	2007	12	11	2007	12	12	2	West Kyushu	Kujukushima	<i>Mesodinium rubrum</i>	1,070	-	-	-	-	-	-	-	-	-	-
	NS	39	2007	12	12	2007	12	13	2	Remote Is.	Goto	<i>Mesodinium rubrum</i>	1,074	-	-	-	-	-	-	-	-	-	-
	NS	40	2007	12	12	2007	12	19	8	Remote Is.	Goto	<i>Mesodinium rubrum</i>	-	-	-	-	-	-	-	-	-	-	-
	NS	41	2007	12	12	2007	12	19	8	Remote Is.	Goto	<i>Mesodinium rubrum</i>	-	-	-	-	-	-	-	-	-	-	-
	NS	42	2007	12	12	2007	12	19	8	Remote Is.	Goto	<i>Mesodinium rubrum</i>	-	-	-	-	-	-	-	-	-	-	-

Annex II-1 Red tide events in the NOWPAP region (Continued)

County	Organization	Event No.	Duration(Start)			Duration(End)			Locatio of occurrence			Causative species(*1)	Maximum density (cells·inds./ml)	Fish/Shellfish species	Fishery damage			Environmental parameters	
			Pref. Cod	Year	No.	Year	Month	day	Sub-area	Spot				Quantity	Economic loss (1,000 Japanese Yen)	Temp. (°C)	Salinity	DO (mg/L)	
Japan	Yamaguchi Prefectural Fisheries Research Center	YM	1	2008	2	29	2008	-	Coastal area of Yamaguchi	Noctiluca sp.	-	-	-	-	-	-	-	-	
		YM	2	2008	3	6	2008	-	Coastal area of Yamaguchi	Sensaki Bay	Noctiluca sp.	-	-	-	-	-	-	-	
		YM	3	2008	3	11	2008	-	Coastal area of Yamaguchi	Hibiki Nada	Noctiluca sp.	-	-	-	-	-	-	-	
		YM	4	2008	4	15	2008	-	Coastal area of Yamaguchi		Noctiluca sp.	-	-	-	-	-	-	-	
		YM	5	2008	7	23	2008	-	Coastal area of Yamaguchi	Hibiki Nada	Karenia mikimotoi	-	-	-	-	-	-	-	
		YM	6	2008	7	30	2008	-	Coastal area of Yamaguchi	Yuya Bay	Karenia mikimotoi	-	-	-	-	-	-	-	
		FO	1	2008	3	12	2008	3	17	5	North Kyushu	Fukukawa Bay (Shiga island)	Noctiluca scintillans	2,200	-	-	-	-	
		FO	2	2008	4	14	2008	4	30	17	North Kyushu	North region of Chikuzen sea area	Glyptophysa oceanica	1,900	-	-	-	-	-
	Fukuoka Fisheries and Marine Technology Research Center	FO	3	2008	5	8	2008	5	14	7	North Kyushu	Coastline of Fukutsu City	Noctiluca scintillans	1,200	-	-	-	-	-
		FO	4	2008	5	15	2008	5	29	15	North Kyushu	Fukukawa Bay	Proocentrum minimum	35,000	-	-	-	-	-
		FO	5	2008	5	15	2008	5	20	6	North Kyushu	Fukukawa Bay (Shiga island)	Lepidocyathus denicius	4,000	-	-	-	-	-
		FO	6	2008	5	28	2008	5	30	3	North Kyushu	Coastline of Kitakyushu City	Heterosigma akashiwo	65,000	-	-	-	-	-
		FO	7	2008	6	4	2008	6	13	10	North Kyushu	East region of Fukuoka Bay	Heterosigma akashiwo	30,000	-	-	-	-	-
		FO	8	2008	6	23	2008	6	30	8	North Kyushu	East region of Fukuoka Bay	Skeletorhena costatum	25,000	-	-	-	-	-
		FO2	1	2008	9	1	2008	9	7	7	West Kyushu	Ariake	Mesodinium rubrum	1,000	-	-	-	-	-
		FO2	2	2008	9	10	2008	9	21	12	West Kyushu	Ariake	Akashio saigonaea Ceratium fusus	300 90	-	-	-	-	-
		FO2	3	2008	9	24	2008	9	28	5	West Kyushu	Ariake	Mesodinium rubrum	19,100	-	-	-	-	171.0
	Saga Prefectural Genkai Fisheries Promotion Center	SA	2	2008	3	5	2008	3	7	3	North Kyushu	Karatsu Bay	Noctiluca scintillans	160	-	-	-	-	-
		SA	4	2008	4	30	2008	5	2	3	North Kyushu	North region of Madara Island (Chinese Town)	Noctiluca scintillans	1,520	-	-	-	-	-
		SA	6	2008	6	23	2008	7	2	10	North Kyushu	Karatsu Bay	Chattonella antiqua	5,530 Chicken gunt	500 ind. 400 ind.	400 75	-	-	-
		SA	7	2008	6	25	2008	7	1	7	North Kyushu	Kanoya Bay	Prorocentrum tredsttinum	300	-	-	-	-	-
		SA	8	2008	7	3	2008	7	4	2	North Kyushu	Imari Bay	Prorocentrum dentatum	22,190	-	-	-	-	-
		SA	16	2008	10	3	2008	10	9	7	North Kyushu	Kanoya Bay	Chattonella antiqua	35	-	-	-	-	-

Annex II-1 Red tide events in the NOWPAP region (Continued)

Country	Organization	Event No.	Duration(Start)					Duration(End)					Locality of occurrence			Environmental parameters				
			Pref. Code	Year	No.	Month	day	Year	Month	day	Sub-area	Spot	Causative species(*)		Maximum density (cells incs/mL)	Fish/Shellfish species		Quantity	Economic loss (1,000 Japanese Yen)	
																Temp (°C)	Salinity	DO (mg/L)	Size of bloom (km ²)	
Saga Prefectural Genkai Fisheries Promotion Center	Sa2	1	2008	2	15	2008	3	18	33	West Kyushu	Ariake	<i>Asterionella kariana</i>	22,000	Laver	-	-	-	-		
	Sa2	2	2008	4	30	2008	5	7	8	West Kyushu	Ariake	<i>Heterocapsa roundata</i>	173,000	-	-	-	-	-		
	Sa2	3	2008	6	13	2008	7	4	22	West Kyushu	Ariake	<i>Amphidinium</i> sp.	47,900	-	-	-	-	-		
	Sa2	4	2008	7	11	2008	7	14	4	West Kyushu	Ariake	<i>Skeletonema costatum</i>	3,950	-	-	-	-	-		
	Sa2	5	2008	7	28	2008	8	3	7	West Kyushu	Ariake	<i>Thalassosira</i> spp. <i>Micromonas</i>	64,000	17,533	-	-	-	-		
	Sa2	6	2008	7	29	2008	8	20	23	West Kyushu	Ariake	<i>Heterosigma akashiwo</i>	250	32,533	-	-	-	-		
	Sa2	7	2008	8	11	2008	8	17	7	West Kyushu	Ariake	<i>Ceratium fusus</i>	11	-	-	-	-	-		
	Sa2	8	2008	8	12	2008	8	13	2	West Kyushu	Ariake	<i>Chattonella sanguinea</i>	290	-	-	-	-	-		
	Sa2	9	2008	8	25	2008	9	15	22	West Kyushu	Ariake	<i>Chattonella antiqua</i>	1,250	-	-	-	-	-		
	Sa2	10	2008	9	8	2008	9	15	8	West Kyushu	Ariake	<i>Thalassosira</i> spp.	13,800	-	-	-	-	-		
	Sa2	11	2008	10	10	2008	10	13	4	West Kyushu	Ariake	<i>Chaetoceros</i> spp.	6,700	-	-	-	-	-		
	Sa2	12	2008	10	14	2008	10	16	3	West Kyushu	Ariake	<i>Thalassosira</i> spp.	22,000	-	-	-	-	-		
	Sa2	13	2008	10	23	2008	11	3	12	West Kyushu	Ariake	<i>Akashiwo sanguinea</i>	350	-	-	-	-	-		
	Sa2	14	2008	11	8	2008	11	12	5	West Kyushu	Ariake	<i>Heterosigma akashiwo</i>	2,250	-	-	-	-	-		
	NS	1	2008	3	17	2008	3	19	2	North Kyushu	Imari Bay	<i>Skeletonema costatum</i>	23,400	-	-	-	-	-		
	NS	6	2008	6	20	2008	6	23	4	West Kyushu	Ariake	<i>Chaetoceros</i> spp.	44,400	-	-	-	-	-		
	NS	7	2008	6	24	2008	6	28	5	West Kyushu	Ariake	<i>Akashiwo sanguinea</i>	138	-	-	-	-	-		
	NS	9	2008	6	24	2008	6	25	2	North Kyushu	Ariake	<i>Fibrocapsa japonica</i>	778	-	-	-	-	-		
	NS	10	2008	6	25	2008	6	27	3	Remote Is.	Ik	<i>Akashiwo sanguinea</i>	4,150	-	-	-	-	-		
	NS	12	2008	7	2	2008	7	24	23	West Kyushu	Kujukushima	<i>Nocilicula scintillans</i>	113	-	-	-	-	-		
	NS	13	2008	7	17	2008	7	18	2	West Kyushu	Omura Bay	<i>Mesodinium rubrum</i>	3,250	-	-	-	-	0.002		
	NS	14	2008	7	25	2008	7	26	2	West Kyushu	Tachihara Bay	<i>Ceratium fusus</i>	21,700	-	-	-	-	-		
	NS	16	2008	9	4	2008	9	5	2	Remote Is.	Goto	<i>Rhizosolenia</i> sp.	49,200	-	-	-	22	10.5		
	NS	17	2008	9	22	2008	9	30	9	North Kyushu	Usuki Bay	<i>Heterosigma akashiwo</i>	9,000	-	-	-	21	8.2		
	NS	18	2008	9	30	2008	10	1	2	West Kyushu	Omura Bay	<i>Karenia mikimotoi</i>	8,250	Japanese pufferfish	4000 ind.	440	24	-		
	NS	19	2008	10	3	2008	10	15	13	North Kyushu	Imari Bay	<i>Mesodinium rubrum</i>	-	-	-	-	-	-		
	Nagasaki Prefectural Institute of Fishes	NS	21	2008	11	7	2008	11	27	21	North Kyushu	Usuki Bay	<i>Mesodinium rubrum</i>	1,820	-	-	-	23	-	
		NS	22	2008	11	25	2008	11	26	2	Remote Is.	Goto	<i>Cochlodinium polykrikoides</i>	195	-	-	-	-	-	
		NS	23	2008	11	26	2008	11	27	2	Remote Is.	Tsurimisima	<i>Alexandrium tamarense</i>	173	-	-	-	-	-	
		NS	24	2008	12	3	2008	12	22	20	Remote Is.	Goto	<i>Mesodinium rubrum</i>	3,900	-	-	-	19	-	
		NS2	2	2008	3	21	2008	3	22	2	West Kyushu	Ariake(sahaya Bay)	<i>Nocilicula scintillans</i>	150	-	-	-	14	-	
		NS2	3	2008	5	8	2008	5	12	5	West Kyushu	Ariake(sahaya Bay)	<i>Heterosigma akashiwo</i>	36,300	-	-	-	20	31.6	
		NS2	4	2008	5	30	2008	5	31	2	West Kyushu	Ariake(sahaya Bay)	<i>Cochlodinium polykrikoides</i>	88	-	-	-	24	7.3	
		NS2	5	2008	6	13	2008	6	14	2	West Kyushu	Ariake(sahaya Bay)	<i>Skeletonema</i>	610	-	-	-	25	4.8	
		NS2	8	2008	6	24	2008	7	1	8	West Kyushu	Ariake(sahaya Bay)	<i>Mesodinium rubrum</i>	35,300	-	-	-	-	-	
		NS2	11	2008	7	1	2008	7	2	2	West Kyushu	Ariake(sahaya Bay)	<i>Cochlodinium polykrikoides</i>	1,950	-	-	-	-	-	
		NS2	15	2008	7	26	2008	8	21	27	West Kyushu	Ariake(sahaya Bay)	<i>Gymnodinium catenatum</i>	138	-	-	-	-	-	
		NS2	20	2008	10	9	2008	10	10	2	West Kyushu	Ariake	<i>Mesodinium rubrum</i>	7,000	-	-	-	-	0	

Annex II-1 Red tide events in the NOWPAP region (Continued)

Country	Organization	Event No.	Duration(Start)			Duration(End)			Locatio of occurrence			Causative species(*1)	Maximum density (cells·inds./ml)	Fishery damage			Environmental parameters (*3)	Size of bloom (km ²)		
			Pref Cod	Year	Month	day	Year	Month	day	Sub-area	Spot			Fish/Shellfish species	Quantity (million ind.)	Economic loss (1,000 won)	Temp. (°C)	Salinity	DO (mg/L)	
Korea National Fisheries Research and Development Institute	SE	1	2007	7	24	2007	7	30	7	Tongyeong	Tongyeong Dosan	Akashivo sangueina	500	-	-	-	22.4-24.5	32.0-33.2	-	
	SE	2	2007	8	6	2007	9	15	42	Namhae	Namhae Mizo	Cochlodinium polykrikoides	32,500	Red sea bream Bass Rockfish Parrot fish	0.688 0.389 0.15 0.61	3,664	-	23.3-29.4	28.3-32.0	-
	SE	2007	3	2007	8	9	2007	9	12	Tongyeong	Tongyeong Sarang Suyou-do	Cochlodinium polykrikoides	23,000	Rockfish Parrot fish etc.	2 other 1.9	7,337	-	24.0-27.6	30.2-34.0	-
	SE	4	2007	8	11	2007	9	1	29	Tongyeong	Goseong Bay	Cochlodinium polykrikoides	4,000	-	-	-	26.0-29.5	30.3-32.3	-	
	SE	5	2007	9	3	2007	9	9	6	Tongyeong	Jinju Bay	Cochlodinium polykrikoides	2,000	-	-	-	22.1-25.6	30.1-32.8	-	
	SE	6	2007	10	19	2007	10	29	10	Tongyeong	Upper Sarang-do	Cochlodinium polykrikoides	2,130	-	-	-	22.5-23.3	32.8-33.2	-	
	SE	1	2008	8	4	2008	9	23	50	Namhae	Tongyeong Donsan	Cochlodinium polykrikoides	5,800	-	-	-	21.0-26.9	30.5-32.9	-	
	SE	2	2008	8	8	2008	9	22	45	Tongyeong	Namhae Mizo	Cochlodinium polykrikoides	2,650	-	-	-	22.2-27.0	28.0-32.3	-	
	SE	2008	3	2008	9	16	2008	9	25	Tongyeong	Tongyeong Sarang Suyou-do	Cochlodinium polykrikoides	2,500	-	-	-	24.0-27.0	30.1-33.2	-	
	SE	4	2008	8	29	2008	9	5	7	Tongyeong	Goseong Bay	Cochlodinium polykrikoides	4,000	-	-	-	24.9-27.0	30.0-32.8	-	
China	SE	5	2008	9	11	2008	9	20	9	Tongyeong	Jinju Bay	Cochlodinium polykrikoides	5,000	-	-	-	26.2-27.0	30.9-33.2	-	
	SE	1	2009	8	4	2009	8	-	4	Goseong	Donghae-myeon	Ceratium furca	2,000	-	-	-	24.6-25.2	28.9-30.6	-	
	SE	2	2009	8	11	2009	8	19	11	Namhae	Nam-nyeon	Alexandrium farreri	6,000	-	-	-	24.1-26.5	28.3-30.9	-	
	SE	2009	3	2009	8	11	2009	8	13	Tongyeong	Tae-do	Gonyaulax polygramma	950	-	-	-	24.2-24.9	30.3-31.4	-	
	SE	4	2009	8	24	2009	8	26	5	Geoe	Chilchon-do	Scyphacella trochoidea	15,000	-	-	-	24.7-25.6	28.1-30.6	-	
	SE	5	2009	11	1	2009	11	9	11	Namhae	Sandong eunjeom	Gymnodinium sp.	1,900	-	-	-	19.0-19.6	31.8-32.9	-	

*1 Scientific name is based on the Integrated Report on Harmful Algal Blooms (HABs) for the NOWPAP Region (NOWPAP CEARC 2005).

*2 In case of China, the range of environmental parameters means the value which observed in some monitoring points during HAB event.

*3 In case of Korea, the range of environmental parameters means the value which observed in some monitoring points.

*4 In case of Russia, the range of environmental parameters means the value which observed during HAB event.

Annex II-1 Red tide events in the NOWPAP region (Continued)

Country	Event No.	Pref Cod e	Year	Duration(Start)		Duration(End)		Locatio of occurrence			Causative species ^(*)	Fishery damage			Environmental parameters ^(*)		
				Month	day	Year	Month	day	Sub-area	Spot		Maximum density (cells·inds./ml)	Fish/Shellfish species	Quantity	Economic loss		
	AB	1991	1	1991	7	8	1991	8	12	36	Amurskii Bay	<i>Procentrum minimum</i>	-	-	-		
	AB	1993	1	1993	11	19	? ?	? ?	<7	Amurskii Bay	<i>Chatonella</i> sp.	800	-	-	-		
	AB	1	1996	2	28	1996	3	28	29	Amurskii Bay	<i>Heterosigma akashiwo</i>	1,000	-	-	-1.0-1.0 33.0-34.0		
	AB	3	1996	7	2	1996	7	16	15	Amurskii Bay	<i>Nocillicula scimillans</i>	1,6	-	-	17.0-20.0 28.0-30.0		
	AB	4	1996	7	8	1996	8	30	31	Amurskii Bay	<i>Chaetoceros affinis</i>	1,900	-	-	19.0-23.0 27.0-28.0		
	AB	5	1996	7	22	1996	8	30	40	Amurskii Bay	<i>Skeletonema costatum</i>	12,700	-	-	20.0-23.0 27.0-30.0		
	AB	7	1996	8	5	1996	8	12	8	Amurskii Bay	<i>Chaetoceros curvisetum</i>	1,500	-	-	20.0-21.0 25.0-27.0		
	AB	8	1996	11	4	1996	12	16	43	Amurskii Bay	<i>Lepidocyathus minimus</i>	1,900	-	-	1.0-7.0 34.0-35.0		
	AB	1	1997	5	4	1997	6	4	32	Amurskii Bay	<i>Chaetoceros contractus</i>	1,300	-	-	11.0-12.0 29.0-30.0		
	AB	1997	4	1997	7	29	? ?	? ?	<7	Amurskii Bay	<i>Thalassia testudinum</i>	3,000	-	-	-		
	AB	5	1997	8	19	1997	8	28	10	Amurskii Bay	<i>Protoceratium reticulatum</i>	0.4	-	-	20.0-23.0 24.0-28.0		
	AB	7	1997	10	17	1997	11	3	18	Amurskii Bay	<i>Karenia mikimotoi</i>	7.2	-	-	5.0-11.0 33.0-35.0		
	AB	1	1998	1	26	1998	2	17	23	Amurskii Bay	<i>Thalassiosira nordenskioldii</i>	1,100	-	-	-2.0-0.5 34.0-35.0		
	AB	2	1998	3	5	1998	3	12	8	Amurskii Bay	<i>Plagiomelism sp.</i>	1,100	-	-	-1.0-0.8 33.0		
	ANB	1	2001	8	13	2001	-	-	Amura Bay	<i>Heterosigma akashiwo</i>	7	-	-	-			
	VB	2001	1	2001	8	16	2001	-	>12	Vostok Bay	<i>Skeletonema costatum</i>	5,250	-	-	22.4-23.5 28.6		
	VB	4	2001	9	30	2001	-	-	? ?	Vostok Bay	<i>Asterionellopsis gelatinosa</i>	1,191	-	-	14.7 33.6		
	VB	2002	2	2002	7	14	2002	-	-	? ?	Vostok Bay	<i>Chatonella gibosa</i>	0.6	-	-	16.4 32.1	
	VB	2003	1	2003	4	23	2003	-	-	Vostok Bay	<i>Heterocapsa rotundata</i>	1,426	-	-	6.2 33.4		
	AB	2004	1	2004	11	17	? ?	? ?	<7	Amurskii Bay	<i>Chaetoceros salmagineus</i>	1,800	-	-	-		
	AB	1	2005	7	12	? ?	? ?	<7	Amurskii Bay	<i>Euglena pastachii</i>	1,500	-	-	-5.0 35.0			
	AB	6	2005	10	20	? ?	<5	Amurskii Bay	<i>Protoceratium minimum</i>	100	-	-	12.0 33.0				
	VB	1	2005	9	1	2005	-	-	Vostok Bay	<i>Heterosigma akashiwo</i>	161	-	-	20.3			
	AB	2	2006	6	5	2006	7	3	29	Amurskii Bay	<i>Thalassionema nitzschiae</i>	2,000	-	-	-13.0-20.0 20.0-29.0		
	Center of Monitoring of HABs & Biotoxins Institute of Marine Biology FEB RAS	5	2006	7	3	? ?	? ?	<5	Amurskii Bay	<i>Karenia mikimotoi</i>	18	-	-	-			
	AB	6	2006	7	3	? ?	? ?	<5	Amurskii Bay	<i>Chaetoceros salmagineus</i>	1,800	-	-	-5.0 33.0			
	VB	2	2006	8	4	2006	-	-	? ?	Vostok Bay	<i>Heterosigma akashiwo</i>	38	-	-	-22.6 30.6		
	VB	3	2006	8	20	2006	-	-	? ?	Vostok Bay	<i>Skeletonema costatum</i>	8,229	-	-	-		
	AB	1	2007	7	11	2007	7	25	14	Amurskii Bay	<i>Dinophysis acuminata</i>	1	-	-	18.0-22.0 26.0-26.7		
	AB	2	2007	7	25	2007	8	20	25	Amurskii Bay	<i>Amurskii Bay</i>	8,897	-	-	-		
	AB	3	2007	7	25	2007	7	25	1	Amurskii Bay	<i>Heterosigma akashiwo</i>	0.3	-	-	-		
	AB	4	2007	8	6	2007	9	17	42	Amurskii Bay	<i>Pseudo-nitzschia delectans</i>	83	-	-	-		
	AB	5	2007	8	20	2007	8	20	1	Amurskii Bay	<i>Heterosigma akashiwo</i>	8	-	-	-23.2 26.8		
	AB	6	2007	9	5	2007	9	17	12	Amurskii Bay	<i>Pseudo-nitzschia calliantha</i>	173	-	-	-		
	AB	7	2007	10	30	2007	10	30	1	Amurskii Bay	<i>Heterosigma akashiwo</i>	10	-	-	-6.5 31.2		
	AB	8	2007	7	25	2007	7	25	1	Amurskii Bay	<i>Pseudo-nitzschia pungens</i>	59	-	-	-		
	VB	1	2007	8	8	2007	-	-	Vostok Bay	<i>Heterosigma akashiwo</i>	19	-	-	-			
	AB	1	2008	3	4	2008	4	7	34	Amurskii Bay	<i>Dinobryon habicum</i>	1,054	-	-	-0.5-6 30.6-33.6		
	AB	2	2008	7	14	2008	7	28	14	Amurskii Bay	<i>Skeletonema costatum</i>	5,826	-	-	-23.5-23.5 22.5-26.0		
	AB	3	2008	6	7	2008	6	7	1	Amurskii Bay	<i>Heterosigma akashiwo</i>	1	-	-	-16.2 18.8		
	AB	4	2008	6	7	2008	7	14	37	Amurskii Bay	<i>Dinophysis acuminata</i>	4	-	-	-16.0-23.3 18.8-26.0		
	AB	5	2008	8	29	2008	-	-	7	Amurskii Bay	<i>Protoceratium minimum</i>	0.9	-	-	-20.5 28.17		
	AB	6	2008	9	15	2008	-	-	7	Amurskii Bay	<i>Protoceratium reticulatum</i>	0.3	-	-	-20.9 29.78		
	AB	1	2009	1	11	2009	-	-	7	Amurskii Bay	<i>Protoceratium reticulatum</i>	0.3	-	-	-1.6 33.31		
	AB	4	2009	6	8	2009	-	-	7	Amurskii Bay	<i>Protoceratium reticulatum</i>	0.4	-	-	-14.1 30		
	AB	7	2009	8	2	2009	-	-	76	Amurskii Bay	<i>Protoceratium reticulatum</i>	509	-	-	-10.5-23.0 20		
	AB	8	2009	9	9	2009	-	-	7	Amurskii Bay	<i>Protoceratium minimum</i>	0.3	-	-	-19.0 25		
	AB	1	2009	7	4	2009	-	-	Vostok Bay	<i>Nitzschia hybrida f. hyalina</i>	8,122	-	-	-15.4 28.27			
	AB	3	2010	3	30	2010	-	-	7	Amurskii Bay	<i>Heterosigma akashiwo</i>	6,942	-	-	-1.0 30.55		
	AB	5	2010	7	30	2010	-	-	7	Amurskii Bay	<i>Dactylosolen fragilissimus</i>	1,860	-	-	-23.0 22.59		

¹* Scientific name is based on the Integrated Report on Harmful Algal Blooms (HABs) for the NOWPAP Region (NOWPAP CEARAC 2005).

²* In case of China, the range of environmental parameters means the value which observed in some monitoring points during HAB event.

³* In case of Korea, the range of environmental parameters means the value which observed in some monitoring points.

⁴* In case of Russia, the range of environmental parameters means the value which observed during HAB event.

Annex II-2 Toxin-producing plankton bloom and shellfish poisoning

Country	Event No.		Duration (Start)			Duration (End)			Location of occurrence			Monitoring date			Fishery damage			Environmental parameters (*2)			
	Pref. Code	Year	No.	Year	Month	day	Year	Month	day	Sub-area	Spot	Date	Time	Causative species (*1)	Maximum density (cells · inds./L.)	Fish/Shellfish species	Shellfish poisoning	Toxin level (*3)	Temp. (°C)	Salinity	DO (mg/L)
China	DL	1999	4	1999	-	-	-	-	-	Dalian	Dalian Bay	-	-	<i>Exuviaella marina</i>	8,100,000	-	-	-	-	-	-
	DL	2004	7	2004	9	25	-	-	-	Dalian	Jinshitan	-	-	<i>Alexandrium catenula</i>	-	-	-	-	-	-	-
Japan	Event No.		Duration (Start)			Duration (End)			Location of occurrence			Monitoring date			Fishery damage			Environmental parameters (*2)			
	Pref. Code	Year	No.	Year	Month	day	Year	Month	day	Sub-area	Spot	Date	Time	Causative species (*1)	Maximum density (cells · inds./L.)	Fish/Shellfish species	Shellfish poisoning	Toxin level (*3)	Temp. (°C)	Salinity	DO (mg/L)
YM	YM	2006	1	2006	11	6				Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	16						
	YM	2006	2	2006	11	6				Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	12						
YM	YM	2006	3	2006	11	13				Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	4						
	YM	2006	4	2006	11	13				Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	23						
YM	YM	2006	5	2006	11	27				Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	4						
	YM	2006	6	2006	11	27				Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	10						
YM	YM	2006	7	2006	11	30				Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	164						
	YM	2006	8	2006	11	30				Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	152						
YM	YM	2006	9	2006	12	6				Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	423						
	YM	2006	10	2006	12	6				Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	667						
YM	YM	2006	11	2006	12	15				Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	29						
	YM	2006	12	2006	12	15				Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	7						
YM	YM	2006	13	2006	12	22				Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	341						
	YM	2006	14	2006	12	22				Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	216						
FO	FO	2006	1	2006	4	11				Fukuoka	Fukuoka Bay			<i>Gymnodinium catenatum</i>	114						
	FO	2006	2	2006	10	12				Fukuoka	Fukuoka Bay			<i>Gymnodinium catenatum</i>	235						
FO	FO	2006	3	2006	12	12				Fukuoka	Fukuoka Bay			<i>Alexandrium</i> spp.	15						
	FO	2006	-											<i>Dinophysis</i> spp.	43						
FO	FO	2006	-											<i>Gymnodinium catenatum</i>	6						
	FO	2006	-											<i>Dinophysis</i> spp.	32						
FO	FO	2006	-											<i>Gymnodinium catenatum</i>	77						
	FO	2006	-											<i>Dinophysis</i> spp.	88						
FO	FO	2006	-											<i>Alexandrium</i> spp.	18						
	FO	2006	-											<i>Dinophysis</i> spp.	1						
FO	FO	2006	-											<i>Dinophysis</i> spp.	37						
	FO	2006	-											<i>Dinophysis</i> spp.	70						

*1 Scientific name is based on the Integrated Report on Harmful Algal Blooms (HABs) for the NWPAP Region (NWPAP CEARAC, 2005).

*2 In case of Japan and Russia, the range of environmental parameters means the value which observed during event.

*3 In case of Japan, the unit of toxin level is MU/g. The unit of other member states is µg/g.

Annex II-2 Toxin-producing plankton bloom and shellfish poisoning (Continued)

County	Event No.		Duration (Start)			Duration (End)			Location of occurrence		Monitoring date		Causative species (*1)	Maximum density (cells · inds./L.)	Fishery damage		Environmental parameters (*2)		
	Pref. Code	Year	No.	Year	Month	day	Year	Month	day	Sub-area	Spot	Date	Time		Fish/Shellfish species	Shellfish poisoning	Toxin level (*3)	Temp. (°C)	Salinity
Japan	SA	2006	1	2006	5	2				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	40				
	SA	2006	2	2006	5	23				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	4800				
	SA	2006	3	2006	5	24				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	128				
	SA	2006	4	2006	5	24				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	104				
	SA	2006	5	2006	5	30				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	68				
	SA	2006	6	2006	5	30				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	16				
	SA	2006	7	2006	5	30				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	512				
	SA	2006	8	2006	6	2				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	20084				
	SA	2006	9	2006	6	8				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	16				
	SA	2006	10	2006	6	8				Saga	Iriomote Bay			<i>Alexandrium</i> spp.	144				
	SA	2006	11	2006	6	9				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	712				
	SA	2006	12	2006	6	13				Saga	Iriomote Bay			<i>Alexandrium</i> spp.	24				
	SA	2006	13	2006	6	13				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	32				
	SA	2006	14	2006	7	3				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	8				
	SA	2006	15	2006	7	3				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	24				
	SA	2006	16	2006	8	2				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	32				
	SA	2006	17	2006	8	2				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	8				
	SA	2006	18	2006	8	6				Saga	Iriomote Bay			<i>Alexandrium</i> spp.	24				
	SA	2006	19	2006	8	8				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	72				
	SA	2006	20	2006	8	13				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	80				
	SA	2006	21	2006	8	20				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	32				
	SA	2006	22	2006	8	27				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	16				
	SA	2006	23	2006	9	13				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	788				
	SA	2006	24	2006	10	2				Saga	Nagoya			<i>Dinophysis</i> spp.	8				
	SA	2006	25	2006	10	2				Saga	Kushihara			<i>Alexandrium</i> spp.	296				
	SA	2006	26	2006	10	3				Saga	Karatsu Bay			<i>Gymnodinium</i> spp.	8				
	SA	2006	27	2006	10	5				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	18				
	SA	2006	28	2006	11	1				Saga	Karatsu Bay			<i>Gymnodinium</i> spp.	10				
	SA	2006	29	2006	11	1				Saga	Kushihara			<i>Alexandrium</i> spp.	58				
	SA	2006	30	2006	11	1				Saga	Karatsu Bay			<i>Gymnodinium</i> spp.	192				
	SA	2006	31	2006	11	2				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	120				
	SA	2006	32	2006	11	2				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	8				
	SA	2006	33	2006	11	20				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	98				
	SA	2006	34	2006	12	1				Saga	Karatsu Bay			<i>Gymnodinium</i> spp.	16				
	SA	2006	35	2006	12	5				Saga	Iriomote Bay			<i>Gymnodinium</i> spp.	8				
	NA	2006	1	2006	4	18				Saga	Karatsu Bay			<i>Gymnodinium</i> spp.	48				
	NA	2006	2	2006	7	12				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	64				
	NA	2006	3	2006	9	19				Saga	Kushihara			<i>Gymnodinium</i> spp.	32				
	NA	2006	4	2006	10	10				Saga	Kushihara			<i>Dinophysis</i> spp.	40				
	NA	2006	5	2006	10	18				Saga	Iriomote Bay			<i>Alexandrium</i> spp.	8				
	NA	2006	6	2006	11	2				Saga	Karatsu Bay			<i>Gymnodinium</i> spp.	2				
	NA	2006	7	2006	12	1				Saga	Kushihara			<i>Gymnodinium</i> spp.	10				
	NA	2006	8	2006	10	10				Saga	Kushihara			<i>Gymnodinium</i> spp.	4				
	NA	2006	9	2006	10	10				Saga	Kushiyama			<i>Alexandrium</i> spp.	2				
	NA	2006	10	2006	11	18				Saga	Kushiyama			<i>Dinophysis</i> spp.	6				

Annex II-2 Toxin-producing plankton bloom and shellfish poisoning (Continued)

County	Event No.	Duration (Start)			Duration (End)			Continuous days	Sub-area	Spot	Date	Time	Causative species (*1)	Maximum density (cells · inds./L.)	Fishery damage		Environmental parameters (*2)				
		Pref. Code	Year	No.	Year	Month	day								Fish/Shellfish species	Toxin level (*3)	Temp (°C)	Salinity	DO (mg/L)		
	YM	2007	1	2006	12	26	2007	2	21	58	Yamaguchi	Sensaki Bay	-	-	<i>Gymnodinium catenatum</i>	1,211	Japanese oyster	PSP	6.18-12.2	9.1-13.6	28.9-34.3
	YM	2007	2	2007	1	5					Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	74					
	YM	2007	3	2007	1	5					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	58					
	YM	2007	4	2007	1	12					Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	14					
	YM	2007	5	2007	1	12					Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	4					
	YM	2007	6	2007	1	17					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	92					
	YM	2007	7	2007	1	17					Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	1211					
	YM	2007	8	2007	1	24					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	115					
	YM	2007	9	2007	1	24					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	57					
	YM	2007	10	2007	1	31					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	102					
	YM	2007	11	2007	1	31					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	12					
	YM	2007	12	2007	2	7					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	39					
	YM	2007	13	2007	11	15					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	12					
	YM	2007	14	2007	11	26					Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	14					
	YM	2007	15	2007	12	3					Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	2					
	YM	2007	16	2007	12	10					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	6					
	YM	2007	17	2007	12	10					Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	12					
	YM	2007	18	2007	12	12					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	20					
	YM	2007	19	2007	12	12					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	120					
	YM	2007	20	2007	12	17					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	12					
	YM	2007	21	2007	12	17					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	39					
	YM	2007	22	2007	12	20					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	12					
	YM	2007	23	2007	12	20					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	246					
	YM	2007	24	2007	12	26					Yamaguchi	Sensaki Bay			<i>Alexandrium</i> spp.	33					
	YM	2007	25	2007	12	26					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	64					
	FO	2007	1	2007	2	9					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	34					
	SA	2007	1	2007	1	8					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	78					
	SA	2007	2	2007	1	12					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	78					
	SA	2007	3	2007	1	16					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	53					
	SA	2007	4	2007	1	16					Yamaguchi	Sensaki Bay			<i>Gymnodinium catenatum</i>	41					
	SA	2007	5	2007	1	18					Yamaguchi	Sensaki Bay			<i>Dinophysis</i> spp.	36					
	SA	2007	6	2007	1	18					Yamaguchi	Fukuoka Bay			<i>Gymnodinium catenatum</i>	160					
	SA	2007	7	2007	1	22					Saga	Karatsu Bay			<i>Alexandrium</i> spp.	72					
	SA	2007	8	2007	1	22					Saga	Nagoya Bay			<i>Alexandrium</i> spp.	6,488					
	SA	2007	9	2007	1	22					Saga	Karatsu Bay			<i>Alexandrium</i> spp.	48					
	SA	2007	10	2007	1	22					Saga	Nagoya Bay			<i>Alexandrium</i> spp.	1,056					
	SA	2007	11	2007	1	25					Saga	Karatsu Bay			<i>Gymnodinium catenatum</i>	64					
	SA	2007	12	2007	1	25					Saga	Karatsu Bay			<i>Dinophysis</i> spp.	32					
	SA	2007	13	2007	1	22					Saga	Nagoya Bay			<i>Gymnodinium catenatum</i>	160					
	SA	2007	14	2007	2	1					Saga	Iriomote Bay			<i>Dinophysis</i> spp.	224					
	SA	2007	15	2007	2	2					Saga	Karatsu Bay			<i>Dinophysis</i> spp.	18					
	SA	2007	16	2007	2	2					Saga	Iriomote Bay			<i>Dinophysis</i> spp.	24					
	SA	2007	17	2007	2	2					Saga	Karatsu Bay			<i>Dinophysis</i> spp.	8					
	SA	2007	18	2007	3	1					Saga	Nagoya Bay			<i>Gymnodinium catenatum</i>	32					
	SA	2007	19	2007	3	1					Saga	Iriomote Bay			<i>Dinophysis</i> spp.	326					
	SA	2007	20	2007	3	1					Saga	Iriomote Bay			<i>Dinophysis</i> spp.	56					
	SA	2007	21	2007	3	1					Saga	Karatsu Bay			<i>Dinophysis</i> spp.	56					
	SA	2007	22	2007	3	1					Saga	Nagoya Bay			<i>Alexandrium</i> spp.	80					
	SA	2007	23	2007	3	1					Saga	Karatsu Bay			<i>Alexandrium</i> spp.	8					
	SA	2007	24	2007	3	1					Saga	Nagoya Bay			<i>Dinophysis</i> spp.	96					

Annex II-2 Toxin-producing plankton bloom and shellfish poisoning (Continued)

Country	Event No.		Duration (Start)			Duration (End)			Location of occurrence		Monitoring date		Causative species (*1)	Maximum density (cells · inds./L.)	Fish/Shellfish species	Fishery damage	Environmental parameters (*2)		
	Pref. Code	Year	No.	Year	Month	day	Year	Month	day	Sub-area	Spot	Date	Time				Temp. (°C)	Salinity	DO (mg/L)
	SA	2007	19	2007	3	2				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	208				
	SA	2007	20	2007	3	2				Saga	Nagoyaura			<i>Dinophysis</i> spp.	80				
	SA	2007	21	2007	3	2				Saga	Kariya Bay			<i>Alexandrium</i> spp.	16				
	SA	2007	22	2007	4	3				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	8				
	SA	2007	23	2007	4	4				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	320				
	SA	2007	24	2007	4	4				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	192				
	SA	2007	25	2007	5	1				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	394				
	SA	2007	26	2007	5	1				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	40				
	SA	2007	27	2007	5	2				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	1016				
	SA	2007	28	2007	5	7				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	48				
	SA	2007	29	2007	5	10				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	752				
	SA	2007	30	2007	5	14				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	32				
	SA	2007	31	2007	5	17				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	56				
	SA	2007	32	2007	5	21				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	32				
	SA	2007	33	2007	5	24				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	136				
	SA	2007	34	2007	5	29				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	16				
	SA	2007	35	2007	6	4				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	760				
	SA	2007	36	2007	6	5				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	16				
	SA	2007	37	2007	6	5				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	24				
	SA	2007	38	2007	6	19				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	144				
	SA	2007	39	2007	6	22				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	8				
	SA	2007	40	2007	6	26				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	104				
	SA	2007	41	2007	7	2				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	48				
	SA	2007	42	2007	7	3				Saga	Kariya Bay			<i>Dinophysis</i> spp.	56				
	SA	2007	43	2007	8	1				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	80				
	SA	2007	44	2007	9	4				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	16				
	SA	2007	45	2007	10	1				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	16				
	SA	2007	46	2007	10	1				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	184				
	SA	2007	47	2007	10	1				Saga	Kariya Bay			<i>Dinophysis</i> spp.	32				
	SA	2007	48	2007	10	2				Saga	Iriomote Bay			<i>Alexandrium</i> spp.	16				
	SA	2007	49	2007	11	1				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	8				
	SA	2007	50	2007	11	1				Saga	Iriomote Bay			<i>Alexandrium</i> spp.	48				
	SA	2007	51	2007	11	1				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	24				
	SA	2007	52	2007	11	2				Saga	Karatsu Bay			<i>Alexandrium</i> spp.	128				
	SA	2007	53	2007	12	4				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	96				
	SA	2007	54	2007	12	4				Saga	Kushihira			<i>Alexandrium</i> spp.	48				
	SA	2007	55	2007	12	4				Saga	Karatsu Bay			<i>Dinophysis</i> spp.	64				
	NA	2007	1	2007	5	14				Saga	Nagoyaura			<i>Alexandrium</i> spp.	64				
	NA	2007	2	2007	7	12				Saga	Iriomote Bay			<i>Dinophysis</i> spp.	24				
	NA	2007	3	2007	8	13				Saga	Kariya Bay			<i>Alexandrium</i> spp.	96				
	NA	2007	4	2007	11	14				Saga	Iriomote Bay			<i>Gymnodinium catenatum</i>	7				
	NA	2007	5	2007	12	12				Saga	Nagasaki			<i>Gymnodinium catenatum</i>	3				
	NA	2007	6	2007	12	17				Saga	Tachibana			<i>Gymnodinium catenatum</i>	54				
	NA	2007	-	-	-	-				Nagasaki	Heijima			<i>Dinophysis</i> spp.	5				
	NA	2007	-	-	-	-				Nagasaki	Heijima			<i>Dinophysis</i> spp.	1				

Annex II-2 Toxin-producing plankton bloom and shellfish poisoning (Continued)

County	Event No.	Duration (Start)			Duration (End)			Locatio of occurrence			Monitoring date		Causative species (*1)	Maximum density (cells·inds./L.)	Fishery damage	Environmental parameters (*2)		
		Pref. Code	Year	No.	Year	Month	day	Year	Month	day	Sub-area	Spot				Temp. (°C)	Salinity	DO (mg/L)
YM	2008 1	2008	1	4							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	8				
YM	2008 2	2008	1	4							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	20				
YM	2008 3	2008	1	9							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	25				
YM	2008 4	2008	1	9							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	45				
YM	2008 5	2008	1	15							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	47				
YM	2008 6	2008	1	15							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	52				
YM	2008 7	2008	1	21							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	9				
YM	2008 8	2008	1	21							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	30				
YM	2008 9	2008	1	30							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	18				
YM	2008 10	2008	1	30							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	41				
YM	2008 11	2008	2	4							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	30				
YM	2008 12	2008	2	12							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	18				
YM	2008 13	2008	2	12							Yamaguchi	Sensaki Bay	<i>Gymnodinium catenatum</i>	2				
YM	2008 14	2008	11	14	-	-	-				Yamaguchi	Sensaki Bay	-	-	PSP	5.25-59	-	
SA	2008 1	2008	1	4							Saga	Karatsu Bay	<i>Dinophysis</i> spp.	208				
SA	2008 2	2008	1	7							Saga	Karuya Bay	<i>Dinophysis</i> spp.	16				
SA	2008 3	2008	1	8							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	96				
SA	2008 4	2008	1	8							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	32				
SA	2008 5	2008	2	4							Saga	Karatsu Bay	<i>Dinophysis</i> spp.	16				
SA	2008 6	2008	2	4							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	32				
SA	2008 7	2008	2	4							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	32				
SA	2008 8	2008	2	5							Saga	Karuya Bay	<i>Dinophysis</i> spp.	8				
SA	2008 9	2008	3	4							Saga	Karuya Bay	<i>Dinophysis</i> spp.	48				
SA	2008 10	2008	4	2							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	8				
SA	2008 11	2008	4	2							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	8				
SA	2008 12	2008	4	3							Saga	Karatsu Bay	<i>Alexandrium</i> spp.	16				
SA	2008 13	2008	4	3							Saga	Karuya Bay	<i>Dinophysis</i> spp.	8				
SA	2008 14	2008	5	1							Saga	Karatsu Bay	<i>Alexandrium</i> spp.	32				
SA	2008 15	2008	5	1							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	16				
SA	2008 16	2008	5	1							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	32				
SA	2008 17	2008	5	2							Saga	Karuya Bay	<i>Alexandrium</i> spp.	48				
SA	2008 18	2008	6	2							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	24				
SA	2008 19	2008	6	3							Saga	Karuya Bay	<i>Dinophysis</i> spp.	32				
SA	2008 20	2008	7	1							Saga	Karatsu Bay	<i>Dinophysis</i> spp.	32				
SA	2008 21	2008	7	1							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	24				
SA	2008 22	2008	7	1							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	112				
SA	2008 23	2008	7	2							Saga	Karuya Bay	<i>Dinophysis</i> spp.	48				
SA	2008 24	2008	8	5							Saga	Karatsu Bay	<i>Dinophysis</i> spp.	8				
SA	2008 25	2008	9	1							Saga	Karuya Bay	<i>Dinophysis</i> spp.	248				
SA	2008 26	2008	9	2							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	56				
SA	2008 27	2008	9	2							Saga	Iriomote Bay	<i>Dinophysis</i> spp.	64				
SA	2008 28	2008	11	4							Saga	Karatsu Bay	<i>Gymnodinium catenatum</i>	48				
SA	2008 29	2008	11	4							Saga	Karatsu Bay	<i>Dinophysis</i> spp.	16				
SA	2008 30	2008	11	4							Saga	Nagoya Bay	<i>Gymnodinium catenatum</i>	48				
SA	2008 31	2008	11	5							Saga	Karuya Bay	<i>Dinophysis</i> spp.	16				
SA	2008 32	2008	12	2							Saga	Karatsu Bay	<i>Dinophysis</i> spp.	40				
Japan																		

Annex II-2 Toxin-producing plankton bloom and shellfish poisoning (Continued)

Country	Event No.		Duration (Start)			Duration (End)			Locatio of occurrence			Monitoring date			Causative species (*1)			Maximum density (cells: inds./L)			Fishery damage			Environmental parameters (*2)		
	Pref. Code	Year	No.	Year	Month	day	Year	Month	day	Sub-area	Spot	Date	Time	Fish/Shellfish species	Shellfish poisoning	Toxin level (*3)	Temp. (°C)	Salinity	DO (mg/L)							
Japan	NA	2008	1	2008	1	16				Nagasaki	Terasshima			Dinophysis spp.		1										
	NA	2008	2	2008	1	23				Nagasaki	South			Gymnodinium catenatum		2										
	NA	2008	3	2008	8	26				Nagasaki	Heijima			Gymnodinium catenatum		30										
	NA	2008	4	2008	10	27				Nagasaki	Heijima			Gymnodinium catenatum		29										
	NA	2008	5	2008	12	18				Nagasaki	Heijima			Gymnodinium catenatum		8										
	SA	2009	1	2009	1	5				Saga	Irari Bay			Dinophysis spp.		8										
	SA	2009	2	2009	1	6				Saga	Nagayura			Dinophysis spp.		8										
	SA	2009	3	2009	1	6				Saga	Kushihira			Dinophysis spp.		8										
	SA	2009	4	2009	1	6				Saga	Kariya Bay			Alexandrium spp.		16										
	SA	2009	5	2009	1	8				Saga	Irari Bay			Dinophysis spp.		16										
Korea	SA	2009	6	2009	2	2				Saga	Kariya Bay			Dinophysis spp.		8										
	SA	2009	7	2009	2	3				Saga	Karatsu Bay			Dinophysis spp.		24										
	SA	2009	8	2009	2	3				Saga	Irari Bay			Dinophysis spp.		16										
	Event No.		Duration (Start)			Duration (End)			Locatio of occurrence			Monitoring date			Causative species (*1)			Maximum density (cells: inds./L)			Fishery damage			Environmental parameters (*2)		
	Pref. Code	Year	No.	Year	Month	day	Year	Month	day	Sub-area	Spot	Date	Time	Fish/Shellfish species	Shellfish poisoning	Toxin level (*3)	Temp. (°C)	Salinity	DO (mg/L)							
Korea	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	

*1 Scientific name is based on the Integrated Report on Harmful Algal Blooms (HABs) for the NOWPAP Region (NOWPAP CEARAC, 2005).

*2 In case of Japan and Russia, the range of environmental parameters means the value which observed during event.

*3 In case of Japan, the unit of toxin level is MU/g. The unit of other member states is µg/g.

Annex II-2 Toxin-producing plankton bloom and shellfish poisoning (Continued)

Country	Event No.	Duration (Start)			Duration (End)			Continuous days		Locatio of occurrence		Monitoring date		Causative species (*1)	Maximum density (cells/inds./L)	Fishery damage	Environmental parameters (*2)			
		Pref. Code	Year	No.	Month	day	Year	Month	day	Sub-area	Spot	Date	Time	Fish/Shellfish species	Shellfish poisoning	Toxin level (*3)	Temp. (°C)	Salinity (mg/L)		
Russia	AB	1992	1	1992	6	25	1992	7	10	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia</i>	11,000,000	-	-	19.0-23.0	27.0-28.0	
	AB	1996	2	1996	6	19	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Dunaliella</i>	800	-	-	-	13.0	
	AB	1996	6	1996	7	29	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis fortii</i>	200	-	-	-	23.0	
	AB	1997	2	1997	6	4	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis acuminata</i>	60	-	-	-	24.0	
	AB	1997	3	1997	6	13	1997	7	22	50	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis acuminata</i>	12,800	-	-	-	12.0
	AB	1997	6	1997	9	4	1997	11	19	66	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia delicatissima</i>	2,700,000	-	-	-	15.0-20.0
	AB	1997	8	1997	11	11	1997	11	19	9	Amurskii Bay	Amurskii Bay	-	-	<i>cailliettii</i>	500,000	-	-	-	1.0-19.0
	AB	1998	3	1998	3	26	-	-	-	7	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis rotundata</i>	600	-	-	-	34.0-35.0
	VB	2001	2	2001	8	29	-	-	-	Vostoik Bay	Vostoik Bay	-	-	<i>Alexandrium tamarense</i>	1,600	-	-	-	0.2	
	VB	2001	3	2001	8	29	-	-	-	Vostoik Bay	Vostoik Bay	-	-	<i>Dinophysis fortii</i>	400	-	-	-	-	
	VB	2001	5	2001	9	30	-	-	-	Vostoik Bay	Vostoik Bay	-	-	<i>Pseudo-nitzschia acuminata</i>	686,000	-	-	-	14.7	
	VB	2002	1	2002	7	14	-	-	-	Vostoik Bay	Vostoik Bay	-	-	<i>Dinophysis acuminata</i>	500	-	-	-	33.6	
	VB	2002	3	2002	10	15	-	-	-	Vostoik Bay	Vostoik Bay	-	-	<i>Pseudo-nitzschia pungens</i>	2,600	-	-	-	16.4	
	VB	2003	2	2003	6	30	-	-	-	Vostoik Bay	Vostoik Bay	-	-	<i>Dinophysis acuminata</i>	100	-	-	-	32.1	
	ANB	2004	1	2004	7	8	2004	12	25	171	Aniva Bay	Aniva Bay	-	-	<i>Mizuhopecan vescensis</i>	-	-	-	-	-
	ANB	2004	2	2004	9	10	2004	9	12	3	Aniva Bay	Aniva Bay	-	-	<i>Pseudo-nitzschia spp.</i>	-	-	-	-	-
	ANB	2004	3	2004	11	20	2004	11	30	11	Aniva Bay	Aniva Bay	-	-	<i>Mizuhopecan vescensis</i>	ASP	100-110	-	-	-
	VB	2004	1	2004	8	1	2004	-	-	Vostoik Bay	Vostoik Bay	-	-	<i>Pseudo-nitzschia spp.</i>	-	-	-	-	-	
	ANB	2005	1	2005	10	20	2005	10	28	9	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis acuminata</i>	200	-	-	-	19.5-20.5
	AB	2005	2	2005	10	26	?	?	?	7	Amurskii Bay	Amurskii Bay	-	-	<i>Alexandrium tamarense</i>	-	-	-	-	23.2
	AB	2005	3	2005	10	5	2005	10	26	22	Aniva Bay	Aniva Bay	-	-	<i>Mizuhopecan vescensis</i>	200,000	-	-	-	28.5
	AB	2005	4	2005	12	5	2005	12	30	26	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia fraudulenta</i>	38,000	-	-	-	-
	AB	2005	5	2005	12	5	2005	12	29	25	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia multisira</i>	800,000	-	-	-	6.0-12.0
	AB	2005	7	2005	9	4	2005	9	10	7	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia delicatissima</i>	80,000	-	-	-	32.0-33.0
	VB	2005	2	2005	11	1	-	-	-	Vostoik Bay	Vostoik Bay	-	-	<i>Pseudo-nitzschia pseudonitzschia</i>	87,000	-	-	-	-	
	AB	2006	1	2006	3	1	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis rotundata</i>	500	-	-	-	15.0	
	AB	2006	3	2006	6	20	2006	7	3	14	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia pungens</i>	60,000	-	-	-	33.0-35.0
	AB	2006	4	2006	6	20	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia seriata</i>	9,100	-	-	-	-1.7	
	VB	2006	1	2006	8	4	-	-	-	Vostoik Bay	Vostoik Bay	-	-	<i>Pseudo-nitzschia seriata</i>	87,000	-	-	-	34.0	
	AB	2007	1	2007	7	11	2007	7	25	14	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis acuminata</i>	686	-	-	-	32.6
	AB	2007	2	2007	7	11	2007	7	11	7	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia delicatissima</i>	686	-	-	-	32.6
	AB	2007	3	2007	11	9	2007	11	9	7	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudonitzschia</i>	340	-	-	-	31.9
	AB	2007	4	2007	8	6	2007	9	17	42	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia delicatissima</i>	83,385	-	-	-	20.0-22.0
	AB	2007	5	2007	7	11	2007	7	11	7	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia</i>	7,800	-	-	-	23.8-32.7
	AB	2007	6	2007	9	5	2007	9	17	12	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudonitzschia</i>	173,400	-	-	-	-
	AB	2007	7	2007	10	30	2007	10	30	7	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia acuminata</i>	1,540	-	-	-	6.5
	AB	2007	8	2007	7	25	2007	7	25	7	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia pungens</i>	56,800	-	-	-	31.2
	AB	2007	9	2007	9	17	2007	10	9	22	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia pungens</i>	4,800	-	-	-	22.0
	AB	2007	10	2007	7	25	2007	7	25	7	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia</i>	3,600	-	-	-	26.7
																18.0-22.0	23.5-26.7			

Annex II-2 Toxin-producing plankton bloom and shellfish poisoning (Continued)

Country	Event No.		Duration (Start)			Duration (End)			Location of occurrence		Monitoring date		Causative species (*1)	Fish/shellfish damage		Environmental parameters (*2)				
	Ref. Code	Year	No.	Month	day	Year	Month	day	Sub-area	Spot	Date	Time		Fish/shellfish species	Shellfish poisoning	Toxin level (µg/L)	Temp. (°C)	Salinity (‰)		
AB	2008	1	2008	3	4	2008	4	7	Amurskii Bay	-	-	-	<i>Dinobryon balicum</i>	1,054,280	-	-	-1.8-5.5	30.6-33.6		
AB	2008	2	2008	9	15	2008	9	15	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia acuminata</i>	2,640	-	-	-	20.9	29.7	
AB	2008	3	2008	7	28	2008	9	29	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia delicatissima</i>	8,800	-	-	-	15.2-23.5	22.5-30.5	
AB	2008	4	2008	3	4	2008	3	4	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia multisira</i>	270	-	-	-	-1.8	32.6	
AB	2008		2008	4	9	2008	11	4	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia spp.</i>	-	<i>Ceromyscus gravatus</i>	ASP	0.01	-	-	
AB	2008		2008	4	11	2008	4	11	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia spp.</i>	-	<i>Modiolus modiolus</i>	ASP	0.02	5.5	-	
AB	2008	5	2008	7	28	2008	7	28	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia multisira</i>	1,257	-	-	-	23.5	22.5	
AB	2008	6	2008	6	7	2008	6	7	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia pungens</i>	640	-	-	-	16.7	18.8	
AB	2008	7	2008	7	14	2008	7	14	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia pungens</i>	330	-	-	-	23.2	26.0	
AB	2008	8	2008	8	29	2008	9	15	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia pungens</i>	1,320	-	-	-	20.5-20.9	28.1-29.8	
AB	2008	9	2008	12	19	2008	12	19	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia pungens</i>	857	-	-	-	-1.6	33.4	
AB	2008	11	2008	6	7	2008	6	7	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis acuminata</i>	3,200	<i>Crassostrea gigas</i>	DSP	81.1	16.2	18.8	
AB	2008	12	2008	5	5	2008	7	14	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis acuminata</i>	4,480	<i>Modiola modiolus</i>	DSP	125.9	9.0-23.3	18.6-28.6	
AB	2008	13	2008	8	11	2008	8	11	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis acuminata</i>	1,900	<i>Ceromyscus gravatus</i>	DSP	155.1	22.7	26.7	
AB	2009	1	2009	3	12	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis acuta</i>	100	-	-	-	0.5	33.08	
AB	2009	2	2009	6	8	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia pungens</i>	200	-	-	-	-14.1	30.0	
AB	2009	3	2009	6	8	2009	7	1	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis acuminata</i>	1,400	-	-	-	14.1-17.2	30	
AB	2009	4	2009	8	2	2009	8	25	Amurskii Bay	Amurskii Bay	-	-	<i>Dinophysis acuminata</i>	2,600	-	-	-	22.5-23.0	20.0-27.0	
AB	2009	5	2009	10	26	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia cf.</i>	1,800	-	-	-	10.5	30.55	
AB	2009	6	2009	10	26	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia</i>	19,200	-	-	-	10.5	-	
AB	2010	1	2010	1	28	2010	2	10	13	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia pungens</i>	500	-	-	-	-1.8	32.99
AB	2010	2	2010	1	28	2010	2	10	13	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia cf.</i>	200	-	-	-	-1.8	32.99
AB	2010	3	2010	7	30	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia pungens</i>	2,000	-	-	-	22.5-23.5	22.59	
AB	2010	4	2010	8	31	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia cf.</i>	32,800	-	-	-	24.0	27.74	
AB	2010	5	2010	8	31	-	-	-	Amurskii Bay	Amurskii Bay	-	-	<i>Pseudo-nitzschia cf.</i>	800	-	-	-	24.0	27.74	

*1 Scientific name is based on the Integrated Report on Harmful Algal Blooms (HABs) for the NW/PAP Region (NOWPAP CEARAC, 2005).

*2 In case of Japan and Russia, the range of environmental parameters means the value which observed during event.

*3 In case of Japan, the unit of toxin level is µg/g. The unit of other member states is ng/g.

Annex II-3 Water Quality Information

Country	Organization	Monitoring date			Location Monitoring point (1)	Transparency (m)	Salinity (°C)	DO (mg/L)	pH	DIN (µM) (*2)	NO3-N (µM) (*2)	NO2-N (µM)	NH4-N (µM)	DIP	PO4-P (µM)	SiO2-Si (µM)	SiO3-Si (µM)	Chl-a
		Year	Month	day														
China (*1) North China Sea Environmental Monitoring Centre	2007 8/20-23 Coastal areas of Qingdao	6	-	-	22.7-25.1	29.1-29.6	6.66-7.42	6.97-8.05	-	5.1-14.1	2.3-2.8	1.3-5.5	-	0.07-0.20	-	12.1-16.8	-	
		8	-	-	22.7-25.2	28.5-29.5	6.90-7.46	7.93-8.09	-	6.0-18.6	2.1-3.0	1.7-14.3	-	0.04-0.12	-	8.6-15.4	-	
		9	-	-	23.0-25.2	29.0-29.5	6.89-7.49	7.96-8.14	-	6.0-12.2	1.9-2.3	1.0-5.9	-	0.03-0.12	-	11.0-16.0	-	
		14	-	-	23.6-25.1	29.0-29.3	6.91-7.57	7.93-8.20	-	6.7-9.4	1.9-2.1	1.7-3.8	-	0.03-0.16	-	10.4-11.0	-	
		15	-	-	23.5-25.2	29.0-29.3	7.04-7.68	7.94-8.19	-	4.0-9.9	1.9-2.3	1.7-5.0	-	0.04-0.17	-	10.1-13.5	-	
		18	-	-	24.1-25.3	28.2-29.2	7.15-7.68	8.00-8.16	-	8.7-18.9	2.2-3.2	2.3-4.3	-	0.07-0.16	-	9.0-11.6	-	
		19	-	-	23.9-25.1	28.5-29.2	7.17-7.81	7.99-8.19	-	4.1-13.2	1.8-2.6	1.2-4.3	-	0.07-0.15	-	8.6-11.6	-	
		20	-	-	24.2-25.3	27.9-28.7	7.22-7.73	7.97-8.16	-	12.4-15.9	2.3-2.8	2.4-3.8	-	0.06-0.17	-	9.7-11.6	-	
		21	-	-	24.2-25.3	28.4-28.6	7.20-7.71	7.98-8.15	-	7.9-19.3	2.4-3.2	0.5-3.8	-	0.07-0.13	-	8.8-11.4	-	
		8	-	-	24.4	29.6	7.17	8.18	-	1.95	0.40	0.34	-	0.05	-	2.63	36.8	
		9	-	-	24.6	29.6	7.17	8.21	-	1.61	0.38	0.33	-	0.03	-	2.7	-	
		14	-	-	24.5	29.4	6.93	8.20	-	1.68	0.38	1.88	-	0.04	-	4.01	-	
		15	-	-	25.0	25.4	8.05	8.26	-	1.60	0.34	2.52	-	0.02	-	2.63	-	

*1 Monitoring points are shown in the map of another sheet (map of monitoring sites)

*2 The range of each parameter means the value observed between 20-23 August

*3 The concentration of nutrient is standardized into common unit (µM)

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date	Location	Monitoring point	Transparency (m)	SST (°C)	Salinity (mg/L)	pH	DIN (µM)	NO3-N (µM)	NO2-N (µM)	DIP (µM)	PO4-P (µM)	SiO2-Si	SiO3-Si	Chl-a (µg/L)	
Japan	Fukuoka Fisheries and Marine Technology Research Center	Year	Month	Day	Time	Area	Monitoring point										
		2006	4	-	-	-	-	14.6	27.9	-	19.46	-	-	0.32	-	-	
		5	-	-	-	-	-	17.6	31.1	-	30.40	-	-	0.53	-	-	
		6	-	-	-	-	-	21.7	31.3	-	19.60	-	-	0.09	-	-	
		7	-	-	-	-	-	23.8	31.6	-	10.90	-	-	0.46	-	-	
		8	-	-	-	-	-	30.1	29.9	-	10.90	-	-	0.10	-	-	
		9	-	-	-	-	-	24.4	29.9	-	16.10	-	-	0.57	-	-	
		10	-	-	-	-	-	22.5	31.6	-	11.40	-	-	0.12	-	-	
		11	-	-	-	-	-	17.6	32.3	-	13.30	-	-	0.22	-	-	
		12	-	-	-	-	-	14.3	32.2	-	36.30	-	-	0.65	-	-	
		5	1	-	-	-	-	16.9	32.0	8.40	0.39	0.14	0.07	0.18	0.00	-	1.70
		6	1	-	-	-	-	Imari Bay	1	4.3	32.0	8.40	0.04	0.02	0.10	0.00	-
		7	3	-	-	-	-	Imari Bay	2	4.1	17.0	31.6	8.20	0.16	0.04	0.00	-
		8	1	-	-	-	-	Imari Bay	3	4.5	17.2	31.7	8.90	0.12	0.05	0.01	0.06
		9	1	-	-	-	-	Imari Bay	4	5.7	21.5	31.7	7.90	0.18	0.10	0.00	0.07
		10	2	-	-	-	-	Imari Bay	5	3.9	21.9	31.4	8.10	0.15	0.05	0.00	0.00
		11	1	-	-	-	-	Imari Bay	6	4.7	21.4	31.4	8.40	0.13	0.06	0.01	0.06
		12	2	-	-	-	-	Imari Bay	7	2.9	25.6	25.0	8.90	0.29	0.17	0.01	0.11
		1	3	-	-	-	-	Imari Bay	8	2.8	25.6	25.2	8.40	0.16	0.06	0.01	0.10
		9	1	-	-	-	-	Imari Bay	9	2.8	25.2	25.3	8.30	0.13	0.05	0.01	0.08
		10	2	-	-	-	-	Imari Bay	10	4.8	29.9	26.3	7.80	0.09	0.09	0.00	0.00
		11	1	-	-	-	-	Imari Bay	11	4.5	29.7	26.6	7.80	0.06	0.05	0.00	0.06
		12	2	-	-	-	-	Imari Bay	12	3.9	29.7	27.0	8.10	0.04	0.04	0.00	0.00
		1	3	-	-	-	-	Imari Bay	13	7.3	26.8	30.1	6.90	0.29	0.09	0.00	0.20
		9	1	-	-	-	-	Imari Bay	14	6.6	26.9	29.2	6.50	0.34	0.12	0.01	0.22
		10	2	-	-	-	-	Imari Bay	15	3.8	28.5	29.6	6.30	0.46	0.31	0.00	0.15
		11	1	-	-	-	-	Imari Bay	16	4.7	23.4	30.9	6.30	0.20	0.13	0.01	0.07
		12	2	-	-	-	-	Imari Bay	17	3.8	23.3	30.9	6.00	0.09	0.14	0.01	0.04
		1	3	-	-	-	-	Kanoya Bay	18	4.2	23.1	30.1	6.90	0.38	0.10	0.01	0.27
		9	4	-	-	-	-	Kanoya Bay	19	7.5	16.9	32.2	8.00	0.46	0.16	0.04	0.27
		10	3	-	-	-	-	Kanoya Bay	20	4.8	20.3	32.7	9.10	0.34	0.22	0.01	0.12
		11	2	-	-	-	-	Kanoya Bay	21	6.0	24.7	24.7	8.30	0.18	0.50	0.02	0.16
		12	1	-	-	-	-	Kanoya Bay	22	8.5	29.1	28.8	8.20	0.54	0.51	0.01	0.02
		1	3	-	-	-	-	Nagoyaura	4	2.7	27.2	26.5	9.10	0.84	0.53	0.01	0.31
		9	1	-	-	-	-	Nagoyaura	10	5.2	23.0	31.2	5.70	0.49	0.16	0.02	0.30
		10	2	-	-	-	-	Nagoyaura	11	4	8.6	16.8	31.6	8.20	0.76	0.58	0.04
		11	5	-	-	-	-	Nagoyaura	12	6.2	19.4	33.7	9.20	0.42	0.09	0.01	0.14
		12	7	-	-	-	-	Nagoyaura	13	7.9	23.0	31.0	7.20	0.88	0.67	0.02	0.33
		1	8	-	-	-	-	Nagoyaura	14	7.5	26.7	29.0	8.40	0.50	0.42	0.01	0.06
		9	1	-	-	-	-	Nagoyaura	15	10.6	25.1	31.6	6.40	0.26	0.10	0.01	0.15
		10	2	-	-	-	-	Nagoyaura	16	6.7	23.1	31.7	6.10	0.38	0.26	0.02	0.10
		11	5	-	-	-	-	Nagoyaura	17	6.0	16.9	32.8	9.00	0.16	0.07	0.02	0.07
		12	6	-	-	-	-	Nagoyaura	18	5.5	20.8	33.4	8.60	0.11	0.04	0.01	0.07
		1	7	-	-	-	-	Hokawazu	19	3.9	24.0	39.1	8.50	1.76	1.45	0.02	0.29
		8	2	-	-	-	-	Hokawazu	20	6.2	28.0	31.8	9.10	0.24	0.16	0.01	0.06
		9	4	-	-	-	-	Hokawazu	21	4.3	26.4	31.2	7.30	0.28	0.18	0.01	0.10
		10	3	-	-	-	-	Hokawazu	22	5.1	23.3	31.0	7.10	0.50	0.40	0.02	0.09
		11	3	-	-	-	-		23	-	-	-	-	-	0.01	-	3.60

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date			Location Monitoring point	Transparency (m)	SST (°C)	Salinity (mg/L)	DO (µM)	pH	DIN (µM)	NO3-N (µM)	NO2-N (µM)	NH4-N (µM)	DIP	PO4-P (µM)	SiO2-Si	SiO3-Si	Chl-a (µg/L)		
		Year	Month	day																	
Nagasaki Prefectural Institute of Fisheries	Japan	6	21	-	Imari Bay	1	9.0	33.4	5.00	-	0.66	0.25	0.01	0.40	-	0.01	-	-	0.90		
		7	18	-	Imari Bay	3	5.0	23.5	32.7	5.00	-	0.26	0.04	0.03	0.19	-	0.06	-	-	1.50	
		8	7	-	Imari Bay	4	6.0	23.5	32.7	5.20	-	0.41	0.05	0.06	0.30	-	0.02	-	-	1.60	
		8	29	-	Ohmura Bay	1	8.0	24.1	32.7	5.20	-	-	-	-	-	-	-	-	-	2.70	
		10	18	-	Imari Bay	3	7.0	26.8	31.8	4.70	-	-	-	-	-	-	-	-	-	2.10	
		9	20	-	Ohmura Bay	4	5.0	23.5	33.1	5.00	-	0.44	0.08	0.04	0.32	-	0.03	-	-	4.80	
		5	1	-	Imari Bay	3	3.5	22.9	32.8	4.70	-	0.37	0.05	0.04	0.28	-	0.02	-	-	2.30	
		9	35	-	Imari Bay	4	4.5	22.7	32.9	4.80	-	0.95	0.67	0.06	0.22	-	0.03	-	-	2.00	
		9	40	-	Imari Bay	5	2.5	28.0	30.1	4.50	-	0.52	0.19	0.04	0.29	-	0.05	-	-	0.60	
		9	45	-	Imari Bay	6	3.0	28.5	30.0	4.20	-	1.65	0.17	0.07	1.41	-	0.03	-	-	1.00	
Saga Prefectural Fisheries Promotion Center	Japan	6	4	-	Imari Bay	7	3.0	30.2	29.6	5.30	-	1.41	0.10	0.07	1.24	-	0.07	-	-	3.10	
		7	2	-	Imari Bay	8	3.0	29.5	29.7	4.90	-	0.44	0.04	0.07	0.33	-	0.12	-	-	3.00	
		9	27	-	Imari Bay	9	1	6.5	26.5	29.5	5.00	-	4.65	3.98	0.34	0.33	-	0.07	-	-	18.7
		9	30	-	Imari Bay	10	05	5.2	18.1	31.9	7.30	-	0.11	0.03	0.01	0.07	-	0.06	-	-	3.70
		9	35	-	Imari Bay	11	4.0	18.4	31.7	8.30	-	0.16	0.06	0.01	0.09	-	0.05	-	-	3.90	
		9	40	-	Imari Bay	12	4.5	26.5	31.6	4.60	-	0.99	0.39	0.12	0.48	-	0.17	-	-	3.90	
		9	45	-	Imari Bay	13	6.5	18.3	31.0	7.60	-	0.30	0.11	0.01	0.18	-	0.00	-	-	1.54	
		9	50	-	Imari Bay	14	5.2	18.1	31.9	7.30	-	0.11	0.03	0.01	0.07	-	0.00	-	-	2.21	
		9	55	-	Imari Bay	15	4.0	18.4	31.7	8.30	-	0.16	0.06	0.01	0.09	-	0.00	-	-	1.82	
		9	60	-	Imari Bay	16	5.5	21.8	34.0	6.80	-	0.15	0.14	0.00	0.01	-	0.04	-	-	0.47	
Nagasaki Prefectural Institute of Fisheries	Japan	9	20	-	Imari Bay	17	4.5	26.5	31.6	4.60	-	1.24	0.42	0.24	0.58	-	0.22	-	-	9.50	
		9	25	-	Imari Bay	18	3.0	29.5	29.7	4.90	-	0.44	0.04	0.07	0.33	-	0.12	-	-	3.00	
		9	30	-	Imari Bay	19	3.5	25.6	29.5	5.00	-	4.65	3.98	0.34	0.33	-	0.07	-	-	18.7	
		9	35	-	Imari Bay	20	3.5	26.5	31.0	5.00	-	0.73	0.23	0.05	0.45	-	0.06	-	-	3.70	
		9	40	-	Imari Bay	21	5.0	26.5	31.6	4.50	-	0.99	0.39	0.12	0.48	-	0.17	-	-	3.90	
		9	45	-	Imari Bay	22	4.5	26.5	31.6	4.60	-	1.24	0.42	0.24	0.58	-	0.22	-	-	9.50	
		9	50	-	Imari Bay	23	6.5	18.3	31.0	7.60	-	0.30	0.11	0.01	0.18	-	0.00	-	-	1.54	
		9	55	-	Imari Bay	24	5.2	18.1	31.9	7.30	-	0.11	0.03	0.01	0.07	-	0.00	-	-	2.21	
		9	60	-	Imari Bay	25	4.0	18.4	31.7	8.30	-	0.16	0.06	0.01	0.09	-	0.00	-	-	1.82	
		9	65	-	Imari Bay	26	5.5	21.8	34.0	6.80	-	0.15	0.14	0.00	0.01	-	0.04	-	-	0.47	
Nagasaki Prefectural Institute of Fisheries	Japan	9	70	-	Imari Bay	27	4.2	21.7	34.1	6.40	-	0.08	0.06	0.01	0.02	-	0.06	-	-	0.94	
		9	75	-	Imari Bay	28	3.0	29.5	29.7	4.90	-	0.10	0.08	0.00	0.01	-	0.05	-	-	0.70	
		9	80	-	Imari Bay	29	3.5	25.6	34.0	6.40	-	0.38	0.12	0.01	0.25	-	0.00	-	-	3.50	
		9	85	-	Imari Bay	30	3.9	25.4	33.6	6.20	-	0.17	0.06	0.01	0.10	-	0.01	-	-	6.60	
		9	90	-	Imari Bay	31	3.5	25.2	33.2	6.20	-	0.14	0.08	0.01	0.06	-	0.01	-	-	6.2	
		9	95	-	Imari Bay	32	3.7	28.2	29.6	7.90	-	1.35	0.27	0.01	1.08	-	0.00	-	-	2.40	
		9	100	-	Imari Bay	33	4.1	28.2	29.5	6.70	-	0.22	0.06	0.01	0.15	-	0.01	-	-	4.10	
		9	105	-	Imari Bay	34	2.7	28.5	32.2	6.40	-	0.41	0.18	0.01	0.22	-	0.01	-	-	1.60	
		9	110	-	Imari Bay	35	1.8	28.5	32.5	5.70	-	0.33	0.19	0.03	0.11	-	0.01	-	-	12.00	
		9	115	-	Imari Bay	36	2.1	27.5	30.0	6.90	-	0.63	0.38	0.01	0.20	-	0.01	-	-	14.90	
Saga Prefectural Fisheries Promotion Center	Japan	9	120	-	Imari Bay	37	1.1	27.9	29.7	7.00	-	0.22	0.06	0.01	0.15	-	0.01	-	-	4.10	
		9	125	-	Imari Bay	38	1.1	27.5	30.6	7.30	-	0.63	0.38	0.05	0.20	-	0.01	-	-	7.20	
		9	130	-	Imari Bay	39	1.1	26.1	30.6	6.70	-	0.68	0.11	0.01	0.56	-	0.01	-	-	10.10	
		9	135	-	Imari Bay	40	1.1	26.0	30.6	6.70	-	0.26	0.07	0.05	0.14	-	0.02	-	-	8.60	
		9	140	-	Imari Bay	41	1.1	26.1	30.6	6.70	-	1.31	0.19	0.10	1.01	-	0.03	-	-	8.60	
		9	145	-	Imari Bay	42	1.1	26.0	32.7	6.30	-	0.26	0.07	0.05	0.14	-	0.02	-	-	8.60	
		9	150	-	Imari Bay	43	1.1	26.1	32.7	6.30	-	0.26	0.07	0.05	0.14	-	0.02	-	-	8.60	
		9	155	-	Imari Bay	44	1.1	26.0	32.7	6.30	-	0.26	0.07	0.05	0.14	-	0.02	-	-	8.60	
		9	160	-	Imari Bay	45	1.1	26.1	32.7	6.30	-	0.26	0.07	0.05	0.14	-	0.02	-	-	8.60	
		9	165	-	Imari Bay	46	1.1	26.0	32.7	6.30	-	0.26	0.07	0.05	0.14	-	0.02	-	-	8.60	

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date			Location Monitoring point	Transparency (m)	SST (°C)	Salinity (mg/L)	DO (µM)	pH	DIN (µM)	NO3-N (µM)	NO2-N (µM)	NH4-N (µM)	DIP	PO4-P (µM)	SiO2-Si	SiO3-Si	Chl-a (µg/L)	
		Year	Month	day																
Saga Prefectural Fisheries Promotion Center	2007	5	2	10:02	A	6.5	18.0	32.8	8.60	-	0.38	0.09	0.01	0.28	-	0.01	-	-	3.70	
		6	5	10:03	A	6.1	22.6	33.4	7.90	-	0.18	0.17	0.01	0.01	-	0.21	-	-	2.40	
		7	3	10:25	Kanya Bay	2.1	25.3	28.5	7.00	-	0.72	0.55	0.02	0.15	-	0.00	-	-	7.20	
		8	2	10:05	A	4.6	27.4	32.1	8.10	-	0.35	0.15	0.02	0.18	-	0.00	-	-	7.60	
		9	4	9:54	A	3.9	28.0	32.0	6.10	-	0.47	0.28	0.02	0.18	-	0.01	-	-	11.60	
		10	2	10:49	A	4.9	25.4	33.0	7.40	-	0.27	0.10	0.01	0.17	-	0.00	-	-	6.20	
		5	1	11:55	4	7.5	18.0	32.4	7.10	-	0.34	0.19	0.01	0.14	-	0.01	-	-	1.30	
		6	4	11:40	4	7.0	20.8	32.5	7.20	-	0.08	0.07	0.00	0.01	-	0.04	-	-	1.60	
		7	3	11:25	Nagoyaura	4	6.2	23.4	34.1	6.20	-	0.64	0.30	0.01	0.33	-	0.01	-	-	2.00
		8	1	11:45	4	3.7	26.1	29.7	7.30	-	0.21	0.09	0.01	0.10	-	0.01	-	-	3.40	
		9	3	11:07	4	4.7	27.5	32.0	5.80	-	1.11	0.81	0.04	0.26	-	0.01	-	-	4.20	
Japan	Prefectural Institute of Fisheries	10	1	12:05	4	8.2	26.3	33.0	7.30	-	0.38	0.14	0.01	0.23	-	0.01	-	-	8.00	
		5	2	10:32	5	10.9	18.1	32.6	8.70	-	0.28	0.13	0.01	0.13	-	0.01	-	-	2.00	
		6	5	10:33	5	4.3	21.8	33.8	8.50	-	0.17	0.16	0.00	0.01	-	0.04	-	-	2.40	
		7	3	10:50	Hokawazu	5	2.3	24.9	29.6	6.40	-	1.09	0.80	0.02	0.27	-	0.01	-	-	3.30
		8	2	10:40		5	4.8	25.8	33.9	7.40	-	0.11	0.04	0.01	0.06	-	0.00	-	-	4.80
		9	4	10:25		5	5.3	27.9	32.9	7.00	-	0.52	0.25	0.01	0.26	-	0.01	-	-	3.50
		10	2	11:18		5	4.0	25.2	33.2	7.20	-	0.21	0.09	0.01	0.11	-	0.00	-	-	6.20
					11:31	1	7.5	22.3	34.0	4.80	-	0.67	0.24	0.05	0.39	-	0.11	-	-	0.90
		6	19	10:40	Imari Bay	3	6.0	21.8	33.9	4.70	-	0.68	0.33	0.06	0.30	-	0.15	-	-	1.10
		7	31	10:54		4	9.0	21.6	34.0	4.80	-	1.03	0.50	0.04	0.50	-	0.42	-	-	2.20
		8	44		1	10.5	28.6	33.2	4.40	-	1.03	0.54	0.09	0.41	-	0.12	-	-	0.80	
		8	28	10:17	Imari Bay	3	5.5	29.9	33.2	4.60	-	0.60	0.21	0.07	0.32	-	0.09	-	-	2.00
					9:56	4	8.5	29.6	33.2	4.60	-	0.68	0.19	0.06	0.43	-	0.09	-	-	0.70
					14:00	b	3.0	31.3	30.6	4.90	-	0.94	0.24	0.10	0.60	-	0.08	-	-	0.40
Nagasaki Prefectural Institute of Fisheries	2007	7	31	13:26	Ohmura Bay	c	3.0	31.6	30.2	5.10	-	0.63	0.31	0.06	0.27	-	0.09	-	-	1.50
					10:29	P	4.0	29.1	30.8	4.80	-	2.13	1.00	0.07	1.06	-	0.08	-	-	1.20
					11:42	Z	3.8	28.9	30.8	4.90	-	0.53	0.16	0.07	0.30	-	0.07	-	-	2.10
					14:00	b	3.0	31.3	30.6	4.90	-	0.25	0.15	0.04	0.05	-	0.08	-	-	4.9
		10	11	13:26	Ohmura Bay	c	3.0	31.6	30.2	5.10	-	1.57	0.52	0.28	0.76	-	0.40	-	-	1.30
		10	11	10:29	Ohmura Bay	P	4.0	29.1	30.8	4.80	-	0.40	0.05	0.09	0.09	-	0.24	-	-	0.70
					11:42	Z	3.8	28.9	30.8	4.90	-	1.51	0.66	0.11	0.75	-	0.34	-	-	0.70

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date			Location Monitoring point	Transparency (m)	SST (°C)	Salinity	DO (mg/L)	pH	DIN (µM)	NO3-N (µM)	NO2-N (µM)	NH4-N (µM)	DIP (µM)	PO4-P (µM)	SiO2-Si	SiO3-Si	Chl-a (µg/L)
		Year	Month	day															
Japan	Fukuoka Fisheries and Marine Technology Research Center	2008	Ariake Sea	4	9:48	1	16.2	30.1	7.55	-	12.79	-	-	-	0.67	-	-	-	
				4	22	2	14	31.1	7.70	-	8.62	-	-	-	0.45	-	-	-	
				8:50		3	14	28.9	7.80	-	12.66	-	-	-	0.50	-	-	-	
				9:32		4	16	31.3	7.79	-	6.67	-	-	-	0.32	-	-	-	
				9:12		1	0.5	20.7	30.6	7.21	-	3.81	-	-	0.38	-	-	-	
				8:55		2	1.3	19.9	30.9	7.37	-	2.14	-	-	0.31	-	-	-	
				8:44		3	1.2	20.0	30.3	7.53	-	2.75	-	-	0.44	-	-	-	
				9:36		4	1.4	19.9	31.8	7.42	-	1.44	-	-	0.25	-	-	-	
				11:01		1	1.2	23.0	22.6	6.57	-	14.72	-	-	0.66	-	-	-	
				6:23		2	2.4	23.0	26.1	6.64	-	13.35	-	-	0.45	-	-	-	
				10:15		3	1.8	23.0	21.0	7.03	-	26.15	-	-	0.85	-	-	-	
				10:43		4	1.8	22.7	26.0	6.85	-	12.93	-	-	0.54	-	-	-	
				15:06		1	0.9	32.0	26.9	8.04	-	0.00	-	-	0.70	-	-	-	
				7:28		2	1.3	32.2	27.6	8.33	-	0.26	-	-	0.40	-	-	-	
				14:32		3	1.1	31.8	26.7	8.92	-	0.02	-	-	0.55	-	-	-	
				14:20		4	1.3	30.0	28.6	7.42	-	1.15	-	-	0.29	-	-	-	
				14:47		1	1.3	31.2	26.1	12.10	-	0.59	-	-	0.57	-	-	-	
				15:15		2	1.2	31.2	26.5	10.95	-	0.92	-	-	0.57	-	-	-	
				8:11		3	1.4	31.0	24.4	13.02	-	0.38	-	-	0.55	-	-	-	
				14:37		4	1.6	30.3	29.8	10.51	-	0.14	-	-	0.38	-	-	-	
				14:29		1	1.4	27.5	28.8	5.27	-	16.28	-	-	1.25	-	-	-	
				13:54		2	1.9	28.0	28.0	6.13	-	14.88	-	-	1.19	-	-	-	
				13:44		3	1.6	28.2	26.4	9.46	-	0.05	-	-	0.47	-	-	-	
				14:09		4	3.2	27.3	30.0	5.43	-	9.87	-	-	1.01	-	-	-	
				15:23		1	1.2	28.4	25.0	14.16	-	0.22	-	-	0.20	-	-	-	
				9:24		2	1.4	29.2	25.3	15.00	-	0.00	-	-	0.11	-	-	-	
				14:32		3	1.6	28.7	24.0	15.33	-	0.01	-	-	0.12	-	-	-	
				15:02		4	1.8	28.2	29.9	11.64	-	0.00	-	-	0.13	-	-	-	
				16:15		1	1.3	23.1	28.9	6.67	-	19.90	-	-	1.55	-	-	-	
				15:27		2	1.3	23.2	30.5	6.15	-	19.09	-	-	1.24	-	-	-	
				10:23		3	1.3	23.2	30.1	6.57	-	15.41	-	-	1.40	-	-	-	
				15:14		4	1.7	23.4	30.2	6.20	-	11.99	-	-	1.06	-	-	-	
				15:45		1	0.9	16.5	30.3	8.21	-	14.05	-	-	1.08	-	-	-	
				11:19		2	0.9	16.7	30.2	8.03	-	13.86	-	-	1.17	-	-	-	
				13:16		3	0.6	16.6	29.3	8.43	-	16.26	-	-	1.37	-	-	-	
				13:40		4	0.6	16.6	30.5	8.19	-	12.46	-	-	1.09	-	-	-	
				11:29		1	1.3	13.5	29.9	8.84	-	15.64	-	-	1.06	-	-	-	
				10:30		2	0.9	13.3	29.6	8.54	-	15.56	-	-	0.92	-	-	-	
				10:18		3	0.9	13.0	28.5	8.92	-	19.87	-	-	1.09	-	-	-	
				11:08		4	1.8	13.8	30.3	8.48	-	12.92	-	-	0.80	-	-	-	

Annex II-3 Water Quality Information (Continued)

Country	Organization	Year	Month	Day	Time	Area	Location Monitoring point	Transparency (m)	SST (°C)	Salinity (mg/L)	DO (µM)	pH	DIN (µM)	NO3-N (µM)	NO2-N (µM)	NH4-N (µM)	DIP	PO4-P (µM)	SiO2-Si	SiO3-Si	Chl-a (µg/L)		
Japan	Fukuoka Fisheries and Marine Technology Research Center	2009	1	14	11:24		1	1.1	9.2	297	9.86	-	12.31	-	-	-	0.64	-	-	-	-		
			2	24	10:27	Atiake Sea	2	1.1	9.1	295	9.77	-	11.24	-	-	-	0.62	-	-	-	-		
			3	10:17			3	0.8	8.7	287	10.04	-	15.07	-	-	-	0.71	-	-	-	-		
			4	11:05			4	1.8	9.6	302	9.80	-	10.42	-	-	-	0.56	-	-	-	-		
			5	9:54			1	1.8	11.4	274	9.85	-	13.03	-	-	-	1.14	-	-	-	-		
			6	8:56			2	1.8	11.4	303	9.36	-	12.1	-	-	-	0.25	-	-	-	-		
			7	8:44			3	1.8	11.2	279	9.48	-	8.46	-	-	-	0.70	-	-	-	-		
			8	9:35			4	2.6	11.8	311	8.84	-	4.02	-	-	-	0.37	-	-	-	-		
			9	10:34			1	1.7	11.9	304	9.21	-	4.41	-	-	-	0.40	-	-	-	-		
			10	9:42			2	1.7	11.8	304	9.08	-	4.38	-	-	-	0.43	-	-	-	-		
			11	9:23			3	1.1	11.8	296	9.08	-	6.81	-	-	-	0.49	-	-	-	-		
			12	10:03			4	2.3	12.2	313	9.10	-	2.66	-	-	-	0.31	-	-	-	-		
			13	9:36			1	5.0	18.4	332	7.10	-	15.32	11.45	0.21	3.66	-	0.12	-	-	1.17		
			14	9:29			2	4.2	18.5	329	6.94	-	5.93	1.27	0.21	4.45	-	0.24	-	-	1.45		
			15	9:47			1	4.0	21.7	317	6.21	-	3.75	1.33	0.12	4.45	-	0.12	-	-	4.39		
			16	9:35			2	3.5	21.6	311	7.51	-	2.03	0.83	0.14	1.06	-	0.16	-	-	12.65		
			17	9:40			1	3.7	23.0	289	8.55	-	12.14	3.09	0.20	8.85	-	0.06	-	-	3.22		
			18	9:30			2	2.5	22.4	275	8.14	-	10.80	7.95	0.35	2.50	-	0.20	-	-	5.74		
			19	9:46			1	5.2	30.3	328	7.55	-	1.15	0.34	0.06	0.75	-	0.09	-	-	7.56		
			20	9:24			2	5.0	30.1	328	7.21	-	2.25	0.91	0.05	1.29	-	0.13	-	-	14.06		
			21	9:52			1	3.5	27.4	313	9.86	-	5.92	3.50	0.37	2.05	-	0.18	-	-	3.4		
			22	9:32			2	3.1	27.4	302	9.66	-	2.47	0.98	0.24	1.25	-	0.20	-	-	4.93		
			23	10:55			1	5.0	23.7	334	5.40	-	10.95	2.98	1.29	6.67	-	0.61	-	-	6.45		
			24	9:44			2	3.3	23.8	330	4.89	-	8.19	3.25	1.55	3.39	-	0.98	-	-	6.06		
			25	9:2			A	6.0	17.9	336	6.36	-	1.98	3.85	0.26	7.87	-	0.18	-	-	2.01		
			26	9:50			A	3.9	20.0	330	5.12	-	7.95	3.20	0.10	4.65	-	0.14	-	-	6.22		
			27	9:47			A	4.5	21.5	287	6.19	-	36.46	32.71	0.70	3.05	-	0.28	-	-	7.29		
			28	9:38			A	3.3	29.2	306	6.86	-	8.91	4.32	0.24	4.35	-	0.18	-	-	12.57		
			29	1:1			A	3.9	26.1	315	6.70	-	9.70	6.58	0.12	3.00	-	0.70	-	-	6.90		
			30	10:30			A	3.9	23.8	330	4.89	-	8.19	3.25	1.55	3.39	-	0.98	-	-	6.06		
			31	10:20			A	1.8	23.8	314	9.08	-	33.42	27.34	0.63	5.45	-	0.07	-	-	18.80		
			32	11:36			4	6.8	17.1	341	7.73	-	16.99	9.36	0.20	7.43	-	0.11	-	-	2.25		
			33	11:27			4	5.0	20.5	327	5.72	-	4.37	2.56	0.17	1.64	-	0.22	-	-	6.79		
			34	10:57			7	2	22.4	281	6.50	-	30.24	25.19	0.61	4.44	-	0.53	-	-	2.79		
			35	11:34			8	6	8.5	27.4	328	7.05	-	19.94	2.07	0.05	17.82	-	0.21	-	-	6.15	
			36	9:1			9	11:14	4	3.5	24.5	329	6.54	-	14.70	8.76	1.03	4.91	-	0.14	-	-	9.72
			37	11:34			10	3	23.1	328	5.29	-	13.12	9.45	0.68	2.99	-	0.12	-	-	2.54		
			38	5			5	2	18.3	341	6.75	-	4.27	1.06	0.17	3.04	-	0.12	-	-	2.27		
			39	3			6	3	19.9	332	6.18	-	2.72	1.76	0.11	0.85	-	0.19	-	-	2.80		
			40	2			7	2	21.3	306	6.06	-	37.37	32.86	0.50	4.01	-	0.53	-	-	2.45		
			41	5			8	5	28.4	319	6.95	-	7.12	5.88	0.17	1.27	-	0.16	-	-	3.89		
			42	10:07			9	2	25.6	330	8.50	-	8.46	6.25	0.30	1.91	-	0.21	-	-	6.85		
			43	11:37			10	2	24.0	345	5.90	-	10.18	3.27	0.81	6.10	-	0.54	-	-	6.60		

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date	Location Monitoring point	Transparency (m)	SST (°C)	Salinity (mg/L)	pH	DIN (µM)	NO2-N (µM)	NO3-N (µM)	NH4-N (µM)	DIP	PO4-P (µM)	SiO2-Si	SiO3-Si	Chl-a (µg/L)
Year	Month	day	Time	Area												
				1	-	14.6	-	-	3.39	-	-	-	0.44	-	-	-
				2	-	14.4	-	-	2.91	-	-	-	0.40	-	-	-
				3	-	13.7	-	-	2.05	-	-	-	0.28	-	-	-
				4	-	13.3	-	-	1.33	-	-	-	0.22	-	-	-
				5	-	13.3	-	-	2.03	-	-	-	0.28	-	-	-
				6	-	14.1	-	-	3.93	-	-	-	0.42	-	-	-
				7	-	14.0	-	-	2.19	-	-	-	0.31	-	-	-
				8	-	13.8	-	-	3.91	-	-	-	0.46	-	-	-
				9	-	14.7	-	-	4.30	-	-	-	0.53	-	-	-
				10	-	14.7	-	-	6.84	-	-	-	0.74	-	-	-
				11	-	13.4	-	-	2.15	-	-	-	0.27	-	-	-
				1	-	19.1	-	-	1.81	-	-	-	0.53	-	-	-
				2	-	17.9	-	-	3.97	-	-	-	0.53	-	-	-
				3	-	17.6	-	-	2.74	-	-	-	0.32	-	-	-
				4	-	17.5	-	-	1.43	-	-	-	0.20	-	-	-
				5	-	17.6	-	-	1.87	-	-	-	0.22	-	-	-
				6	-	18.9	-	-	5.46	-	-	-	0.66	-	-	-
				7	-	17.9	-	-	3.48	-	-	-	0.42	-	-	-
				8	-	18.7	-	-	4.40	-	-	-	0.63	-	-	-
				9	-	19.9	-	-	4.83	-	-	-	0.77	-	-	-
				10	-	20.0	-	-	5.25	-	-	-	0.80	-	-	-
				11	-	17.0	-	-	3.53	-	-	-	0.32	-	-	-
				1	-	23.6	-	-	10.50	-	-	-	1.12	-	-	-
				2	-	22.1	-	-	5.81	-	-	-	0.75	-	-	-
				1	-		-	-	0.34	-	-	-	0.21	-	-	-
				3	-	21.4	-	-	3.79	-	-	-	0.51	-	-	-
				4	-	20.3	-	-	8.01	-	-	-	0.76	-	-	-
				5	-	20.6	-	-	8.67	-	-	-	0.83	-	-	-
				6	-	21.0	-	-	5.94	-	-	-	0.73	-	-	-
				7	-	21.0	-	-		-	-	-	0.81	-	-	-
				8	-	20.5	-	-	7.20	-	-	-	0.66	-	-	-
				9	-	21.8	-	-	5.01	-	-	-	0.75	-	-	-
				10	-	22.1	-	-	5.33	-	-	-	0.34	-	-	-
				11	-	20.5	-	-	2.93	-	-	-	1.04	-	-	-
				1	-	25.6	-	-	1.87	-	-	-	0.45	-	-	-
				2	-	24.1	-	-		-	-	-	0.77	-	-	-
				3	-	24.2	-	-	3.80	-	-	-	0.43	-	-	-
				4	-	24.0	-	-	0.96	-	-	-	0.06	-	-	-
				5	-	24.6	-	-	0.93	-	-	-	0.04	-	-	-
				6	-	24.6	-	-	14.77	-	-	-	1.04	-	-	-
				7	-	24.7	-	-	4.99	-	-	-	0.43	-	-	-
				8	-	24.8	-	-		-	-	-	1.90	-	-	-
				9	-		-	-		-	-	-	21.79	-	-	-
				10	-		-	-		-	-	-		-	-	-
				11	-		-	-		-	-	-		-	-	-
				1	-		-	-		-	-	-		-	-	-
				2	-		-	-		-	-	-		-	-	-
				3	-		-	-		-	-	-		-	-	-
				4	-		-	-		-	-	-		-	-	-
				5	-		-	-		-	-	-		-	-	-
				6	-		-	-		-	-	-		-	-	-
				7	-		-	-		-	-	-		-	-	-
				8	-		-	-		-	-	-		-	-	-
				9	-		-	-		-	-	-		-	-	-
				10	-		-	-		-	-	-		-	-	-
				11	-		-	-		-	-	-		-	-	-
				1	-		-	-		-	-	-		-	-	-
				2	-		-	-		-	-	-		-	-	-
				3	-		-	-		-	-	-		-	-	-
				4	-		-	-		-	-	-		-	-	-
				5	-		-	-		-	-	-		-	-	-
				6	-		-	-		-	-	-		-	-	-
				7	-		-	-		-	-	-		-	-	-
				8	-		-	-		-	-	-		-	-	-
				9	-		-	-		-	-	-		-	-	-
				10	-		-	-		-	-	-		-	-	-
				11	-		-	-		-	-	-		-	-	-
				1	-		-	-		-	-	-		-	-	-
				2	-		-	-		-	-	-		-	-	-
				3	-		-	-		-	-	-		-	-	-
				4	-		-	-		-	-	-		-	-	-
				5	-		-	-		-	-	-		-	-	-
				6	-		-	-		-	-	-		-	-	-
				7	-		-	-		-	-	-		-	-	-
				8	-		-	-		-	-	-		-	-	-
				9	-		-	-		-	-	-		-	-	-
				10	-		-	-		-	-	-		-	-	-
				11	-		-	-		-	-	-		-	-	-
				1	-		-	-		-	-	-		-	-	-
				2	-		-	-		-	-	-		-	-	-
				3	-		-	-		-	-	-		-	-	-
				4	-		-	-		-	-	-		-	-	-
				5	-		-	-		-	-	-		-	-	-
				6	-		-	-		-	-	-		-	-	-
				7	-		-	-		-	-	-		-	-	-
				8	-		-	-		-	-	-		-	-	-
				9	-		-	-		-	-	-		-	-	-
				10	-		-	-		-	-	-		-	-	-
				11	-		-	-		-	-	-		-	-	-
				1	-		-	-		-	-	-		-	-	-
				2	-		-	-		-	-	-		-	-	-
				3	-		-	-		-	-	-		-	-	-
				4	-		-	-		-	-	-		-	-	-
				5	-		-	-		-	-	-		-	-	-
				6	-		-	-		-	-	-		-	-	-
				7	-		-	-		-	-	-		-	-	-
				8	-		-	-		-	-	-		-	-	-
				9	-		-	-		-	-	-		-	-	-
				10	-		-	-		-	-	-		-	-	-
				11	-		-	-		-	-	-		-	-	-
				1	-		-	-		-	-	-		-	-	-
				2	-		-	-		-	-	-		-	-	-
				3	-		-	-		-	-	-		-	-	-
				4	-		-	-		-	-	-		-	-	-
				5	-		-	-		-	-	-		-	-	-
				6	-		-	-		-	-	-		-	-	-
				7	-		-	-		-	-	-		-	-	-
				8	-		-	-		-	-	-		-	-	-
				9	-		-	-		-	-	-		-	-	-
				10	-		-	-		-	-	-		-	-	-
				11	-		-	-		-	-	-		-	-	-
				1	-		-	-		-	-	-		-	-	-
				2	-		-	-		-	-	-		-	-	-
				3	-		-	-		-	-	-		-	-	-
				4	-		-	-		-	-	-		-	-	-
				5	-		-	-		-	-	-		-	-	-
				6	-		-	-		-	-	-		-	-	-
				7	-		-	-		-	-	-		-	-</	

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date	Location Monitoring point	Transparency (m)	SST (°C)	Salinity (mg/L)	DO (µM)	pH	DIN (µM)	NO3-N (µM)	NO2-N (µM)	NH4-N (µM)	DIP	PO4-P (µM)	SiO2-Si	SiO3-Si	Chl-a (µg/L)
Year	Month	day	Time	Area													
Japan	Saga Prefectural Ariake Fisheries Promotion Center	Ariake Sea	9	-	24.8	-	-	-	7.08	-	-	-	-	0.73	-	-	-
			10	-	25.5	-	-	-	11.03	-	-	-	-	1.39	-	-	-
			11	-	24.0	-	-	-	11.14	-	-	-	-	0.04	-	-	-
			1	-	30.7	-	-	-	0.74	-	-	-	-	1.47	-	-	-
			2	-	30.2	-	-	-	0.49	-	-	-	-	0.94	-	-	-
			3	-	29.6	-	-	-	0.78	-	-	-	-	0.34	-	-	-
			4	-	29.0	-	-	-	0.57	-	-	-	-	0.37	-	-	-
			5	-	29.7	-	-	-	0.71	-	-	-	-	0.50	-	-	-
			6	-	28.5	-	-	-	3.01	-	-	-	-	1.25	-	-	-
			7	-	29.2	-	-	-	0.67	-	-	-	-	0.95	-	-	-
			8	-	28.6	-	-	-	1.27	-	-	-	-	1.22	-	-	-
			9	-	29.5	-	-	-	0.61	-	-	-	-	1.65	-	-	-
			10	-	29.8	-	-	-	0.68	-	-	-	-	1.46	-	-	-
			11	-	28.7	-	-	-	0.65	-	-	-	-	0.38	-	-	-
			1	-	27.3	-	-	-	2.39	-	-	-	-	1.14	-	-	-
			2	-	27.0	-	-	-	2.52	-	-	-	-	0.96	-	-	-
			3	-	26.9	-	-	-	2.17	-	-	-	-	0.83	-	-	-
			4	-	26.7	-	-	-	5.13	-	-	-	-	1.08	-	-	-
			5	-	26.8	-	-	-	1.10	-	-	-	-	0.64	-	-	-
			6	-	27.4	-	-	-	13.41	-	-	-	-	2.09	-	-	-
			7	-	26.9	-	-	-	8.61	-	-	-	-	1.64	-	-	-
			8	-	27.3	-	-	-	12.96	-	-	-	-	2.11	-	-	-
			9	-	27.1	-	-	-	7.95	-	-	-	-	1.78	-	-	-
			10	-	27.2	-	-	-	5.30	-	-	-	-	1.57	-	-	-
			11	-	26.7	-	-	-	8.57	-	-	-	-	1.20	-	-	-
			1	-	24.8	-	-	-	11.05	-	-	-	-	2.35	-	-	-
			2	-	25.2	-	-	-	7.71	-	-	-	-	1.56	-	-	-
			5	-	25.2	-	-	-	6.87	-	-	-	-	1.31	-	-	-
			6	-	24.5	-	-	-	10.53	-	-	-	-	1.59	-	-	-
			7	-	24.5	-	-	-	8.17	-	-	-	-	1.36	-	-	-
			8	-	24.3	-	-	-	12.08	-	-	-	-	1.79	-	-	-
			9	-	24.3	-	-	-	12.16	-	-	-	-	1.91	-	-	-
			10	-	24.1	-	-	-	12.87	-	-	-	-	2.18	-	-	-
			1	-	20.6	-	-	-	23.58	-	-	-	-	2.20	-	-	-
			2	-	21.4	-	-	-	13.07	-	-	-	-	1.45	-	-	-
			3	-	22.1	-	-	-	11.08	-	-	-	-	1.27	-	-	-
			4	-	21.8	-	-	-	11.72	-	-	-	-	1.28	-	-	-
			5	-	21.6	-	-	-	12.53	-	-	-	-	1.39	-	-	-
			6	-	20.8	-	-	-	22.90	-	-	-	-	1.19	-	-	-
			7	-	20.9	-	-	-	19.06	-	-	-	-	1.90	-	-	-
			8	-	19.9	-	-	-	22.56	-	-	-	-	2.04	-	-	-
			9	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			10	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			11	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			12	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			13	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			14	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			15	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			16	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			17	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			18	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			19	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			20	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			21	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			22	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			23	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			24	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			25	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			26	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			27	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			28	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			29	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			30	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			31	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			1	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			2	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			3	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			4	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			5	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			6	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			7	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			8	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			9	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			10	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			11	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			12	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			13	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			14	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			15	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			16	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			17	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			18	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			19	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			20	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			21	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			22	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			23	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			24	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			25	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			26	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			27	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			28	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			29	-	-	-	-	-	-	-	-	-	-	-	-	-	-
			30	-	-	-	-	-	-	-	-	-	-	-	-	-	-

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date	Location	Monitoring point	Transparency (m)	SST (°C)	Salinity (mg/L)	DO (mg/L)	pH	DIN (μM)	NO3-N (μM)	NO2-N (μM)	DIP (μM)	PO4-P (μM)	SiO2-Si (μM)	SiO3-Si (μM)	Chl-a (μg/L)
Year	Month	day	Time	Area													
Japan	Saga Prefectural Fisheries Promotion Center	2009	2	24	Ariake Sea	9	-	20.6	-	-	22.66	-	-	-	2.13	-	-
						10	-	20.8	-	-	21.27	-	-	-	2.15	-	-
						11	-	22.0	-	-	21.27	-	-	-	1.15	-	-
						1	-	13.4	-	-	17.82	-	-	-	1.85	-	-
						2	-	14.7	-	-	14.72	-	-	-	1.54	-	-
						3	-	16.6	-	-	11.92	-	-	-	1.20	-	-
						4	-	16.3	-	-	12.91	-	-	-	1.34	-	-
						5	-	15.7	-	-	15.25	-	-	-	1.45	-	-
						6	-	14.6	-	-	18.72	-	-	-	1.71	-	-
						7	-	15.3	-	-	16.88	-	-	-	1.65	-	-
						8	-	14.5	-	-	20.49	-	-	-	1.80	-	-
						9	-	14.2	-	-	20.15	-	-	-	1.90	-	-
2008	Prefectural Fisheries Promotion Center	11	27			10	-	13.8	-	-	19.85	-	-	-	1.84	-	-
						11	-	17.1	-	-	11.48	-	-	-	1.15	-	-
						1	-	10.3	-	-	25.08	-	-	-	1.67	-	-
						2	-	10.0	-	-	22.61	-	-	-	1.55	-	-
						3	-	12.6	-	-	13.89	-	-	-	1.27	-	-
						4	-	12.1	-	-	14.92	-	-	-	1.33	-	-
						5	-	10.6	-	-	17.66	-	-	-	1.42	-	-
						6	-	12.0	-	-	20.66	-	-	-	1.45	-	-
						7	-	10.9	-	-	32.07	-	-	-	1.75	-	-
						8	-	11.1	-	-	24.69	-	-	-	1.68	-	-
						9	-	10.8	-	-	23.95	-	-	-	1.64	-	-
						10	-	10.4	-	-	24.47	-	-	-	1.82	-	-
2009		12	25			1	-	8.5	-	-	5.23	-	-	-	0.36	-	-
						2	-	9.6	-	-	2.06	-	-	-	0.41	-	-
						3	-	10.5	-	-	6.33	-	-	-	0.69	-	-
						4	-	10.2	-	-	5.77	-	-	-	0.66	-	-
						5	-	9.5	-	-	5.25	-	-	-	0.61	-	-
						6	-	8.9	-	-	16.03	-	-	-	1.06	-	-
						7	-	9.4	-	-	7.15	-	-	-	0.82	-	-
						8	-	8.7	-	-	9.80	-	-	-	1.05	-	-
						9	-	8.4	-	-	8.28	-	-	-	1.07	-	-
						10	-	8.4	-	-	6.52	-	-	-	0.96	-	-
						11	-	11.1	-	-	7.80	-	-	-	0.79	-	-
2009		1	27			1	-	8.5	-	-	2.06	-	-	-	0.41	-	-
						2	-	9.6	-	-	6.33	-	-	-	0.69	-	-
						3	-	10.5	-	-	5.77	-	-	-	0.66	-	-
						4	-	10.2	-	-	5.25	-	-	-	0.61	-	-
						5	-	9.5	-	-	16.03	-	-	-	1.06	-	-
						6	-	8.9	-	-	7.15	-	-	-	0.82	-	-
						7	-	9.4	-	-	9.80	-	-	-	1.05	-	-
						8	-	8.7	-	-	8.28	-	-	-	1.07	-	-
						9	-	8.4	-	-	6.52	-	-	-	0.96	-	-
						10	-	8.4	-	-	7.80	-	-	-	0.79	-	-
						11	-	11.1	-	-	2.47	-	-	-	0.07	-	-
2009		2	24			1	-	11.0	-	-	2.39	-	-	-	0.18	-	-
						2	-	11.0	-	-	0.42	-	-	-	0.06	-	-
						3	-	11.0	-	-	0.53	-	-	-	0.13	-	-
						4	-	11.3	-	-	0.59	-	-	-	0.05	-	-
						5	-	11.0	-	-	5.81	-	-	-	0.43	-	-
						6	-	11.3	-	-	6.69	-	-	-	0.46	-	-
						7	-	11.2	-	-	4.39	-	-	-	0.40	-	-
						8	-	10.9	-	-	9.10	-	-	-	0.59	-	-
						9	-	11.0	-	-	6.30	-	-	-	1.65	-	-
						10	-	10.8	-	-	0.45	-	-	-	0.13	-	-
						11	-	11.5	-	-	-	-	-	-	-	-	-

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date			Location	Transparency (m)	SST (°C)	Salinity	DO (mg/L)	pH	DIN (µM)	NO3-N (µM)	NO2-N (µM)	NH4-N (µM)	DIP (µM)	PO4-P (µM)	SiO2-Si (µM)	SiO3-Si (µM)	Chl-a (µg/L)
		Year	Month	day															
Japan	Nagasaki Prefectural Institute of Fisheries	2008	8	6	11:04	8.4	28.8	32.3	4.37	-	0.50	0.06	0.05	0.38	-	0.04	-	0.90	
			6	12:27	3	5.5	28.8	32.5	4.23	-	0.29	0.00	0.01	0.28	-	0.07	-	1.37	
			13:22	Imari Bay	4	8.0	29.7	32.4	4.17	-	0.43	0.07	0.06	0.31	-	0.07	-	0.78	
			10:59		1	5.2	25.5	32.3	5.00	-	1.17	0.12	0.00	1.05	-	0.06	-	2.71	
			9	2	12:23	3	4.3	31.6	5.06	-	1.13	0.08	0.00	1.05	-	0.04	-	2.16	
			13:16		4	2.8	26.8	30.3	5.04	-	1.18	0.08	0.00	1.11	-	0.06	-	6.04	
		2009	14:44		b	4.0	29.7	30.4	4.94	-	0.66	0.10	0.09	0.47	-	0.03	-	0.82	
			14:05		c	2.8	30.2	30.0	4.95	-	2.13	1.44	0.07	0.62	-	0.04	-	2.24	
			7	15	12:54	P	4.5	28.8	30.5	4.69	-	0.95	0.17	0.06	0.72	-	0.03	-	0.78
			11:29		Z	3.5	28.1	30.4	4.97	-	1.02	0.12	0.07	0.83	-	0.03	-	3.76	
			9:54	Omura Bay	b	4.5	27.5	31.1	3.85	-	2.21	0.15	0.00	2.05	-	0.05	-	4.50	
			10:35		c	4.3	28.3	31.0	4.07	-	1.85	0.16	0.00	1.69	-	0.13	-	4.56	
		2010	9	4	11:46	P	5.7	27.6	31.3	4.16	-	1.67	0.15	0.00	1.52	-	0.05	-	2.80
			13:11		Z	4.8	27.8	31.4	4.42	-	1.80	0.18	0.00	1.62	-	0.04	-	3.08	

*1 Monitoring points are shown in the map of another sheet (map of monitoring sites)

*2 The range of each parameter means the value observed between 20-23 August

*3 The concentration of nutrient is standardized into common unit (µM)

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date	Location Monitoring point	Area	Transparency (m)	SST (°C)	Salinity (mg/L)	DO (mg/L)	pH	DIN (µM)	NO3-N (µM)	NO2-N (µM)	DIP (µM)	PO4-P (µM)	SiO2-Si (µM)	SiO3-Si (µM)	Chl-a (µg/L)		
Year	Month	day	Time																
Korea National Fisheries Research and Development Institute	Tongyeong	-	-	Tongyeong	3.0	20.5	33.4	6.69	8.06	-	1.50	0.43	4.21	1.71	-	6.50	-	9.30	
	Geseong-	4	5.0	21.6	33.5	6.72	8.08	-	1.29	0.07	1.36	2.65	-	5.36	-	2.30	-	4.00	
	Jaran Bay	5	3.0	23.0	25.9	6.04	7.96	-	0.79	0.07	4.07	1.90	-	19.5	-	1.90	-	3.48	
	-	6	5.0	22.8	33.5	5.57	7.95	-	0.79	0.07	1.29	2.03	-	14.8	-	5.30	-	3.00	
	Sachun	7	4.0	21.5	33.5	7.76	8.05	-	1.14	0.14	0.93	1.65	-	17.1	-	2.60	-	2.30	
	Jinju Bay	8	3.0	21.4	33.4	6.26	7.91	-	4.64	0.71	2.36	2.06	-	9.04	-	7.10	-	0.50	
	Tongyeong	9	3.0	23.6	33.3	7.56	7.94	-	1.14	0.14	2.21	2.03	-	7.43	-	3.40	-	3.40	
	Geseong-	10	16.0	20.7	33.5	7.65	8.12	-	1.07	0.21	1.57	1.58	-	14.4	-	2.20	-	2.20	
	Jaran Bay	11	5.0	20.7	33.7	7.73	8.08	-	1.14	1.07	1.14	1.87	-	1.44	-	1.44	-	1.44	
	-	12	5.0	33.7	6.66	8.12	-	1.86	0.36	2.43	-	10.64	-	2.36	-	14.0	-	15.3	
	Tongyeong	3	2.0	24.6	32.5	8.92	8.12	-	5.07	0.14	1.14	0.13	-	9.93	-	1.30	-	1.30	
2007	Geseong-	4	6.0	25.5	32.7	6.86	8.06	-	4.29	0.14	1.21	0.19	-	29.1	-	1.28	-	1.28	
	Jaran Bay	5	3.0	27.4	31.4	8.32	8.29	-	2.50	0.14	1.43	0.42	-	1.86	-	1.86	-	1.86	
	-	6	6.0	26.3	31.8	7.73	8.10	-	2.57	0.14	1.29	1.23	-	3.39	-	1.70	-	1.70	
	Sachun	7	3.0	24.1	32.3	8.39	8.11	-	3.86	0.29	1.29	0.23	-	4.96	-	2.70	-	2.70	
	Jinju Bay	8	3.0	25.7	31.1	8.10	8.27	-	8.84	0.50	1.43	0.23	-	0.68	-	0.70	-	0.70	
	-	9	2.0	26.3	31.1	7.23	8.27	-	4.71	0.14	1.43	0.00	-	4.50	-	0.30	-	0.30	
	Tongyeong	10	11.0	24.1	32.9	7.48	8.08	-	5.50	0.07	1.21	0.26	-	1.93	-	0.20	-	0.20	
	Geseong-	11	9.0	24.8	32.5	7.40	8.06	-	2.86	0.21	1.43	0.45	-	1.93	-	0.20	-	0.20	
	Jaran Bay	-	12	4.0	23.6	32.9	7.73	8.03	-	5.07	0.29	1.36	0.29	-	1.00	-	1.00	-	1.00
	-	13	3.0	22.7	32.8	7.77	8.01	-	2.71	0.07	0.71	0.32	-	0.54	-	12.6	-	12.6	
	Tongyeong	4	4.0	25.0	32.6	7.49	7.88	-	0.86	1.57	0.71	0.74	-	0.46	-	4.00	-	4.00	
	Geseong-	5	3.0	25.7	32.0	7.34	7.70	-	2.21	0.21	0.71	0.42	-	1.29	-	8.80	-	8.80	
	Jaran Bay	6	6.0	24.0	32.1	9.03	7.93	-	1.86	0.00	0.57	0.23	-	0.82	-	5.20	-	5.20	
2007	-	7	7	4.0	23.2	7.41	7.96	-	2.71	0.14	0.64	0.81	-	2.96	-	6.00	-	6.00	
	Sachun	8	2.5	24.5	32.3	7.10	7.80	-	2.36	0.14	0.50	1.06	-	1.14	-	2.40	-	2.40	
	Jinju Bay	9	3.0	26.1	31.3	7.52	8.00	-	2.86	0.79	0.86	2.00	-	1.68	-	4.30	-	4.30	
	-	10	4.0	23.7	32.5	6.95	8.08	-	8.57	0.93	0.57	0.61	-	1.79	-	2.60	-	2.60	
	Tongyeong	11	5.0	24.1	32.6	8.10	7.97	-	3.00	0.00	0.43	0.29	-	0.54	-	2.20	-	2.20	
	Geseong-	12	4.0	23.1	33.0	8.30	8.10	-	2.71	0.57	1.07	0.52	-	0.71	-	5.00	-	5.00	
	Jaran Bay	3	1.8	24.6	30.0	8.31	8.12	-	2.36	0.57	0.43	0.87	-	0.86	-	23.9	-	23.9	
	Tongyeong	4	4.0	24.8	30.9	6.60	8.06	-	2.43	0.21	0.71	0.23	-	0.64	-	7.80	-	7.80	
	Geseong-	5	1.5	24.8	30.7	7.91	8.19	-	0.57	0.13	0.71	0.16	-	6.36	-	4.90	-	4.90	
	Jaran Bay	6	5.0	24.8	30.8	7.17	8.08	-	0.43	0.57	1.43	0.32	-	12.1	-	2.40	-	2.40	
	-	7	2.0	24.2	30.0	6.29	8.00	-	5.36	1.14	1.16	-	26.6	-	4.90	-	4.90		
	Sachun	8	1.2	24.2	26.6	6.52	8.00	-	22.00	2.21	2.14	1.13	-	49.6	-	8.20	-	8.20	
	Jinju Bay	9	1.0	24.8	21.2	8.50	8.69	-	1.93	1.07	0.86	0.84	-	34.5	-	42.0	-	42.0	
	-	10	6.5	24.8	30.5	6.16	8.15	-	0.57	0.64	0.86	0.16	-	8.36	-	4.00	-	4.00	
	Tongyeong	11	4.0	24.8	30.9	7.77	8.00	-	0.43	0.79	1.21	0.42	-	14.1	-	6.80	-	6.80	
	off shore	12	3.0	24.4	30.5	8.10	8.11	-	0.71	1.29	0.71	0.16	-	12.0	-	16.3	-	16.3	

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date	Location	SST (°C)	Salinity (mg/L)	DO (mg/L)	pH	DIN (µM)	NO3-N (µM)	NO2-N (µM)	DIP (µM)	PO4-P (µM)	SiO2-Si (µM)	SiO3-Si (µM)	Chl-a (µg/L)					
Year	Month	Day	Time	Area	Monitoring point	Transparency (m)														
Korea	National Fisheries Research and Development Institute	2008	-	Tongyeong	3	2.0	24.4	32.9	-	8.16	-	1.07	0.36	3.50	0.58	-	5.82	-	9.0	
			-	Geseong-Jean Bay	4	3.5	30.1	33.7	-	8.03	-	2.93	0.29	3.43	0.35	-	11.43	-	1.3	
			-	Sachun	5	3.5	28.7	32.6	-	7.94	-	2.64	0.36	3.14	1.13	-	28.2	-	1.7	
			-	Jinju Bay	6	7.0	28.2	32.6	-	8.07	-	3.71	0.43	2.93	0.16	-	10.4	-	0.3	
		8	-	Tongyeong off shore	7	5.0	25.5	32.8	-	8.15	-	1.57	0.50	0.57	0.39	-	9.9	-	1.2	
			-	Jinju Bay	8	3.5	25.5	32.8	-	8.15	-	3.07	0.50	4.21	0.16	-	4.1	-	2.1	
			-	Tongyeong off shore	9	4.0	29.3	31.8	-	8.12	-	2.86	0.50	4.21	0.71	-	3.89	-	0.8	
			-	Tongyeong off shore	10	10.0	24.7	33.0	-	8.20	-	3.00	0.43	1.50	0.39	-	7.89	-	0.0	
		9	-	Tongyeong off shore	11	9.0	25.6	32.8	-	8.13	-	0.64	0.57	1.00	0.58	-	10.5	-	0.3	
			-	Jinju Bay	12	3.5	22.3	33.4	-	8.02	-	0.93	0.50	3.36	0.32	-	3.57	-	2.5	
			-	Tongyeong off shore	3	2.0	23.7	35.4	7.97	7.99	-	0.57	0.14	0.43	0.35	-	9.61	-	4.6	
			-	Geseong-Jean Bay	4	5.5	29.3	33.1	8.97	8.09	-	0.93	0.36	1.43	1.06	-	3.07	-	1.6	
		2009	-	Sachun	5	3.0	27.8	33.4	7.98	7.92	-	0.86	0.57	1.50	1.29	-	35.6	-	2.8	
			-	Jinju Bay	6	5.0	28.0	33.0	7.34	8.02	-	0.79	0.57	1.93	0.74	-	15.43	-	1.1	
			-	Tongyeong off shore	7	5.0	22.3	33.3	8.20	8.16	-	1.43	0.36	2.14	0.39	-	7.21	-	2.5	
			-	Jinju Bay	8	2.0	25.1	32.8	8.81	7.95	-	1.14	0.71	1.07	0.71	-	12.04	-	5.0	
		8	-	Tongyeong off shore	9	2.0	26.3	32.8	9.21	8.04	-	0.86	0.57	0.79	0.16	-	3.57	-	3.8	
			-	Tongyeong off shore	10	5.0	23.6	33.2	8.65	8.21	-	0.36	0.36	1.21	0.29	-	6.21	-	1.0	
			-	Tongyeong off shore	11	4.0	23.5	33.3	8.05	7.66	-	0.14	0.29	1.93	0.74	-	11.71	-	2.0	
			-	Tongyeong off shore	12	3.0	21.6	33.8	7.71	8.03	-	1.64	0.57	1.36	0.71	-	4.46	-	3.8	
		9	-	Tongyeong off shore	3	2.5	25.5	32.1	-	8.13	-	1.71	0.21	0.79	0.23	-	3.89	-	5.3	
			-	Tongyeong off shore	4	2.0	26.7	32.8	-	7.99	-	2.07	0.14	0.71	0.16	-	10.39	-	5.3	
			-	Geseong-Jean Bay	5	1.5	27.2	33.0	7.97	-	3.71	0.07	0.43	0.32	-	3.89	-	2.4		
			-	Sachun	6	5.0	26.4	32.2	-	8.07	-	2.43	0.14	0.57	0.00	-	2.86	-	1.1	
		10	-	Jinju Bay	8	2.0	27.0	32.5	-	8.13	-	2.64	0.29	0.50	0.16	-	2.29	-	1.2	
			-	Tongyeong off shore	9	2.0	26.5	32.4	-	8.08	-	3.07	0.14	0.71	0.10	-	1.71	-	4.5	
			-	Tongyeong off shore	11	11.0	25.0	31.9	8.16	-	3.21	0.14	0.57	0.23	-	1.25	-	2.3		
			-	Tongyeong off shore	12	5.0	24.9	32.3	8.14	-	2.50	0.07	0.86	0.09	-	6.14	-	0.2		
		7	-	Tongyeong off shore	1	7	8.0	21.1	32.5	-	8.16	-	2.36	0.14	0.57	0.10	-	2.14	-	2.9
			-	Namhae	10	4.0	22.5	26.8	-	3.07	25.21	0.57	4.29	0.55	-	28.82	-	2.2		
			-	Yeosu	3	0.9	20.7	33.0	-	6.86	5.86	0.21	1.36	0.71	-	4.07	-	3.5		
			-	Tongyeong off shore	5	10.0	24.5	30.6	-	16.86	14.64	0.57	1.64	0.81	-	18.07	-	1.7		
		8	-	Namhae	7	9.0	24.2	30.5	-	4.14	2.00	0.07	0.71	0.10	-	7.29	-	1.4		
			-	Yeosu	3	2.0	24.7	31.7	-	6.93	5.07	0.14	1.71	0.13	-	4.21	-	3.4		
			-	Tongyeong off shore	9	2.5	24.9	31.5	-	6.79	5.43	0.21	1.21	0.13	-	4.00	-	3.4		
			-	Yeosu	6	2.5	24.9	31.5	-	-	-	-	-	-	-	-	-	-		

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date			Location		Transparency	SST	Salinity	DO	pH	DIN	NO3-N	NO2-N	NH4-N	DIP	PO4-P	SiO2-Si	SiO3-Si	Chl-a
		Year	Month	day	Time	Area														
Russia	Institute of Marine Biology FEB RAS Center of Monitoring of HABs & Biotoxins Institute of Marine Biology FEB RAS	2001	8	16	-	Vostok Bay	-	-	22.4	28.6	-	-	-	-	-	-	-	-	-	
		2001	9	30	-	Vostok Bay	-	-	14.7	33.6	-	-	-	-	-	-	-	-	-	
		2002	7	14	-	Vostok Bay	-	-	16.4	32.1	-	-	-	-	-	-	-	-	-	
		2003	4	23	-	Vostok Bay	-	-	6.2	33.4	-	-	-	-	-	-	-	-	-	
		2003	6	30	-	Vostok Bay	-	-	17.5	33.2	-	-	-	-	-	-	-	-	-	
		2004	8	1	-	Vostok Bay	-	-	23.2	28.5	-	-	-	-	-	-	-	-	-	
		2005	9	1	-	Vostok Bay	-	-	20.3	-	-	-	-	-	-	-	-	-	-	
		2005	11	1	-	Vostok Bay	-	-	3.0	32.6	-	-	-	-	-	-	-	-	-	
		2006	8	4	-	Vostok Bay	-	-	22.6	-	-	-	-	-	-	-	-	-	-	
		2006	6	30	-	Vostok Bay	-	-	22.6	30.6	-	-	-	-	-	-	-	-	-	
		2007	7	11	-	Amurskii	4.67	18.0	-	-	-	-	-	-	-	-	-	-	-	
		2007	25	-	-	Amurskii	3.67	22.0	-	-	-	-	-	-	-	-	-	-	-	
		2007	8	6	-	Amurskii	3.33	26.0	-	-	-	-	-	-	-	-	-	-	-	
		2007	20	-	-	Amurskii	2.50	23.2	-	-	-	-	-	-	-	-	-	-	-	
		2007	9	5	-	Amurskii	8.54	22.0	-	-	-	-	-	-	-	-	-	-	-	
		2007	17	-	-	Amurskii	2.54	20.0	-	-	-	-	-	-	-	-	-	-	-	
		2007	10	3	-	Amurskii	1.79	17.0	-	-	-	-	-	-	-	-	-	-	-	
		2007	17	-	-	Amurskii	5.04	12.0	-	-	-	-	-	-	-	-	-	-	-	
		2007	30	-	-	Amurskii	2.33	6.5	-	-	-	-	-	-	-	-	-	-	-	
		2008	11	9	-	Amurskii	0.62	6.8	-	-	-	-	-	-	-	-	-	-	-	
		2008	23	-	-	Amurskii	4.87	-1.7	-	-	-	-	-	-	-	-	-	-	-	
		2008	12	4	-	Amurskii	7.79	-1.7	-	-	-	-	-	-	-	-	-	-	-	
		2008	19	-	-	Amurskii	7.74	-1.7	-	-	-	-	-	-	-	-	-	-	-	
		2008	1	4	-	Amurskii	0.73	-1.7	-	-	-	-	-	-	-	-	-	-	-	
		2008	22	-	-	Amurskii	0.59	-1.8	-	-	-	-	-	-	-	-	-	-	-	
		2008	6	-	-	Amurskii	0.65	-1.8	-	-	-	-	-	-	-	-	-	-	-	
		2008	20	-	-	Amurskii	0.50	-1.8	-	-	-	-	-	-	-	-	-	-	-	
		2008	3	4	-	Amurskii	0.73	-1.8	-	-	-	-	-	-	-	-	-	-	-	
		2008	21	-	-	Amurskii	0.96	0.5	-	-	-	-	-	-	-	-	-	-	-	
		2008	4	7	-	Amurskii	2.17	5.5	-	-	-	-	-	-	-	-	-	-	-	
		2008	5	5	-	Amurskii	4.39	9.0	-	-	-	-	-	-	-	-	-	-	-	
		2008	6	7	-	Amurskii	3.39	16.2	-	-	-	-	-	-	-	-	-	-	-	
		2008	26	-	-	Amurskii	10.20	17.8	-	-	-	-	-	-	-	-	-	-	-	
		2008	7	17	-	Amurskii	2.48	23.2	-	-	-	-	-	-	-	-	-	-	-	
		2008	7	28	-	Amurskii	2.96	23.5	-	-	-	-	-	-	-	-	-	-	-	
		2008	8	11	-	Amurskii	4.32	22.7	-	-	-	-	-	-	-	-	-	-	-	
		2008	8	29	-	Amurskii	4.54	20.5	-	-	-	-	-	-	-	-	-	-	-	
		2008	9	15	-	Amurskii	3.35	20.9	-	-	-	-	-	-	-	-	-	-	-	
		2008	9	29	-	Amurskii	2.04	15.2	-	-	-	-	-	-	-	-	-	-	-	
		2008	10	13	-	Amurskii	3.31	12.9	-	-	-	-	-	-	-	-	-	-	-	
		2008	11	5	-	Amurskii	1.23	7.0	-	-	-	-	-	-	-	-	-	-	-	
		2008	11	20	-	Amurskii	1.82	-1.0	-	-	-	-	-	-	-	-	-	-	-	
		2008	12	3	-	Amurskii	3.50	0.0	-	-	-	-	-	-	-	-	-	-	-	
		2008	12	19	-	Amurskii	1.54	-1.6	-	-	-	-	-	-	-	-	-	-	-	

Annex II-3 Water Quality Information (Continued)

Country	Organization	Monitoring date			Location Monitoring point	Transparency	SST	Salinity	DO	pH	DIN	NO ₂ -N	NO ₃ -N	NH ₄ -N	DIP	PO ₄ -P	SiO ₂ -Si	SiO ₃ -Si	Chl-a
		Year	Month	day															
Russia	Institute of Marine Biology FEB RAS	1	11	-	Amurskii	1.18	-1.8	33.3	-	-	-	-	-	-	-	-	-	-	-
		3	12	-	Amurskii	1.09	0.5	33.1	-	-	-	-	-	-	-	-	-	-	-
		6	8	-	Amurskii	-	14.1	30.0	-	-	-	-	-	-	-	-	-	-	-
		8	2	-	Amurskii	-	23.0	20.0	-	-	-	-	-	-	-	-	-	-	-
		9	9	-	Amurskii	-	19.0	25.0	-	-	-	-	-	-	-	-	-	-	-
	Center of Monitoring of HABs & Biotoxins Institute of Marine Biology FEB RA	10	26	-	Amurskii	0.55	10.5	30.6	-	-	0.01	0.06	-	-	-	0.25	18.86	-	1.2
		7	4	-	Vostočnaya Bay	-	15.4	28.3	-	-	-	-	-	-	-	-	-	-	-
		9	1	-	Vostočnaya Bay	-	16.2	24.5	-	-	-	-	-	-	-	-	-	-	-
	Institute of Marine Biology FEB RA	1	28	-	Amurskii	1.00	-1.8	33.0	-	-	0.14	0.02	-	-	-	0.24	7.47	-	-
		3	30	-	Amurskii	2.17	-1.0	30.6	-	-	9.36	0.26	-	-	-	0.11	4.98	-	-
		7	30	-	Amurskii	2.00	23.0	22.6	-	-	0.16	0.02	-	-	-	0.09	25.62	-	-
	Institute of Marine Biology FEB RA	8	31	-	Amurskii	1.20	24.0	27.7	-	-	0.55	0.04	-	-	-	0.29	14.23	-	-
		9	30	-	Amurskii	2.00	16.0	30.1	-	-	0.56	0.03	-	-	-	0.80	28.11	-	-

*1 Monitoring points are shown in the map of another sheet (map of monitoring sites)

*2 The range of each parameter means the value observed between 20-23 August

*3 The concentration of nutrient is standardized into common unit (μM)



Integrated Report on Harmful Algal Blooms
for the NOWPAP Region

NOWPAP CEARAC